Appendix D1
Arborist Report - Tallaght to City Centre

BusConnects Infrastructure Dublin, Greenhills to City Centre

Arboricultural Impact Assessment Report

National Transport Authority

Project number: 60599126

November 2022

Table of Contents

1. Introduction 6
1.1 Background 6
1.2 Methodology 6
1.3 General Considerations 6
1.3.1 Soils 6
1.3.2 Trees and Risk in the Context of Development 6
1.3.3 Trees and Wildlife 7
1.3.4 Tree Works 7
2. Initial Tree Survey Overview 7
2.1 The Site 7
2.2 The Trees 9
2.3 Statutory and Non-Statutory Designations 9
3. The Proposed Development 11
4. Arboricultural Impact Assessment 12
4.1 Purpose 12
4.2 Trees to be Removed 13
4.3 Tree Works 13
4.4 Incursions within the RPA or Canopy Spread 13
4.5 The Future Management of Retained Trees 14
4.6 Tree Protection 15
4.7 Tree Planting 15
5. Conclusions 16
References 16
Appendix A Tree Survey Schedule 17
Key to Abbreviations Used in the Survey 92
Appendix B Tree Clearance Plans 94
Appendix C Arboricultural Method Statement 95
C.1 Arboricultural Method Statement Overview 95
C.2 Pre commencement site meeting 95
C.3 Order of operations 95
C.4 Preliminary tree works 95
C.5 Site briefing 96
C.6 Site monitoring 96
C.7 Toolbox Talk 96
C.8 Protective fencing 96
C.9 Ground protection 98
C.10 Carriageway widening into footways or verges 98
C.11 Footway or verge widening into existing carriageway 98
C.12 Removal and/or replacement of an existing hard surface within an RPA 98
C.13 Installation of new hard surfacing within RPAs 100
C.14 Demolition 101
C.15 Construction of New Boundary Walls 101
C.16 Installation of Piles 101
C.17 Movement of Vehicles and People and the Movement and Operation of Machinery 102
C.18 Site organisation, storage and mixing of materials 102
C.19 General principles for the management of tree roots 102
C.20 Installation of new lamp columns, road signs and bus shelters 102
C.21 Installation of new drainage within RPAs 103
C.22 Installation or diversion of utilities within RPAs 103
C.23 Redundant utilities 104

C.24 Dismantling of tree protection measures 104
C.25 Contact details 104
Appendix D Site Monitoring Form (Example) 105

Figures

Figure 1 BusConnects CBC Route 9, Greenhills to City Centre southern section 8
Figure 2 BusConnects Route 9, Greenhills to City Centre Northern Section 9
Figure 3 Default specification for tree protection barrier in accordance with BS5837:2012 figure 2. 97

Tables

Table 1: Summary of removals, Incursions and Pruning of Individual Trees to Facilitate the Proposed Development 12
Table 2: Summary of Removals, Incursions and Pruning of Tree Groups to Facilitate the Proposed Development 12

1. Introduction

1.1 Background

AECOM has been instructed by the National Transport Authority (The Applicant) to carry out an Arboricultural Impact Assessment of the development proposals for the BusConnects Infrastructure project on the Greenhills to City Centre Core Bus Corridor (CBC) (hereafter referred to as 'the Site' and 'Proposed Development) in support of a planning application. This report identifies the likely direct and indirect impacts of the Proposed Development along with suitable mitigation measures, as appropriate. The Tree Clearance Plan (included within Appendix B) identifies trees to be removed and how retained trees are to be successfully protected.

AECOM commissioned the initial preliminary tree survey and report the information from which has informed the following Arboricultural Impact Assessment. This tree survey and report is based on the requirements of BS5837:2012 Trees in relation to design demolition and construction – Recommendations (BS5837) and was prepared by Dr Philip Blackstock (dated 26/09/20 (updated 02/12/20)).

1.2 Methodology

The tree survey has been based on the topographical survey plan provided, (Ref: Route 9 (Greenhills): BCIDA-ACM-SUR_SV-0009_XX_00-M2-GG-0001

Where tree positions were not included on the topographical survey they have been plotted indicatively and marked with an '*'. All such positions must be considered to be indicative only.

Some areas of the scheme were outside the original tree survey extents, and no tree survey data is currently available for these areas. In these circumstances, trees have been plotted indicatively based on aerial imagery and/or topographical survey data and recorded as 'un-surveyed/uncategorised tree' features. Where such features are likely to be significantly impacted by the scheme, new tree survey data will be obtained in due course.

The survey was otherwise conducted in accordance with the requirements of BS5837:2012 Trees in relation to design, demolition and construction – Recommendations (BS5837).

Dr Blackstock undertook the tree survey data collection and verification. AECOM have adopted the tree survey data provided by Dr Blackstock and carried out a desk-based review of the proposed development and the likely impact on trees.

1.3 General Considerations

1.3.1 Soils

On shrinkable clay soil, tree growth can lead to the differential movement of structures as moisture is removed from the soil during the growing season. Soils must be carefully assessed, and any foundations that could be influenced by trees must be installed following the recommendations of National House Building Council (NHBC) Standards *Chapter 4.2: Building Near Trees* (2020) to avoid potential future damage. Where trees which predate existing structures are to be removed, this can result in heave as the soils are re-wet.

The advice of a suitably qualified engineer must be obtained to inform any potential issue of heave. Specific advice in relation to this issue is beyond the scope of this report.

1.3.2 Trees and Risk in the Context of Development

Tree owners/managers have a legal duty to prevent foreseeable harm. It is generally accepted that this duty can be fulfilled by undertaking proactive inspections of significant trees to identify obvious defects and by taking appropriate remedial action or gaining further advice as appropriate.

Further guidance is available from the National Tree Safety Group[1].

[1] National Tree Safety Group (NTSG),2011. Common sense risk management of trees. Forestry Commission.

The tree survey carried out by Dr Blackstock as the basis of this report is primarily for planning purposes, focusing on the quality and benefits of the trees and is not specifically designed to assess the safety of trees on Site. However, when obvious issues have been identified recommendations have been included in the Tree Survey Schedule.

Developers and contractors have responsibilities for health and safety as a result of their actions. Should trees be left in an unstable or hazardous condition those responsible could be subject to prosecution along with the potential for further Civil claims for damages.

1.3.3 Trees and Wildlife

Full consideration must be given to the presence of species protected under the Wildlife Act (1976 – as amended) and other relevant legislation protected wildlife and habitats, in particular the presence of bats and nesting birds. It is recommended that wherever possible, significant tree/hedge works take place outside of the typical bird nesting season of March to September. The advice of a qualified ecologist should be sought in relation to tree works with the potential to impact on protected species.

1.3.4 Tree Works

Any tree surgery recommendations contained within this report are to be undertaken in accordance with BS3998: 2010 Tree work – Recommendations (BS3998) by suitably qualified and insured contractors. Significant pruning works are best undertaken when trees are dormant or outside periods of high functional activity to reduce the overall impact on energy available to the tree for growth and processes. In general, the optimum period for works is between November to February and July to August (subject to the presence of protected species) when the tree is less active and better placed to respond to wounding and a reduction in leaf area.

2. Initial Tree Survey Overview

2.1 The Site

The Site, as shown in Figures 1 and 2 below, commences on Belgard Square West at the junction with Cookstown Way. Continuing along Belgard Square West into Belgard Square North and then Belgard Square East towards Old Blessington Road the Site continues along Ballymount Avenue, Calmount Road and Walkinstown Road as far as the junction with Long Mile Road. From here the Site extends along Drimnagh Road, Crumlin Road, Dolphin's Barn, Cork Street, St. Luke's Avenue, The Coombe, and Dean Street to the junction with Patrick Street. Turning into Patrick Street it continues into Nicholas Street up to the junction with Christchurch Place where the Site ends.



Figure 1 BusConnects CBC Route 9, Greenhills to City Centre southern section[2]

[2] https://busconnects.ie/media/2110/08-clondalkin-to-drimnagh-preferred-route-301020fa-web.pdf



Figure 2 BusConnects Route 9, Greenhills to City Centre Northern Section

The Site extends from modern development areas though mostly twentieth century suburbs into the historic heart of Dublin.

2.2 The Trees

A total of 752 tree features (i.e. individual trees and individual groups of trees) were included within Dr Blackstock's report; 38% of which were considered to be mature. Approximately 64% were categorised as Category B (moderate quality), approximately 34% as Category C (low quality), 1.6% were categorised as Category U (unsuitable for retention) and 0.3% were categorised as Category A (high quality).

Over 25% of the individual trees surveyed were identified as lime (*Tilia sp.*), with other frequently encountered species including Norway maple (*Acer platanoides*), sycamore (*Acer pseudoplatanus*), rowan (*Sorbus aucup*aria), ash (*Fraxinus excelsior*), birch (*Betula sp.*) and flowering cherry (*Prunus sp.*). Other, less frequent species noted include plane (*Platanus x hispanica*), Turkish hazel (*Corylus colurna*), Monterey cypress (*Cupressus macrocarpa*), cabbage palm (*Cordyline australis*), horse chestnut (*Aesculus hippocastanum*) and hornbeam (*Carpinus betulus*).

To the south west of the route trees are predominantly young street trees although as the route progresses north east there is generally very little in the way of formal street tree planting until the City Centre where significant tree planting is noted within central reservations along the road. The majority of the tree population is sporadically placed within industrial parks, front gardens and within the grounds of churches and the priory. Tree groups often provide screening of the road from adjacent land.

2.3 Statutory and Non-Statutory Designations

Dr Blackstock contacted Dublin City Council (DCC) and South Dublin County Council (SDCC) in relation to statutory designations affecting trees. Three Tree Preservation Orders (TPOs) are identified in the DCC Tree Strategy (2016-2020) document; although none of these are within or close to the Site.

No areas subject to Special Amenity Area Order designation have been identified within or close to the Site boundary, however this must be confirmed with the planning authority.

The Site incurs within or close to Architectural Conservation Areas such as at Tallaght and other Conservation Areas across its length. In these areas it is understood that trees are not given specific protection, but the contribution they make to the wider Conservation Area is taken into account as part of the planning process.

A felling licence may be required by the Forest Service to fell trees where an exception does not apply (full planning consent is an exception to this requirement where tree removal was specifically identified at the application stage).

The Data.gov.ie Ancient and Long-Established Woodland Inventory (2010) indicates ancient or long-established woodland well outside of the Site boundary with no potential to be impacted by the Proposed Development.

No veteran trees were identified during the survey.

3. The Proposed Development

The Proposed Development forms part of the National Transport Authority's (NTA) BusConnects programme which is a key element of the Governments' policies to improve bus and sustainable transport services within Dublin.

The Proposed Development constitutes the Greenhills to City Centre CBC and is broken down into specific sections within the Busconnects Preferred Route documentation[3] where more detail is available. A brief description of the main points within the Proposed Development are detailed below.

Belgard Square South to Greenhills Road

The existing roundabout junction Belgard Square South will be changed to a fully signalised junction with improved pedestrian facilities. A bus interchange is proposed at the start of the route and Belgard Square West will be closed to general traffic being a bus only route.

Signal Controlled Priority will be given to buses across Old Bessington Road.

The roundabout junction at the Tallaght Hospital entrance on Belgard Square North will be changed to a fully signalised junction including a new bus lane and pedestrian facilities and upgrading of the existing cycle facilities to provide segregated cycle routes to and from Tallaght Hospital.

A new junction is proposed on Old Greenhills Road to provide Signal Controlled Priority bus turning at the location of the existing cul de sac.

Greenhills Road to Walkinstown Roundabout

Between the Old Greenhills Road and the junction with Mayberry Road along the Greenhills Road and between the Calmount Road and Walkinstown Roundabout, the proposals include two-way bus, cycle and general traffic lanes which will require some land take thereby increasing the width of the existing road route.

Other changes include, the implementation of some local road network improvements between Mayberry Road and Tymon Lane as identified in the South Dublin County Council County Development Plan, the construction of a new link road (Greenhills Road) on land south of Birchview Avenue and Treepark Road and the construction of a second bridge over the M50.

New link roads are proposed at Keadeen Park, connecting to Ballymount Avenue, and between Calmount Road and Greenhills Road. The roundabout junction between Ballymount Avenue and Calmount Road will be upgraded to a signalised junction.

Walkinstown Roundabout to Dolphin Road

On Walkinstown Road, between Walkinstown Roundabout and the Long Mile Road, and on Drimnagh Road the road will include a bus, a cycle and a general traffic lane in each direction which will require some land take to achieve the proposed cross section.

It is proposed to introduce a right turn ban into Kilnamanagh Road and to the southern entrance of the Supervalu supermarket.

The upgrading of junctions along this section of the route are proposed to improve cycle facilities including the junction at Long Mile Road and Walkinstown Road. Amendments are also proposed to the parallel parking provision adjacent to the shop frontage on Long Mile Road.

Signal Controlled Priority for buses will be provided along a constrained section along Crumlin Road which will also include the closure of access to Clonard Road and Bangor Drive to facilitate traffic management. There is insufficient space to provide dedicated cycle lanes although cyclists will be redirected through Kildare Road the safety along which will be improved through the prevention of general through traffic.

Kerb alignment and pedestrian crossing improvements are proposed at the junction between Crumlin Road and Herberton Road.

[3] https://busconnects.ie/media/2186/09-greenhills-to-city-centre-preferred-route-221120fa-web.pdf

Between Herberton Road and Dolphin Road on the Crumlin Road there is insufficient space to provide dedicated cycle tracks to the road here will consist of one bus lane and one general traffic lane in both directions.

Dolphin Road to Christchurch Place

Between Dolphin Road and South Circular Road, South Circular Road and Ardee Street and between Dean Street Junction and Christchurch Place; a bus lane, a cycle lane and a general traffic lane are proposed in each direction. However, on Dean Street there is insufficient width for bus lanes, so bus priority will be achieved through Signal Controlled Priority.

The junctions at South Circular Road and Ardee Street will be upgraded with improved pedestrian facilities. The junction at Kevin Street/Dean Street will be improved to upgrade the cycle facilities and the junction at Christchurch Place/Winetavern Street/High Street will be realigned to improve pedestrian accessibility, its relationship to Peace Park and Christchurch Cathedral and to deflect traffic away from the City Centre towards High Street.

The Proposed Development is overlain onto the Tree Protection Plan (Appendix B).

4. Arboricultural Impact Assessment

4.1 Purpose

This impact assessment sets out the likely principal direct and indirect impacts of the Proposed Development on the trees on or immediately adjacent to the Site and suitable mitigation measures to allow for the successful retention of significant trees or to mitigate for trees to be removed, where appropriate.

A brief summary of trees to be removed, tree works and incursions related to the Proposed Development are detailed within the tables below.

Table 1: Summary of removals, Incursions and Pruning of Individual Trees to Facilitate the Proposed Development

Impact	Category A	Category B	Category C	Category U	Uncategorised tree features
Individual trees to be removed to facilitate the Proposed Development	1	109 individual trees	63 individual trees	13 individual trees	15 individual trees
Individual trees to be retained but subject to an RPA incursion	0	14 individual trees	7 individual trees	0	0
Individual trees to be pruned to facilitate the Proposed Development	0	0	0	0	0

Table 2: Summary of Removals, Incursions and Pruning of Tree Groups to Facilitate the Proposed Development

Impact	Category A	Category B	Category C	Category U	Uncategorised tree features
Tree groups to be removed to facilitate the Proposed Development	0	16 tree groups, 1 hedge, 1 shrub	16 tree groups, 9 hedges, 1 shrub	1 group	0
Tree groups to be retained but subject to an RPA incursion	0	5 tree groups	1 tree group	0	0
Tree groups to be pruned to facilitate the Proposed Development	0	0	0	0	0

4.2 Trees to be Removed

186 individual trees, 33 tree groups, ten hedges and two shrubs are to be removed to facilitate the Proposed Development; this includes 1 individual tree classed as high quality (Category A), 109 individual trees, 12 full tree groups, part of two tree groups, part of two woodland groups and one full hedge and one shrub classed as moderate quality (Category B) and the remaining 63 individual trees, eight full tree groups, part of eight tree groups, seven full hedges, two part hedges and one shrub classified as low quality (Category C).

In addition, 13 individual trees and one tree group of very low quality (Category U) are also recommended for removal. These trees are not suitable for long-term retention in the context of the current Site use and their removal is justified regardless of the Proposed Development.

15 individual uncategorised trees are also to be removed. These features were outside the scope of the original tree survey and were not subject to a formal tree survey. Categorisation and further assessment of these trees should be completed as part of the detailed design tree surveys.

Tree removals are listed in the Tree Survey Schedule included as Appendix A.

Many of the trees to be removed are within the existing road boundary and/or the red line application boundary for the Site. However, some trees are likely to be under third party ownership (indicated by the P suffix in the Tree Survey Schedule in Appendix A).

The design has been developed to minimise any negative impact on significant trees as fully as possible. Where tree loss is required it is necessary to achieve the proposals for the Site. The latest available information on the road layout, landscape general arrangement, drainage, structures, earthworks, lighting and compounds have been reviewed to inform this assessment.

Tree removals assume a reasonable worst case and in practice some trees may be feasible to retain subject to on site investigation such as trail holes to determine root spread in conjunction with the guidance of the Project Arboriculturist.

Where part of a group of trees is to be removed the Project Arboriculturist must carry out a site walkover immediately following site clearance work to determine the suitability and stability of retained trees which may have been impacted by a loss of companion shelter. Where any additional tree pruning or removals are required these will be discussed with the Project Arboriculturist.

Tree removals will be mitigated with a high-quality scheme of new tree planting and associated landscaping works as detailed in the proposed Landscape General Arrangement Plans.

4.3 Tree Works

Tree removals to facilitate the Proposed Development are detailed in the Tree Survey Schedule included as Appendix A. Aside from tree removals no other tree works such as tree pruning has been identified at this stage. Where new areas of access are proposed close to trees crown lifting to ensure a clear height of 2.5m for footways, 3m for cycleways and 5.2m for roads is likely to be required. The requirement for pruning should be addressed following a pre-commencement site walkover to review any trees which could form an obstruction, or which require pruning to facilitate construction works and to prevent inadvertent damage to tree crowns.

This level of pruning will generally not have a significant negative impact on the health or amenity of the trees in question.

No additional works to retained trees are likely to be required. All tree work is to follow the principles of *BS3998: 2010 Treework – Recommendations* and must be carried out by suitably qualified and insured contractors.

Should the requirement for additional tree works be identified, this will be discussed with the Project Arboriculturist.

4.4 Incursions within the RPA or Canopy Spread

The design has been developed to avoid the area of constraint around trees where feasible. A range of works are required within or close to the RPA of retained trees which will require specialist working methods to ensure trees are not significantly impacted. This will apply to T2, T3, T51, T52, T53, G69, G166, T189, T193, T194,

G196, T238, T239, T475, T478, T565, T597, W639, G685 which are Category B features and G167, T370, T570, T594, T596, T709, T724 and T725 which are Category C features.

The Arboricultural Method Statement included as Appendix C sets out the methodology for specific activities near retained trees. The following general principles have been applied:

- Where resurfacing of existing hard surfacing is required this will be applied over the existing wearing course or on the existing intact subbase following the careful removal of the wearing course.
- New surfacing on existing unsurfaced ground within a significant proportion of an RPA will be achieved using a three-dimensional cellular confinement system (e.g. Cellweb or equivalent) installed without excavation using no dig techniques. This applies to one individual tree and one tree group of low quality (G493 and T570) and one group of moderate quality (G685).
- Where existing verges or footways are to be widened out into the existing carriageway, kerb stones and haunching will be carefully removed by hand to protect adjacent tree roots, the amended scheme will likely result in improved growing conditions for trees where sections of carriageway are replaced by less heavily engineered footway or verge. This will apply to five moderate quality features (T189, T193, T194, G196 and T475) and three low quality features (T370, T724 and T725). In addition to this, existing areas of hard surfacing are to be converted to unsurfaced ground within the RPA of five moderate quality trees (T238, T239, T478 and T597) and two low quality trees (T594 and T596). The existing surface will be broken out carefully using hand tools with no excavation below the existing sub base. New high quality free draining top soil will be added to address ground levels. The ground level immediately around the tree stem base will not be increased, where necessary to address level differences this will be filled with washed gravel or sharp sand.
- Where the existing road is to be widened requiring a section of cut into a tree RPA or where new drainage cannot feasibly be adjusted to fully avoid the RPA, tree retention will be feasible where trees are considered on balance to be of an age, condition and species which will tolerate the degree of disturbance required (generally not more than a maximum of 20% of the overall RPA) and that this is preferable to the loss of the tree. The area of excavation nearest the tree will be carried out by hand and roots will be carefully assessed by the Project Arboriculturist and pruned as required. New kerb stones and any haunching will be the narrowest profile feasible, and alternative methodologies such as reinforced bridged/lintel sections of kerb can be applied should significant roots need to be retained and worked around. This will apply to G69 and W639 which are moderate quality features and T709 which is a low quality feature.
- The position of new lamp columns, signs and bus shelter footings can be locally adjusted to avoid significant roots and tree canopies and the lowest diameter footings feasible will be employed (such as screw piles or equivalent). This will apply to three moderate quality trees (T51, T52 and T53).
- All new or diverted utilities will avoid the RPA of retained trees where possible, where this is not possible, utilities will be installed using trenchless methods or via careful excavation in accordance with BS5837: 2012 and guidance from the National Joint Utilities Group (NJUG) Volume 4. Utilities to be removed will be cut off and left in situ where feasible to minimise disturbance or will be removed via careful excavation.

4.5 The Future Management of Retained Trees

Retained trees will require periodic inspection to assess their structural condition and safety. Occasional removal of dead wood or other remedial works to address significant defects or obstructions may be required in areas of frequent access. This is unlikely to be overly onerous and will be the responsibility of the tree owner.

Trees within and adjacent to the Site will require ongoing maintenance and assessment by a competent person to ensure that any risks from tree failure are managed in accordance with best practice.

All tree works recommended as a result of the preliminary tree survey of the Site which considered trees in the context of the current use of the Site (these works are included as preliminary management recommendations in the Tree Schedule in Appendix A of this report) should be actioned within the recommended timescales.

4.6 Tree Protection

Retained trees are vulnerable to damage from construction activities which can include physical damage to stems and branches following impacts with plant, root severance following trenching, root death or dysfunction following damage to soil structure (caused by the movement of people or machinery on unsurfaced ground) or via the spillage of materials toxic to tree health. The default position is that the RPA and canopy spread of trees to be retained will form an effective Construction Exclusion Zone, secured with robust fencing where no access will be permitted, in the context of the Site (road environment) this will typically apply where there is no existing hard surfacing in place or where existing hard surfacing is to be removed. Where access is necessary within these areas, special measures such as the use of ground protection (or retention of existing hard surfacing) and arboricultural supervision are required. In some cases, existing boundary walls and fences can be employed as a tree protection barrier where they are robust and sufficient to prevent access or damage.

Outline tree protection measures are considered in Appendix C of this report.

4.7 Tree Planting

Existing areas of unsurfaced ground must be protected during the demolition and construction phases if they are to be re-used for new plantings. Protection can be achieved using fit for purpose ground protection measures as set out in BS5837:2012 Section 6.2.3 or by creating a fenced exclusion zone. Where protection is not feasible, soil amelioration or replacement works will be required to ensure suitable growing conditions for new trees to fully establish.

Where new trees are to be planted, the minimum planting distances detailed in Annexe A, Table A.1 of BS5837:2012 must be considered, to prevent direct damage to services and structures from future tree growth.

New tree planting should be implemented in accordance with the guidance set out in BS8545: 2014 Trees: from nursery to establishment in the landscape – Recommendations.

5. Conclusions

186 individual trees, 33 tree groups, ten hedges and two shrubs are to be removed to facilitate the Proposed Development; this includes one individual tree classed as high quality (Category A), 109 individual trees, 12 full tree groups, part of two tree groups, part of two woodland groups and one full hedge and one shrub classed as moderate quality (Category B) and the remaining 63 individual trees, eight full tree groups, part of eight tree groups, seven full hedges, two part hedges and one shrub classified as low quality (Category C).

In addition, 13 individual trees and one tree group of very low quality (Category U) are also recommended for removal. These trees are not suitable for long-term retention in the context of the current Site use and their removal is justified regardless of the Proposed Development.

15 individual uncategorised trees are also to be removed. These features were outside the scope of the original tree survey and were not subject to a formal tree survey. Categorisation and further assessment of these trees should be completed as part of the detailed design tree surveys

The design has been developed to minimise the impact on trees, and trees are proposed to be retained where careful construction methodologies will allow their retention. Trees are to be removed due to a direct conflict with the Proposed Development and where specialist methodologies or design tweaks are not considered practical to facilitate their retention.

Tree loss will be mitigated with a robust and high-quality scheme of new tree planting as detailed in the proposed Landscape General Arrangement Plans.

Soil structure for areas of new tree planting where the ground is currently unsurfaced will either be protected using ground protection or fenced exclusion zones; or the soil structure will be ameliorated or replaced following the completion of construction works on Site.

References

British Standards Institution (BSI), BS5837:2012. Trees in relation to design, demolition and construction – Recommendations. BSI

British Standards Institution (BSI), BS3998:2010. Tree work – Recommendations. BSI

British Standards Institution (BSI) BS8545: 2014 Trees: from the nursery to independence in the landscape - Recommendations

National House Building Council (NHBC) Standards, (2021). Chapter 4.2: Building Near Trees

National Joint Utilities Group (NJUG) Volume 4, Issue 2, (2007). NJUG Guidelines for the Planning, Installation and Maintenance of Utility Apparatus in Proximity to Trees.

National Tree Safety Group (NTSG), 2011. Common sense risk management of trees. Forestry Commission.

Dublin City Council Tree Strategy 2016-2020 https://www.dublincity.ie/residential/parks/strategies-and-policies/tree-strategy#:~:text=The%20Tree%20Strategy%20seeks%20to,the%20management%20of%20public%20trees

Dublin City Council (2016) Dublin City Development Plan 2016-2022 Written Statement (2016)

Appendix A Tree Survey Schedule[4]

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-001	1	Hornbeam, Carpinus betulus	12	370	6	6	6	5	N-2	3	M	Multi stem from 2.0m	Fair	None	None	No action is required	40+	B1	4440		
T 09-002	2	Plane, Platanus X hispanica.	19	1030	8	8	6	8	S-4	2	M	Multi stem from 4.0m	Fair	None	Lamp, Path, Road, Buildings	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear back from building, Clear lamp	40+	B1	12360		
T 09-003	3	Plane, Platanus X hispanica.	18	980	6	7	7	6	E-4	2	M	Multi stem from 5.0m	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	40+	B1	11760		
S 09-004	4	Pittorsporum	9	250	4	3	3	4	N-1	2	M	Multi stem	Fair	None	Lamp, Path	Crown lift to 2.4m Over path Or lawn, Clear lamp	20+	B1	3000		
T 09-005	5	Whitebeam, Sorbus aria	13	450	5	4	6	5	E-2	2	M	2 stems from 2.0m	Fair	Narrow fork, Recent crown failure	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	5400		
G 09-006	6	Lime, Tilia sp.	4	150	2	2	2	2	E-2	2	Y	Single stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	1800	Fell in part for new hard surfacing	2
T 09-007	7	Lime, Tilia sp.	6	220	5	4	2	4	N-3	2	YM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2640		
T 09-008	8	Lime, Tilia sp.	9	270	4	5	4	4	S-3	3	YM	Multi stem from 5.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-009	9	Lime, Tilia sp.	9	280	5	5	4	5	S-3	3	YM	Multi stem from 4.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3360		

[4] Site survey information provided by Dr Philip Blackstock 26/09/20 (updated 02/12/20)

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0010	10	Lime, Tilia sp.	8	260	4	4	4	4	S-3	2	YM	Multi stem from 5.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3120		
T 09-0011	11	Lime, Tilia sp.	4	80	1	1	1	1	W-2	2	Y	0	Fair	None	None	No action is required	40+	C1	960		
T 09-0012	12	Lime, Tilia sp.	11	320	4	5	4	5	S-3	3	YM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3840		
T 09-0013	13	Lime, Tilia sp.	11	280	4	4	3	5	W-3	3	YM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3360		
T 09-0014	14	Lime, Tilia sp.	10	230	4	4	3	3	S-3	3	YM	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2760		
G 09-0015	15	Lime, Tilia sp.	5	80	1	1	1	1	E-2	2	Y	0	Fair	None	None	No action is required	40+	C1	960		
T 09-0016	16	Lime, Tilia sp.	11	290	4	5	3	4	W-3	3	YM	2 stems from 3.0m	Fair	Narrow fork	Road	Crown lift to 5.1m Over road Or field	40+	B1	3480		
T 09-0017	17	Lime, Tilia sp.	6	140	2	3	2	3	W-3	3	Y	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	1680		
T 09-0018	18	Lime, Tilia sp.	9	240	3	5	5	4	S-2	3	YM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2880		
T 09-0019	19	Lime, Tilia sp.	12	290	3	5	5	3	N-4	4	YM	Single stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3480		
T 09-0020	20	Lime, Tilia sp.	8	220	5	4	4	5	N-3	3	YM	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2640		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0021	21	Lime, Tilia sp.	12	300	4	5	4	5	S-4	3	YM	Multi stem from 4.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3600		
T 09-0022	22	Plane, Platanus X hispanica.	19	940	9	6	4	8	E-6	3	M	Spreading crown, Single stem to 6.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	11280		
T 09-0023	23	Plane, Platanus X hispanica.	20	850	5	7	4	8	W-4	3	M	3 stems from 4.0 m	Fair	None	Lamp, Path	Crown lift to 2.4m Over path Or lawn, Clear lamp	40+	B1	10200		
T 09-0024	24	Plane, Platanus X hispanica.	20	880	5	8	4	8	E-4	4	M	2 stems from 4.0m	Fair	None	Lamp	Clear lamp	40+	B1	10560		
T 09-0025	25	Lime, Tilia sp.	20	650	4	5	5	5	W-6	3	M	Single stem to 6.0m	Fair	Forming cavity	None	No action is required	20+	B1	7800		
T 09-0026	26	Plane, Platanus X hispanica.	21	980	7	8	5	7	N-3	2	M	Multi stem from 3.0m	Fair	None	None	No action is required	40+	B1	11760		
T 09-0027	27	Plane, Platanus X hispanica.	19	1080	7	7	5	7	N-5	4	M	Single stem to 6.0m	Fair	None	None	No action is required	40+	B1	12960		
T 09-0028	28	Lime, Tilia sp.	20	650	5	6	4	6	N-5	3	M	Single stem to 8.0m	Fair	Thinning crown	None	Crown clean	40+	B1	7800		
T 09-0029	29	Plane, Platanus X hispanica.	20	1270	5	9	7	8	E-2	3	M	2 stems from 2.0m	Fair	None	Lamp	Clear lamp	40+	B1	15240		
T 09-0030	30	Zelklova,	6	280	3	4	6	5	W-2	2	YM	3 stems from 2.0m	Fair	None	None	No action is required	40+	B1	3360		
T 09-0031	31	Flowering cherry, Prunus Sp	5	430	3	5	4	3	E-2	2	M	3 stems from 2.0m, Spreading crown	Fair	Thinning crown	None	Crown clean	20+	B1	5160		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-0032	32	Plane, Platanus X hispanica.	5	60	1	1	1	1	N-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	720		6
T 09-0033	33	Turkish hazel, Corylus colurna	4	80	1	1	1	1	W-2	2	Y	Single stem	Good	None	None	No action is required	40+	C1	960		
T 09-0034	34	Turkish hazel, Corylus colurna	5	90	2	2	1	1	E-2	2	Y	Single stem	Good	None	None	No action is required	40+	C1	1080		
T 09-0035	35	Turkish hazel, Corylus colurna	5	140	2	2	2	2	W-2	2	Y	Single stem	Good	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1680		
G 09-0036	36	Turkish hazel, Corylus colurna	6	140	2	2	2	2	E-2	2	Y	Single stem	Good	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	40+	C1	1680		
T 09-0037	37	Turkish hazel, Corylus colurna	5	110	2	2	2	2	W-2	2	Y	Single stem	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	40+	C1	1320		
G 09-0038	38	Plane, Platanus X hispanica.	5	70	1	1	1	1	W-2	2	Y	Single stem	Fair	Thinning crown	None	No action is required	40+	C1	840		
T 09-0039	39	Oriental Plane, Platanus orientalis	13	280	4	4	4	4	S-3	2	EM	Single stem	Fair	None	Path, Road, Buildings	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear back from building	40+	B1	3360		
S 09-0040	40	Buddleia oriental, Buddleia davidii	5	100	3	3	3	3	-3	2	M	Multi stem	Fair	None	Path, Wall or fence	Crown lift to 2.4m Over path Or lawn, Clear back from wall or fence	10+	C1	1200		
G 09-0041	41	Plane, Platanus X hispanica.	5	60	1	1	1	1	-3	0	Y	Single stem	Fair	Thinning crown	None	No action is required	40+	C1	720		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-0042	42	Turkish hazel, Corylus colurna	10	150	3	3	3	3	-3	0	YM	Single stem	Fair	Thinning crown	Lamp, Path	Crown clean, Crown lift to 2.4m Over path Or lawn, Clear lamp	40+	C1	1800		
G 09-0043	43	Turkish hazel, Corylus colurna	5	70	1	1	1	1	-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	840		
T 09-0044	44	Turkish hazel, Corylus colurna	5	160	3	2	3	2	N-3	3	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	1920		
T 09-0045	45	Turkish hazel, Corylus colurna	5	80	1	2	2	2	E-2	2	Y	Single stem	Fair	Thinning crown	None	No action is required	40+	C1	960		
T 09-0046	46	Turkish hazel, Corylus colurna	5	120	2	2	2	2	N-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	1440		
T 09-0047	47	Turkish hazel, Corylus colurna	5	100	1	1	1	1	W-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	1200		
T 09-0048	48	Turkish hazel, Corylus colurna	9	170	3	3	2	2	E-4	4	YM	Single stem	Fair	None	None	No action is required	40+	B1	2040		
G 09-0049	-	Rowan, Sorbus aucuparia	6	150	4	4	4	4	W-1	3	M	Multi stem from 1.0m, One sided crown	Poor	Excessive deadwood	None	No recommendations are given	10+	C1	1800		
T 09-0050	50	Turkish hazel, Corylus colurna	5	120	1	2	2	1	S-3	3	Y	Single stem	Fair	None	None	No action is required	40+	C1	1440		
T 09-0051	-	Plane, Platanus X hispanica.	21	1630	6	8	8	6	W-2	3	M	Single main stem with heavy side branches	Fair	None	None	No recommendations are given	40+	B1	19560		
T 09-0052	-	Plane, Platanus X hispanica.	22	1240	5	4	8	7	E-3	3	M	One sided crown, Single stem to 8.0m	Fair	None	None	No recommendations are given	40+	B1	14880		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0053	-	Sycamore, Acer pseudoplatanus	12	300	3	5	5	5	E-1	3	YM	2 stems from the ground	Fair	None	Lamp	Clear lamp	40+	B1	3600		
G 09-0054	-	Rowan, Sycamore, Sorbus aucuparia 'Joseph Rock'	8	170	4	4	4	4	S-1	2	M	Multi stem from 1.0m	Poor	Thinning crown	None	No recommendations are given	10+	C1	2040		
T 09-0055	55	Turkish hazel, Corylus colurna	7	150	2	2	2	2	N-3	3	Y	Single stem	Fair	None	None	No action is required	40+	C1	1800	Fell for cycleway	
T 09-0056	-	Flowering cherry, Prunus Sp	11	550	6	7	6	6	E-2	2	M	Multi stem from 2.0m, Spreading crown	Fair	None	None	No recommendations are given	20+	B1	6600		
T 09-0057	57	Turkish hazel, Corylus colurna	6	150	2	2	2	2	N-3	3	YM	Single stem	Fair	None	None	No action is required	40+	C1	1800		
T 09-0058	-	Flowering cherry, Prunus Sp	7	310	3	5	3	3	E-1	2	M	2 stems from 1.0m, Spreading crown, Leaning	Fair	None	None	No recommendations are given	20+	B1	3720		
T 09-0059	59	Turkish hazel, Corylus colurna	5	110	2	1	2	1	E-3	0	Y	Single stem	Fair	Thinning crown	None	No action is required	40+	C1	1320		
T 09-0060	60	Turkish hazel, Corylus colurna	5	100	2	2	2	1	S-3	3	Y	Single stem	Fair	None	None	No action is required	40+	C1	1200		
T 09-0061	61	Norway maple, Acer platanoides	16	710	7	7	6	5	S-3	3	M	Multi stem from 3.0m	Poor	Narrow fork	None	No recommendations are given	20+	C1	8520		
T 09-0062	62	Swedish whitebeam, Sorbus intermedia	11	480	5	4	5	4	S-2	3	OM	Multi stem from 2.0m	Poor	Excessive deadwood	None	Monitor for death	10+	C1	5760		
H 0900-63	-	Beech, Fagus sylvatica sp.	3	100	1	1	1	1	-2	0	YM	Multi stem	Fair	None	None	Maintain as hedge	40+	C1	1200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0064	64	Turkish hazel, Corylus colurna	6	160	2	2	2	2	W-3	3	YM	Single stem	Fair	None	None	No action is required	40+	B1	1920	Fell for new road layout	
T 09-0065	65	Turkish hazel, Corylus colurna	5	150	2	2	2	2	E-3	3	YM	Single stem	Fair	None	None	No action is required	40+	C1	1800	Fell for new road layout	
T 09-0066	66	Turkish hazel, Corylus colurna	6	180	3	2	3	3	W-3	3	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	2160		
G 09-0067	-	Flowering cherry, Lime, Sycamore, Prunus Sp	11	500	5	5	5	5	S-2	3	M	Multi stem from 2.0m	Fair	None	None	No recommendations are given	20+	B1	6000		
T 09-0068	68	Lime, Tilia sp.	11	470	3	3	3	2	W-3	4	M	Multi stem from 4.0m	Fair	None	None	No recommendations are given	40+	B1	5640		
G 09-0069	69	Hornbeam, Carpinus betulus	10	170	2	2	2	1	W-2	3	YM	Single stem, Upright crown	Fair	None	None	No action is required	40+	B1	2040		
T 09-0070	70	Norway maple, Acer platanoides	5	110	1	1	1	1	W-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	1320	Fell for road widening	
T 09-0071	71	Norway maple, Acer platanoides	6	130	2	2	2	2	W-2	2	Y	3 stems from 2.0m	Fair	None	None	No action is required	40+	C1	1560	Fell for road widening	
T 09-0072	-	Lime, Tilia sp.	8	290	5	4	2	3	N-3	2	YM	3 stems from 3.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3480		
T 09-0073	-	Lime, Tilia sp.	12	270	5	4	3	2	S-2	2	YM	3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-0074	-	Lime, Tilia sp.	13	320	5	5	3	4	N-3	3	YM	2 stems from 3.0m	Fair	None	None	No action is required	40+	B1	3840		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0075	-	Lime, Tilia sp.	12	360	5	5	4	5	N-3	2	YM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4320		
T 09-0076	76	Sycamore, Acer pseudoplatanus	0	80	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	<10	U	960		
G 09-0077	77	Norway maple, Acer platanoides	5	130	1	1	1	1	E-2	2	Y	Multi stem from 2.0m, Upright crown	Poor	Thinning crown	Road	Crown lift to 5.1m Over road Or field, Monitor for death	40+	C1	1560		
G 09-0078	78	Norway maple, Acer platanoides	7	160	2	2	2	2	N-2	2	YM	Multi stem from 2.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	1920		
T 09-0079	79	Norway maple, Acer platanoides	9	350	5	5	5	5	S-2	1	EM	2 stems from 2.0m, Spreading crown	Fair	None	Lamp, Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear lamp	40+	B1	4200		
T 09-0080	80	Sycamore, Acer pseudoplatanus	8	320	5	4	4	3	W-1	2	EM	3 stems from 2.0m	Fair	Thinning crown	None	Crown clean	40+	B1	3840		
T 09-0081	-	Birch, Betula sp.	5	130	2	2	1	1	S-2	2	Y	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	C1	1560		
T 09-0082	-	Birch, Betula sp.	4	100	1	1	1	1	S-2	2	Y	Single stem	Poor	Excessive deadwood	None	Crown clean	20+	C1	1200		
-83	-	Oak, Quercus sp.	6	140	1	1	1	1	W-1	1	Y	Single stem, Upright crown	Fair	Thinning crown	None	No recommendations are given	40+	C1	1680		
S 09-0084	-	Fatsia	2	100	2	2	2	2	-	0	M	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0085	-	Birch, Betula sp.	3	240	2	3	4	3	W-2	0	EM	Multi stem from 2.0m, Weeping form	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	2880		
H 0900-86	-	Australian laurel,	1	100	0	0	0	0	-	0	EM	0	Fair	None	0	Maintain as hedge	20+	C1	1200		
T 09-0087	-	Holly, Ilex sp.	9	280	2	3	4	3	E-1	0	M	3 stems from the ground	Fair	None	Path, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Clear overhead cables	20+	B1	3360		
T 09-0088	-	Cabbage palm, Cordyline australis	5	420	2	2	2	2	E-1	1	M	Multi stem from 1.0m	Fair	None	None	No action is required	20+	B1	5040		
T 09-0089	-	Cabbage palm, Cordyline australis	6	300	2	1	2	2	W-2	3	M	3 stems from 2.0m	Fair	None	None	No action is required	20+	B1	3600		
S 09-0090	-	Magnolia, Magnolia sp.	4	220	2	3	3	2	S-1	1	EM	Multi stem	Fair	None	None	No action is required	40+	B1	2640		
G 09-0091	-	Plum, Prunus domestica	3	80	1	3	2	1	E-1	2	Y	3 stems from 1.0m	Fair	None	None	No action is required	20+	C1	960		
H 0900-92	-	Box, Buxus sempervirens	2	100	1	1	1	1	-	0	EM	0	Fair	None	0	Maintain as hedge	20+	C1	1200		
G 09-0093	-	Sycamore, Acer pseudoplatanus	14	550	3	5	5	4	N-2	3	EM	Single main stem with heavy side branches	Fair	None	0	0	40+	B1	6600		
H 0900-94	-	Privet, Ligustrum Sp	3	100	1	1	1	1	-	0	M	0	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	1200		
G 09-0095	-	Rowan, Sorbus aucuparia	6	150	2	2	2	2	E-1	1	EM	Single stem	Fair	None	None	No action is required	20+	C1	1800		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-0096	-	Birch, Betula sp.	7	130	1	2	1	1	S-1	1	Y	Single stem	Fair	None	None	No action is required	20+	C1	1560		
H 0900-97	-	Privet , Ligustrum Sp	4	100	1	1	1	1	-	0	M	0	Fair	None	0	Maintain as hedge	20+	C1	1200		
G 09-0098	-	Birch, Betula sp.	12	250	2	2	2	2	-	0	EM	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	3000		
T 09-0099	99	Sycamore, Acer pseudoplatanus	13	360	5	6	5	3	E-3	1	EM	3 stems from 3.0m	Fair	None	Buildings	Clear back from building	40+	B1	4320		
T 09-00100	-	Wych elm,	5	130	3	2	1	2	N-1	2	Y	Multi stem	Poor	Thinning crown	None	Monitor for death	10+	C1	1560		
T 09-00101	101	Flowering cherry, Prunus Sp	7	440	6	5	5	3	E-2	1	M	2 stems from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	5280		
T 09-00102	102	Apple, Malus sp.	4	150	3	2	1	2	N-2	2	M	2 stems from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800		
T 09-00103	103	Flowering cherry, Prunus Sp	7	490	5	5	5	4	E-2	2	M	3 stems from 2.0m, Spreading crown	Fair	None	Path	Crown clean, Crown lift to 2.4m Over path Or lawn	20+	B1	5880		
T 09-00104	104	Apple, Malus sp.	6	230	3	2	1	2	N-3	2	M	Single main stem with heavy side branches, Leaning	Poor	Basal rot, Basal damage, Infection of phellinus pomaceus	None	Fell	<10	U	2760		
T 09-00105	105	Lime, Tilia sp.	13	380	6	5	5	2	N-2	2	EM	2 stems from 2.0m	Fair	None	Path, Road, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	4560		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00106	106	Lime, Tilia sp.	13	330	5	3	2	3	E-4	2	EM	Single stem	Fair	None	Lamp, Path, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Clear lamp, Clear overhead cables	40+	B1	3960		
T 09-00107	107	Lime, Tilia sp.	13	330	2	4	4	4	N-4	2	EM	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3960		
T 09-00108	108	Lime, Tilia sp.	13	310	5	5	3	3	N-2	2	EM	2 stems from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3720		
T 09-00109	109	Lime, Tilia sp.	14	270	3	3	4	3	S-4	2	EM	Multi stem from 4.0m	Fair	None	Lamp, Path	Crown lift to 2.4m Over path Or lawn, Clear lamp	40+	B1	3240		
T 09-00110	110	Lime, Tilia sp.	14	340	5	3	3	4	E-2	1	EM	2 stems from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4080		
T 09-00111	111	Lime, Tilia sp.	13	350	2	4	4	2	E-4	1	EM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4200		
T 09-00112	112	Lime, Tilia sp.	13	330	3	2	5	4	E-3	1	EM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3960		
T 09-00113	113	Rowan, Sorbus aucuparia	9	280	4	3	4	2	E-2	3	M	Multi stem from 3.0m	Poor	Thinning crown	Lamp	Monitor for death, Clear lamp	10+	C1	3360		
T 09-00114	114	Rowan, Sorbus aucuparia	10	290	4	2	3	2	N-2	3	M	2 stems from 2.0m, 3 stems from 2.0m, 3 stems from 3.0m	Fair	None	None	No action is required	10+	B1	3480		
G 09-00115	115	Lime, Tilia sp.	13	350	6	3	6	4	S-2	2	EM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4200		
T 09-00116	116	Birch, Betula sp.	12	280	3	3	4	3	S-4	3	EM	Single main stem with heavy side branches	Fair	None	Buildings	Clear back from building	20+	B1	3360		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00117	117	Birch, Betula sp.	12	230	3	3	3	3	W-3	3	EM	Single main stem with heavy side branches	Fair	None	Buildings	Clear back from building	20+	B1	2760		
T 09-00118	118	Birch, Betula sp.	13	260	3	4	3	2	W-3	3	EM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	3120		
T 09-00119	119	Birch, Betula sp.	13	220	2	3	4	2	S-3	2	EM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	2640		
T 09-00120	120	Lime, Tilia sp.	14	530	5	6	5	5	E-4	0	EM	2 stems from 4.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	6360		
T 09-00121	-	Flowering cherry, Prunus Sp	6	550	5	5	4	4	E-1	2	M	2 stems from 1.0m, Spreading crown	Poor	Basal rot	None	Fell	<10	U	6600	Fell for new hard surfacing	
G 09-00122	122	Rowan, Sorbus aucuparia	6	250	3	3	3	3	E-1	2	M	Multi stem from 1.0m	Fair	None	None	No action is required	20+	B1	3000		
G 09-00123	123	Flowering cherry, Rowan, Prunus Sp	5	200	2	2	2	2	W-1	1	EM	Multi stem	Fair	None	None	No action is required	20+	B1	2400		
H 0900-124	-	Australian laurel,	3	100	2	2	2	2	-	0	M	0	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	1200		
H 0900-125	-	Photinia,	2	100	1	1	1	1	-	0	EM	Multi stem	Fair	None	None	Maintain as hedge	20+	C1	1200		
H 0900-126	126	Elder , Privet , Sambucus nigra	3	100	2	2	2	2	-	0	M	0	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	1200	Fell in part for road widening	
T 09-00127	127	Flowering cherry, Prunus Sp	6	300	4	5	3	4	N-2	2	EM	2 stems from 2.0m, Spreading crown	Fair	None	None	No action is required	20+	B1	3600	Fell for road widening	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-128	-	Privet, escallonia, Ligustrum Sp	2	100	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	1200		
H 0900-129	-	Privet, Ligustrum Sp	2	100	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	1200		
T 09-00130	-	Eucalyptus, Eucalyptus globulus	8	370	5	5	4	3	W-1	2	EM	2 stems from 1.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	4440		
T 09-00131	131	Beech, Fagus sylvatica sp.	4	60	1	1	1	1	E-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	720		
T 09-00132	132	Horse chestnut, Aesculus hippocastanum	10	320	4	3	5	4	N-2	3	EM	3 stems from 2.0m	Poor	Excessive deadwood, Thinning crown, Bark damage	Road	Crown clean, Crown lift to 5.1m Over road Or field, Monitor for death	10+	C1	3840		
T 09-00133	133	Hawthorn, Crataegus sp.	6	170	4	2	3	3	W-2	2	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2040		
T 09-00134	134	Beech, Fagus sylvatica sp.	17	820	7	7	6	7	N-3	1	M	Multi stem from 3.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	9840		
T 09-00135	-	Lawson cypress, Chamaecyparis lawsoniana	5	200	2	3	2	1	W-1	0	YM	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	2400		
T 09-00136	-	Flowering cherry, Prunus Sp	8	420	5	5	5	4	S-2	2	M	Multi stem from 2.0m, Spreading crown	Fair	None	Buildings	No recommendations are given	20+	B1	5040		
H 0900-137	-	Australian laurel,	2	100	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	1200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-00138	-	Cabbage palm, Holly, Crusaders palm, Cotinia, Cordyline australis	8	270	2	2	2	2	N-2	2	EM	Single main stem with heavy side branches	Fair	None	Buildings	No recommendations are given	20+	B1	3240		3
T 09-00139	-	Hawthorn, Crataegus sp.	7	350	4	3	2	3	N-1	2	M	Multi stem from 1.0m	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn	20+	B1	4200		
T 09-00140	-	Rowan, Sorbus aucuparia	9	300	4	3	2	4	N-2	1	M	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	3600		
T 09-00141	-	Laburnum, Laburnum sp.	6	180	4	3	1	1	E-1	3	M	Multi stem from 1.0m	Poor	Basal rot	None	Crown clean, Monitor for death	10+	C1	2160	Fell for road widening	
T 09-00142	-	Horse chestnut, Aesculus hippocastanum	17	600	5	4	4	4	W-3	2	M	Single main stem with heavy side branches	Poor	Excessive deadwood, Excessive ivy	None	Crown clean, Remove ivy, Monitor for death	10+	C1	7200	Fell for road widening	
T 09-00143	-	Purple plum, Prunus cerasifera 'Pissardii'	8	300	2	3	3	2	E-1	1	OM	Single main stem with heavy side branches	Poor	Basal rot	None	No recommendations are given	10+	C1	3600		
T 09-00144	-	Ash, Fraxinus excelsior	15	630	6	4	4	3	W-2	3	M	Multi stem from 3.0m	Poor	Excessive deadwood, Thinning crown	None	Crown clean, Monitor for death	10+	C1	7560	Fell for road widening	
T 09-00145	-	Rowan, Sorbus aucuparia	4	130	2	1	2	1	S-2	2	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	C1	1560	Fell for road widening	
T 09-00146	-	Ash, Fraxinus excelsior	13	270	7	2	3	3	S-0	2	YM	2 stems from The ground	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3240	Fell for road widening	
T 09-00147	-	Birch, Betula sp.	13	340	3	2	3	4	N-2	2	M	3 stems from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	4080	Fell for road widening	
T 09-00148	-	Birch, Betula sp.	15	330	4	3	3	3	E-3	2	M	Single main stem with heavy side branches	Fair	None	Road, Buildings	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m	20+	B1	3960	Fell for road widening	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
																Over road Or field					
T 09-00149	-	Holly, Ilex sp.	8	330	4	4	3	3	N-2	2	M	Single stem	Poor	Thinning crown	Path	Crown lift to 2.4m Over path Or lawn, Monitor for death	10+	C1	3960	Fell for road widening	
T 09-00150	-	Yew, Salix sp.	7	250	3	3	3	3	N-1	1	M	Multi stem, Upright crown	Fair	None	None	No action is required	40+	B1	3000		
T 09-00151	-	Flowering cherry, Prunus Sp	5	150	2	1	2	2	W-1	1	Y	Multi stem from 1.0m, Upright crown	Fair	None	None	No action is required	40+	C1	1800		
T 09-00152	152	Lime, Tilia sp.	10	230	3	3	4	3	N-2	2	YM	Single stem	Fair	None	Lamp, Road	Crown lift to 5.1m Over road Or field, Clear lamp	40+	B1	2760		
T 09-00153	153	Lime, Tilia sp.	9	230	4	4	3	3	W-2	2	YM	Single stem	Fair	None	None	No action is required	40+	B1	2760	Fell for road widening	
T 09-00154	154	Lime, Tilia sp.	9	210	4	4	4	3	N-2	2	YM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	2520	Fell for road widening	
T 09-00155	155	Norway maple, Acer platanoides	14	470	6	6	4	5	W-2	3	M	2 stems from 2.0m	Fair	None	None	Crown clean	40+	B1	5640	Fell for road widening	
S 09-00156	-	Cabbage palm, Escallonia, Cordyline australis	4	100	2	2	2	2	S-1	1	EM	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1200		
T 09-00157	-	Apple, Malus sp.	5	210	4	3	3	2	N-2	2	M	2 stems from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	2520		
T 09-00158	158	Gean, Prunus avium	13	460	5	6	5	5	E-2	1	M	Multi stem from 4.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	5520		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00159	159	Flowering cherry, Prunus Sp	6	260	4	4	5	2	E-1	2	EM	Single main stem with heavy side branches, Spreading crown	Fair	None	Path, Wall or fence	Crown lift to 2.4m Over path Or lawn, Clear back from wall or fence	20+	B1	3120		
T 09-00160	160	Rowan, Sorbus aucuparia	8	210	2	2	2	2	N-2	2	M	Single main stem with heavy side branches, Upright crown	Fair	None	Overhead telephone cables	Clear overhead cables	20+	B1	2520		
T 09-00161	-	Weeping birch, Betula pendula 'Youngii'	2	140	2	2	1	1	W-1	2	EM	Multi stem from 2.0m, Weeping form	Fair	None	None	No action is required	20+	C1	1680		
H 0900-162	-	Privet, Ligustrum Sp	2	100	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	1200		
G 09-00163	-	Pear, Pyrus sp.	7	170	2	3	2	3	W-1	2	EM	Multi stem from 2.0m	Fair	None	None	No action is required	40+	B1	2040		
G 09-00164	-	Pear, Pyrus sp.	8	250	4	3	3	4	W-1	2	EM	Multi stem from 1.0m, Upright crown	Fair	None	None	No action is required	40+	B1	3000		
H 0900-165	-	Lawson cypress, Privet, Australian laurel, Chamaecyparis lawsoniana cv.	3	100	1	1	1	1	-	0	M	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	1200		
G 09-00166	166	Lime, Tilia sp.	5	170	2	2	2	2	W-1	0	Y	Single main stem with heavy side branches	Fair	Thinning crown	Path	Crown clean, Crown lift to 2.4m Over path Or lawn	40+	B1	2040		
G 09-00167	167	Birch, Scots pine, Betula sp.	5	80	2	3	2	1	E-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	960		
T 09-00168	168	Flowering cherry, Prunus Sp	5	160	3	4	1	3	E-2	2	EM	Multi stem from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	1920	Fell for new hard surfacing	
T 09-00169	169	Flowering cherry, Prunus Sp	6	220	4	5	4	1	E-2	3	EM	3 stems from 2.0m, One sided crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2640	Fell for cycleway	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00170	170	Flowering cherry, Prunus Sp	6	270	2	5	4	5	W-2	2	EM	Multi stem from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3240	Fell for cycleway	
T 09-00171	171	Flowering cherry, Prunus Sp	5	170	2	3	2	1	S-2	2	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2040	Fell for cycleway	
T 09-00172	172	Flowering cherry, Prunus Sp	4	150	3	3	1	1	S-2	2	EM	3 stems from 2.0m	Fair	None	None	No action is required	20+	C1	1800	Fell for cycleway	
T 09-00173	173	Flowering cherry, Prunus Sp	6	220	3	4	2	0	E-2	2	YM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2640	Fell for cycleway	
T 09-00174	174	Flowering cherry, Prunus Sp	5	160	3	3	2	1	W-2	2	EM	Single main stem with heavy side branches	Poor	Thinning crown	Road	Crown clean, Crown lift to 5.1m Over road Or field	10+	C1	1920	Fell for cycleway	
T 09-00175	175	Flowering cherry, Prunus Sp	5	190	2	4	2	0	E-2	3	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2280	Fell for cycleway	
G 09-00176	-	Flowering cherry, Prunus Sp	8	450	6	6	6	6	-	0	M	Multi stem from 1.0m, Spreading crown	Fair	None	None	No recommendations are given	20+	B1	5400		
T 09-00177	-	Lime, Tilia sp.	14	660	5	6	6	5	-	1	M	2 stems from 2.0m	Fair	None	None	No recommendations are given	40+	B1	7920		
T 09-00178	178	Flowering cherry, Prunus Sp	5	130	3	3	3	1	E-2	2	EM	3 stems from 2.0m, Spreading crown	Fair	None	Path, Road, Buildings	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear back from building	20+	C1	1560	Fell for new hard surfacing	
T 09-00179	179	Flowering cherry, Prunus Sp	6	260	3	4	5	1	S-2	2	M	2 stems from 1.0m	Fair	None	Path, Road, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	3120	Fell for cycleway	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00180	180	Flowering cherry, Prunus Sp	8	410	3	5	5	5	N-2	2	M	2 stems from 3.0m	Fair	None	Path, Road, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	4920	Fell for cycleway	
T 09-00181	181	Flowering cherry, Prunus Sp	5	160	3	4	4	3	N-2	2	EM	Multi stem from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	1920		
T 09-00182	-	Gean, Prunus avium	13	530	4	6	6	5	S-2	2	M	Multi stem from 2.0m	Fair	None	Buildings	No recommendations are given	20+	B1	6360		
T 09-00183	183	Flowering cherry, Prunus Sp	5	210	2	3	4	4	N-2	2	EM	3 stems from 2.0m	Fair	None	Path, Road, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	2520		
T 09-00184	184	Flowering cherry, Prunus Sp	7	330	3	3	3	3	S-2	3	M	2 stems from 2.0m	Poor	Excessive deadwood	Road, Overhead electric cables	Crown clean, Crown lift to 5.1m Over road Or field, Monitor for death, Clear overhead cables	10+	C1	3960		
T 09-00185	185	Flowering cherry, Prunus Sp	11	410	5	5	5	5	S-3	2	M	Single main stem with heavy side branches	Fair	None	Path, Road, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	4920		
T 09-00186	186	Flowering cherry, Prunus Sp	7	230	3	4	3	1	W-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2760		
T 09-00187	187	Flowering cherry, Prunus Sp	7	220	3	4	3	1	N-2	2	EM	Multi stem from 2.0m, Upright crown	Fair	None	Road, Overhead electric cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	2640	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
S 09-00188	-	Philadelphus	4	50	3	3	2	2	-	0	M	Multi stem	Fair	None	None	No recommendations are given	20+	C1	600		
T 09-00189	-	Gean, Prunus avium	11	560	6	6	5	5	S-2	1	M	Multi stem from 2.0m	Fair	None	Path, Buildings, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Clear back from building, Clear overhead cables	20+	B1	6720		
T 09-00190	-	Birch, Betula sp.	10	350	5	4	4	4	S-0	1	M	2 stems from The ground	Fair	None	Path, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Clear overhead cables	20+	B1	4200		
T 09-00191	191	Flowering cherry, Prunus Sp	6	220	2	4	3	1	-2	2	EM	Multi stem from 2.0m, Upright crown	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	2640	Fell for new hard surfacing	
T 09-00192	192	Flowering cherry, Prunus Sp	7	220	3	5	2	1	N-2	2	M	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over road Or field	20+	B1	2640	Fell for new hard surfacing	
T 09-00193	193	Flowering cherry, Prunus Sp	7	260	5	4	4	3	E-2	2	M	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3120		
T 09-00194	194	Flowering cherry, Prunus Sp	5	220	2	3	3	1	N-2	2	EM	3 stems from 2.0m, One sided crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2640		
T 09-00195	195	Flowering cherry, Prunus Sp	4	120	4	3	1	1	E-2	2	EM	2 stems from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1440	Fell for new hard surfacing	
G 09-00196	-	Leyland cypress, Cupressocyparis leylandii	15	600	5	5	5	5	N-1	2	M	Multi stem from 3.0m	Fair	None	Lamp	No recommendations are given	20+	B1	7200		
T 09-00197	197	Flowering cherry, Prunus Sp	6	330	3	3	3	3	N-2	2	M	3 stems from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3960	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00198	-	Flowering cherry, Prunus Sp	5	180	3	3	2	3	N-2	2	YM	2 stems from The ground, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	2160		
T 09-00199	-	Flowering cherry, Prunus Sp	4	120	3	3	2	2	N-0	1	Y	3 stems from the ground	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1440		
T 09-00200	-	Hawthorn, Crataegus sp.	8	310	3	1	2	2	W-1	1	M	Multi stem from 1.0m	Fair	None	None	No action is required	40+	B1	3720		
T 09-00201	-	Gean, Prunus avium	9	290	4	4	4	4	W-1	1	EM	Single stem	Fair	None	Path, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Clear overhead cables	20+	B1	3480		
T 09-00202	202	Flowering cherry, Prunus Sp	7	350	3	5	5	2	N-2	2	M	Multi stem from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	4200	Fell for new hard surfacing	
G 09-00203	-	Lawson cypress, Chamaecyparis lawsoniana	6	330	3	3	3	3	N-1	1	M	Multi stem from 1.0m, Upright crown	Fair	None	None	No action is required	10+	B1	3960		
T 09-00204	204	Flowering cherry, Prunus Sp	5	150	3	4	1	0	N-2	2	M	2 stems from 2.0m, One sided crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800	Fell for new hard surfacing	
T 09-00205	205	Flowering cherry, Prunus Sp	6	230	3	4	2	1	W-2	2	M	Multi stem from 2.0m, One sided crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	2760	Fell for new hard surfacing	
T 09-00206	206	Flowering cherry, Prunus Sp	12	450	6	6	5	4	W-2	2	M	2 stems from 3.0m, Spreading crown	Fair	Excessive end weight	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	5400	Fell for new hard surfacing	
T 09-00207	207	Flowering cherry, Prunus Sp	8	330	6	4	5	5	S-2	1	M	Multi stem from 3.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3960	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00208	208	Flowering cherry, Prunus Sp	6	250	3	3	1	1	W-2	2	M	Multi stem from 2.0m, One sided crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3000	Fell for new hard surfacing	
T 09-00209	209	Flowering cherry, Prunus Sp	8	290	4	4	3	2	N-2	2	M	3 stems from 2.0m	Poor	Basal rot, Forming cavity, Basal damage	Path, Road	Fell	<10	U	2393.499	Fell for new hard surfacing	
H 0900-210	-	Photinia, forsythia,	3	100	1	1	1	1	-	0	EM	Multi stem	Fair	None	None	Maintain as hedge	20+	C1	1200		
T 09-00211	-	Monkey puzzle, Araucaria araucana	14	470	5	4	4	5	S-3	2	M	Single stem	Fair	None	None	No action is required	20+	B1	5640		
H 09-00212	-	Lawson cypress, Chamaecyparis lawsoniana	4	180	1	1	1	1	-	0	M	Multi stem	Fair	None	None	Maintain as hedge	20+	B1	2160		
T 09-00213	213	Flowering cherry, Prunus Sp	6	180	4	4	2	2	N-2	2	EM	Multi stem from 2.0m	Poor	Basal damage	Road	Fell	<10	U	2160	Fell for new hard surfacing	
G 09-00214	-	Himalayan birch, Betula utilis	5	250	2	2	3	2	S-2	1	YM	Multi stem from 2.0m	Fair	None	None	No action is required	20+	B1	3000		
G 09-00215	215	Maidenhair, Ginkgo biloba	6	150	1	2	2	1	N-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	1800	Fell for new road layout	3
T 09-00216	216	Pear, Pyrus sp.	9	210	3	3	2	2	W-2	3	EM	2 stems from 4.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field, Reduce end weight by 3.0m	40+	B1	2520		
G 09-00217	-	Himalayan birch, Betula utilis	4	60	1	1	1	1	N-1	1	Y	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	C1	720		
H 0900-218	-	Australian laurel,	2	80	1	1	1	1	-	0	EM	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	960	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00219	-	Peach	3	50	2	2	2	2	S-0	1	YM	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	600		
T 09-00220	-	Himalayan birch, Betula utilis	6	290	3	4	4	4	N-1	2	EM	Multi stem from 1.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	3480		
T 09-00221	-	Rowan, Sorbus aucuparia	6	160	2	3	1	2	E-1	2	M	2 stems from 1.0m	Fair	None	None	No action is required	20+	B1	1920		
T 09-00222	-	Bay, Laurus nobilis	8	100	3	4	3	4	-	0	M	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1200		
T 09-00223	-	Weeping birch, Betula pendula 'Youngii'	4	200	3	3	3	2	N-2	1	EM	Multi stem from 2.0m, Weeping form	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	2400	Fell for new road layout	
T 09-00224	-	Flowering cherry, Prunus Sp	2	140	3	2	2	1	S-1	1	M	Multi stem from 1.0m, Weeping form	Poor	Excessive deadwood	None	Crown clean, Monitor for death	10+	C1	1680	Fell for new road layout	
T 09-00225	225	Rowan, Sorbus aucuparia	8	380	4	3	3	2	N-1	2	M	Multi stem from 1.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4560	Fell for new road layout	
T 09-00226	226	Horse chestnut, Aesculus hippocastanum	14	760	5	6	5	3	N-2	3	OM	Multi stem from 3.0m	Poor	Excessive deadwood, Thinning crown	Road	Fell	<10	U	9120	Fell for new road layout	
T 09-00227	227	Rowan, Sorbus aucuparia	8	290	3	3	2	2	N-1	2	M	3 stems from 1.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	3480	Fell for new road layout	
T 09-00228	228	Lime, Tilia sp.	16	530	5	5	3	3	W-1	0	M	2 stems from 5.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6360	Fell for new road layout	
T 09-00229	229	Lime, Tilia sp.	16	590	4	5	5	2	S-3	2	M	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	7080	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-230	230	Privet, Ligustrum Sp	2	100	1	1	1	1	-	0	M	0	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	1200		
T 09-00231	231	Lime, Tilia sp.	6	220	3	3	3	3	N-2	1	Y	2 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	2640	Fell for new road layout	
T 09-00232	232	Sycamore, Acer pseudoplatanus	11	320	3	4	2	2	S-3	3	EM	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3840	Fell for new road layout	
T 09-00233	233	Sycamore, Acer pseudoplatanus	8	350	2	4	3	2	E-3	3	EM	2 stems from 3.0m	Fair	None	Road	Crown lift to 2.4m Over path Or lawn	40+	B1	4200	Fell for new road layout	
T 09-00234	234	Lime, Tilia sp.	13	560	5	5	4	3	W-2	0	EM	2 stems from 3.0m	Fair	None	Path, Road	Remove ivy, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6720	Fell for new road layout	
T 09-00235	-	Sycamore, Acer pseudoplatanus	12	440	5	5	5	5	N-0	4	EM	2 stems from The ground	Fair	None	Lamp, Road	Crown lift to 5.1m Over road Or field, Clear lamp	40+	B1	5280		
T 09-00236	-	Holly, Ilex sp.	10	260	2	3	3	3	S-3	2	M	Single stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	3120		
S 09-00237	-	Holly, Ilex sp.	4	150	1	2	1	2	-	2	M	3 stems from the ground	Fair	Thinning crown	Path	Crown lift to 2.4m Over path Or lawn	10+	C1	1800		
T 09-00238	238	Rowan, Sorbus aucuparia	5	180	2	1	2	2	W-2	3	M	2 stems from 2.0m	Fair	None	None	No action is required	20+	B1	2160		
T 09-00239	239	Lime, Tilia sp.	10	270	3	3	3	2	N-2	2	YM	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00240	240	Lime, Tilia sp.	7	240	3	2	3	3	S-2	1	Y	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2880		
T 09-00241	241	Swedish whitebeam, Sorbus intermedia	6	260	3	2	3	2	S-2	3	M	Multi stem from 2.0m	Poor	Thinning crown	None	No action is required	10+	C1	3120	Fell for new hard surfacing	
T 09-00242	242	Monterey cypress, Cupressus macrocarpa	18	940	6	5	6	8	W-4	5	M	Multi stem from 5.0m	Fair	None	None	No recommendations are given	20+	B1	11280	Fell for new hard surfacing	
T 09-00243	243	Norway maple, Acer platanoides	5	100	2	1	2	1	S-2	2	Y	2 stems from 2.0m	Poor	Thinning crown	Overhead telephone cables	Clear overhead cables	20+	C1	1200	Fell for new hard surfacing	
T 09-00244	244	Purple plum, Prunus cerasifera 'Pissardii'	3	130	1	2	1	1	-	1	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	C1	1560	Fell for new hard surfacing	
T 09-00245	245	Swedish whitebeam, Sorbus intermedia	4	120	1	1	1	1	W-2	2	YM	2 stems from 2.0m	Poor	Thinning crown	None	No action is required	10+	C1	1440	Fell for new hard surfacing	
T 09-00246	-	Rowan, Sorbus aucuparia	0	250	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	<10	U	3000	Fell as unsuitable	
S 09-00247	-	Cotinus, Cotinus coggygria	3	80	2	1	1	1	-	1	M	Multi stem from 1.0m	Fair	None	None	No action is required	20+	C1	960		
T 09-00248	-	Cabbage palm, Cordyline australis	3	230	1	1	1	1	W-2	2	M	Multi stem from 2.0m	Fair	None	None	No action is required	20+	B1	2760		
T 09-00249	-	Whitebeam, Sorbus aria	14	510	5	5	4	4	S-2	2	M	Multi stem from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	6120	Fell for new hard surfacing	
T 09-00250	-	Birch, Betula sp.	4	180	1	1	1	1	S-2	2	Y	2 stems from 2.0m	Fair	None	None	No action is required	20+	B1	2160	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-251	-	Privet, Ligustrum Sp	2	100	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	1200	Fell for new hard surfacing	
H 0900-252	-	Australian laurel,	2	100	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	1200		
T 09-00253	-	Western red cedar, Thuja plicata	6	230	2	2	1	2	E-1	2	YM	2 stems from 1.0m	Fair	None	None	No action is required	40+	B1	2760	Fell for new hard surfacing	
S 09-00254	-	Photinia,	4	100	3	3	3	3	-	0	M	Multi stem	Fair	None	Overhead telephone cables	Clear overhead cables	20+	C1	1200		
T 09-00255	-	Monterey cypress, Cupressus macrocarpa	5	440	4	4	4	3	S-1	2	YM	3 stems from 1.0m, Spreading crown	Poor	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	10+	C1	5280	Fell for new hard surfacing	
H 0900-256	-	Elder, Sambucus nigra	6	150	2	2	2	2	S-0	1	EM	Multi stem	Fair	None	Overhead telephone cables	Clear overhead cables	20+	C1	1800	Fell in part as per TPP for new hard surfacing	
T 09-00257	-	Apple, Malus sp.	6	320	2	2	3	2	N-2	2	M	Multi stem from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3840		
H 0900-258	-	Privet, Ligustrum Sp	3	50	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	600		
T 09-00259	-	Wych elm,.	0	350	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	-	U	4200	Fell as unsuitable	
H 0900-260	-	Australian laurel,	2	70	1	1	1	1	-	0	M	0	Fair	None	None	Maintain as hedge	20+	C1	840		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-261	-	Privet , lilac, Ligustrum Sp	5	120	2	2	2	2	-	0	M	0	Fair	Excessive deadwood	Path	Crown clean, Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	1440		
T 09-00262	262	Lime, Tilia sp.	17	550	6	6	6	6	E-3	2	M	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6600		
T 09-00263	263	Turkish hazel, Corylus colurna	5	80	1	1	1	1	E-2	2	Y	Single stem	Good	None	None	No action is required	40+	C1	960		
T 09-00264	264	Lime, Tilia sp.	11	280	3	5	4	3	S-2	2	YM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3360		
T 09-00265	265	Lime, Tilia sp.	10	270	3	3	2	2	N-3	2	YM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3240		
T 09-00266	266	Lime, Tilia sp.	7	170	1	3	2	1	E-3	2	Y	Single stem	Poor	Forming cavity, Bark damage	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	2040		
T 09-00267	267	Lime, Tilia sp.	17	560	6	5	6	5	W-4	2	M	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6720		
T 09-00268	268	Lime, Tilia sp.	16	480	5	5	5	3	N-3	2	M	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	5760		
T 09-00269	269	Lime, Tilia sp.	17	440	4	5	4	4	W-2	2	M	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	5280		
T 09-00270	270	Lime, Tilia sp.	15	320	5	5	5	5	W-3	3	EM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3840		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00271	271	Lime, Tilia sp.	18	730	6	6	7	7	N-3	2	M	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	8760		
T 09-00272	272	Lime, Tilia sp.	14	350	3	5	5	4	E-4	2	M	2 stems from 5.0m	Fair	None	Path	Crown lift to 5.1m Over road Or field	40+	B1	4200		
T 09-00273	273	Birch, Betula sp.	5	40	1	1	1	1	-	2	Y	Single stem	Fair	None	None	No action is required	20+	C1	480		
T 09-00274	274	Lime, Tilia sp.	16	490	5	6	5	4	S-2	3	M	2 stems from 2.0m	Poor	Hollow	None	Complete prune to include thinning re-shaping reducing end weight by 3.0m	10+	C1	5880		
T 09-00275	275	Lime, Tilia sp.	15	390	5	5	4	4	N-3	4	M	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	4680		
T 09-00276	276	Lime, Tilia sp.	16	440	6	5	5	4	N-2	2	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5280		
T 09-00277	277	Lime, Tilia sp.	16	450	5	5	3	4	W-4	4	M	Multi stem from 4.0m	Fair	None	None	No action is required	40+	B1	5400		
T 09-00278	278	Lime, Tilia sp.	13	330	4	4	3	3	S-4	2	EM	Multi stem from 4.0m	Fair	None	Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	3960		
T 09-00279	279	Lime, Tilia sp.	16	370	4	5	4	3	E-2	3	EM	2 stems from 3.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	4440		
T 09-00280	280	Lime, Tilia sp.	17	550	6	5	6	5	E-3	3	M	3 stems from 3.0m	Fair	Thinning crown	Road	Crown lift to 5.1m Over road Or field	40+	B1	6600		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00281	281	Lime, Tilia sp.	15	480	5	5	5	5	W-3	2	M	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5760		
T 09-00282	282	Lime, Tilia sp.	15	370	6	5	5	3	E-4	3	M	3 stems from 4.0 m	Fair	None	Overhead telephone cables, None	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	4440		
T 09-00283	283	Lime, Tilia sp.	17	580	6	4	6	5	S-4	2	M	3 stems from 4.0 m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6960		
T 09-00284	284	Lime, Tilia sp.	15	500	6	5	5	5	S-2	2	M	2 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6000		
T 09-00285	285	Lime, Tilia sp.	15	380	5	5	4	4	E-2	3	EM	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4560		
T 09-00286	286	Lime, Tilia sp.	15	520	4	5	4	4	W-3	54	M	2 stems from 3.0m	Fair	None	None	No action is required	40+	B1	6240		
T 09-00287	287	Lime, Tilia sp.	15	380	4	5	5	3	S-2	3	M	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4560		
T 09-00288	288	Lime, Tilia sp.	18	570	6	5	6	4	S-5	4	M	Multi stem from 5.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	6840		
T 09-00289	289	Lime, Tilia sp.	17	620	5	5	6	4	E-2	2	M	2 stems from 2.0m	Fair	Narrow fork	Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	7440		
T 09-00290	290	Sycamore, Acer pseudoplatanus	8	190	2	3	4	3	W-2	3	YM	2 stems from 3.0m	Fair	Basal damage	None	No action is required	40+	B1	2280		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00291	291	Lime, Tilia sp.	14	420	5	5	5	3	S-4	3	M	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5040		
T 09-00292	292	Lime, Tilia sp.	16	400	5	5	4	2	E-4	3	M	3 stems from 4.0 m, Leaning	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4800		
T 09-00293	293	Lime, Tilia sp.	14	380	5	5	5	4	S-3	3	M	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4560		
T 09-00294	294	Sycamore, Acer pseudoplatanus	11	220	2	3	4	3	N-3	3	YM	Multi stem from 3.0m	Fair	Basal damage	Road	Crown lift to 5.1m Over road Or field	40+	B1	2640		
T 09-00295	295	Sycamore, Acer pseudoplatanus	14	320	5	5	5	2	N-4	3	EM	3 stems from 4.0 m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3840		
T 09-00296	296	Lime, Tilia sp.	16	540	5	6	6	5	N-3	3	M	Multi stem from 3.0m, Spreading crown	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	6480		
T 09-00297	297	Lime, Tilia sp.	16	540	5	6	5	4	E-2	4	M	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	6480		
T 09-00298	298	Lime, Tilia sp.	4	320	1	1	1	1	-	2	Y	Single stem	Fair	Bark damage	None	No action is required	20+	B1	3840		
T 09-00299	299	Lime, Tilia sp.	17	630	7	6	6	5	E-3	2	M	3 stems from 3.0m, Spreading crown	Poor	Infection of Kretzschmaria deusta	Path, Road	Fell	<10	U	7560		
T 09-00300	300	Lime, Tilia sp.	14	390	5	5	4	3	E-3	2	M	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4680		
T 09-00301	301	Lime, Tilia sp.	15	480	5	6	6	4	N-2	2	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5760		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00302	302	Lime, Tilia sp.	15	550	5	5	4	2	N-3	2	M	3 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6600		
T 09-00303	303	Lime, Tilia sp.	7	200	3	2	2	1	N-2	2	Y	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	2400		
T 09-00304	304	Lime, Tilia sp.	13	350	5	5	5	5	W-4	2	EM	2 stems from 4.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4200		
T 09-00305	305	Lime, Tilia sp.	14	520	6	5	5	3	E-3	4	M	3 stems from 3.0m, Leaning	Fair	None	Road	Fell to clear road	<10	B1	6240		
T 09-00306	306	Lime, Tilia sp.	15	520	6	6	5	5	E-4	2	M	Multi stem from 4.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6240		
T 09-00307	307	Lime, Tilia sp.	14	300	5	4	4	4	E-3	2	EM	3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3600		
T 09-00308	308	Lime, Tilia sp.	14	300	4	3	4	4	S-4	2	EM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3600		
T 09-00309	309	Lime, Tilia sp.	15	550	6	5	6	6	W-4	2	M	Single stem to 8.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6600		
T 09-00310	310	Lime, Tilia sp.	11	370	4	3	2	3	E-3	2	EM	Multi stem from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4440		
T 09-00311	311	Lime, Tilia sp.	15	420	5	6	4	5	N-3	3	EM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5040		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00312	312	Lime, Tilia sp.	14	480	5	6	5	4	S-3	2	M	Multi stem from 3.0m	Fair	None	Path, Road, Wall or fence	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear back from wall or fence	40+	B1	5760		
T 09-00313	313	Lime, Tilia sp.	8	320	4	4	2	3	N-2	2	YM	Single main stem with heavy side branches	Fair	Bark damage	Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	3840		
T 09-00314	314	Lime, Tilia sp.	8	260	3	4	2	3	S-3	2	YM	Multi stem from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3120		
T 09-00315	315	Lime, Tilia sp.	10	270	4	3	4	2	S-2	2	YM	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-00316	316	Flowering cherry, Prunus Sp	12	520	3	7	6	6	E-2	1	M	Multi stem from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	6240		
T 09-00317	317	Lime, Tilia sp.	10	350	5	5	4	4	N-2	2	YM	2 stems from 2.0m	Poor	Thinning crown	Path, Road, Overhead telephone cables	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m, Clear overhead cables	20+	C1	4200		
T 09-00318	318	Flowering cherry, Prunus Sp	12	540	5	6	6	6	E-2	1	M	Multi stem from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	6480		
T 09-00319	319	Lime, Tilia sp.	13	390	5	5	4	5	N-2	3	EM	3 stems from 2.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	4680		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00320	320	Lime, Tilia sp.	13	500	6	6	5	5	W-2	2	M	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6000		
G 09-00321	-	Apple, Laburnum, Purple plum, Sycamore, Tree cotoneaster, Malus spp.	12	300	5	5	5	5	-	0	M	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	3600		
T 09-00322	-	Flowering cherry, Prunus Sp	14	630	5	7	6	7	W-2	2	M	3 stems from 3.0m	Fair	None	None	No recommendations are given	10+	B1	7560		
T 09-00323	-	Flowering cherry, Prunus Sp	13	580	6	7	6	6	E-2	2	M	Multi stem from 2.0m, Spreading crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	6960		
G 09-00324	-	Rowan, Sorbus aucuparia	7	320	3	3	3	3	-	2	M	Multi stem	Poor	Excessive deadwood, Thinning crown	None	Crown clean, Monitor for death	10+	C1	3840		
G 09-00325	-	Whitebeam, Sorbus aria	12	460	6	6	6	6	-	1	M	2 stems from 1.0m, Multi stem, Multi stem from 1.0m	Fair	None	Path, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Clear overhead cables	20+	B1	5520		
G 09-00326	-	Lawson cypress, Leyland cypress, Chamaecyparis lawsoniana cv.	13	650	3	3	3	3	-	1	M	Multi stem	Fair	Thinning crown	Path	Crown lift to 2.4m Over path Or lawn, Monitor for death	10+	B1	7800		
T 09-00327	327	Lime, Tilia sp.	13	350	5	5	5	3	N-2	2	EM	2 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4200		
T 09-00328	328	Lime, Tilia sp.	15	560	5	6	5	4	E-4	3	M	Multi stem from 5.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	6720		
T 09-00329	329	Lime, Tilia sp.	14	440	5	4	5	4	N-3	0	M	Multi stem from 3.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	5280		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00330	330	Apple, Malus sp.	5	150	3	2	3	2	S-2	2	EM	Single main stem with heavy side branches	Fair	Thinning crown	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800		
T 09-00331	331	Hornbeam, Carpinus betulus	5	140	2	2	1	1	W-2	2	YM	Single main stem with heavy side branches, Upright crown	Fair	None	None	No action is required	40+	C1	1680		
T 09-00332	332	Hornbeam, Carpinus betulus	6	170	2	2	1	1	N-2	2	YM	Single main stem with heavy side branches, Upright crown	Fair	None	None	No action is required	40+	B1	2040		
T 09-00333	333	Swedish whitebeam, Sorbus intermedia	8	320	3	2	2	3	S-2	2	M	Multi stem from 2.0m	Poor	Hollow, Forming cavity, Bark damage	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	10+	C1	3840		
T 09-00334	334	Rowan, Sorbus aucuparia	4	150	1	3	2	1	S-2	2	M	Single main stem with heavy side branches, Leaning	Poor	Excessive deadwood	Path	Fell	<10	U	1800		
T 09-00335	335	Rowan, Sorbus aucuparia	5	130	1	2	2	1	N-2	2	M	3 stems from 2.0m	Poor	Thinning crown	Path	Crown clean, Crown lift to 2.4m Over path Or lawn	10+	C1	1560		
T 09-00336	336	Rowan, Sorbus aucuparia	5	160	2	3	2	2	W-2	2	M	3 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	1920		
T 09-00337	337	Swedish whitebeam, Sorbus intermedia	9	370	4	3	4	3	S-2	1	M	2 stems from 2.0m, Spreading crown	Fair	None	Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	4440		
T 09-00338	338	Red Oak, Quercus rubra	5	80	1	1	1	1	E-2	2	Y	Single stem	Good	None	None	No action is required	40+	C1	960		
T 09-00339	339	Rowan, Sorbus aucuparia	8	250	1	1	2	2	E-1	1	M	2 stems from 3.0m	Poor	Recent crown failure	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	10+	C1	3000		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00340	340	Rowan, Sorbus aucuparia	4	150	2	1	1	1	E-2	2	M	Multi stem from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800		
T 09-00341	341	Sycamore, Acer pseudoplatanus	10	270	3	3	3	3	S-2	2	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-00342	342	Swedish whitebeam, Sorbus intermedia	8	330	4	4	3	3	E-2	2	M	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3960		
T 09-00343	343	Field maple, Acer campestre	8	230	3	2	3	2	N-2	2	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2760		
T 09-00344	344	Swedish whitebeam, Sorbus intermedia	8	300	3	4	4	4	E-2	2	M	2 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3600		
T 09-00345	345	Swedish whitebeam, Sorbus intermedia	7	290	3	3	3	3	E-2	2	M	Multi stem from 2.0m	Fair	None	Lamp, Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear lamp, Clear overhead cables	20+	B1	3480		
T 09-00346	346	Birch, Betula sp.	4	70	1	1	1	1	E-2	1	Y	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	840		
T 09-00347	347	Swedish whitebeam, Sorbus intermedia	6	280	3	3	3	2	S-2	2	M	3 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3360		
T 09-00348	348	Rowan, Sorbus aucuparia	5	170	2	2	2	1	E-2	2	M	Multi stem from 2.0m	Poor	Excessive deadwood, Thinning crown	Road	Crown clean, Crown lift to 5.1m Over road Or field, Monitor for death	10+	C1	2040		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00349	349	Birch, Betula sp.	4	70	1	1	1	1	S-1	1	Y	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	840		
T 09-00350	350	Norway maple, Acer platanoides	11	390	4	4	4	4	N-2	2	EM	Multi stem from 3.0m	Fair	Thinning crown	Road	Crown clean, Reduce end weight by 1.0m, Crown lift to 5.1m Over road Or field	20+	B1	4680		
T 09-00351	351	Swedish whitebeam, Sorbus intermedia	7	270	4	4	4	3	S-2	2	M	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn	20+	B1	3240		
T 09-00352	352	Birch, Betula sp.	4	70	2	2	2	1	E-2	1	Y	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	840	Fell for cycleway	
T 09-00353	353	Birch, Betula sp.	7	80	2	1	1	1	E-2	1	YM	Single stem	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	C1	960	Fell for cycleway	
T 09-00354	354	Rowan, Sorbus aucuparia	6	270	4	4	2	3	E-2	2	M	Multi stem from 2.0m, One sided crown	Poor	Excessive deadwood, Bark death	Lamp, Path	Crown clean, Crown lift to 2.4m Over path Or lawn, Monitor for death, Clear lamp	10+	C1	3240	Fell for cycleway	
T 09-00355	355	Swedish whitebeam, Sorbus intermedia	9	380	4	5	3	4	E-2	2	M	Multi stem from 2.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	4560	Fell for cycleway	
T 09-00356	356	Rowan, Sorbus aucuparia	7	260	3	2	3	4	W-2	4	OM	Multi stem from 2.0m	Poor	Excessive deadwood, Basal rot, Forming cavity, Bark death	None	Fell	<10	C1	3120	Fell for cycleway	
T 09-00357	357	Swedish whitebeam, Sorbus intermedia	10	380	4	4	4	5	E-2	3	M	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4560	Fell for cycleway	
T 09-00358	358	Turkish hazel, Corylus colurna	9	230	3	3	4	3	N-2	2	EM	Single main stem with heavy side branches	Good	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	A1	2760	Fell for cycleway	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00359	359	Turkish hazel, Corylus colurna	9	230	3	3	3	3	E-2	2	EM	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2760	Fell for cycleway	
T 09-00360	360	Rowan, Sorbus aucuparia	7	300	2	4	3	3	E-2	3	M	Multi stem from 2.0m	Poor	Excessive deadwood, Bark death	Road	Crown clean, Monitor for death	10+	C1	3600	Fell for cycleway	
T 09-00361	361	Himalayan birch, Betula utilis	4	60	2	1	1	1	N-2	2	Y	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	720	Fell for cycleway	
T 09-00362	362	Himalayan birch, Betula utilis	4	70	2	1	1	1	W-2	2	Y	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	840	Fell for cycleway	
T 09-00363	363	Rowan, Sorbus aucuparia	7	270	3	3	3	3	W-2	3	OM	Multi stem from 2.0m	Poor	Excessive deadwood, Bark death	Road, Overhead telephone cables	Fell	<10	U	3240	Fell for cycleway	
T 09-00364	364	Birch, Betula sp.	5	70	2	1	1	1	N-2	1	Y	Single stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	840		
T 09-00365	365	Himalayan birch, Betula utilis	4	70	2	1	1	1	N-2	2	Y	Single stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	840		
T 09-00366	366	Himalayan birch, Betula utilis	4	60	2	2	1	2	E-2	2	Y	Single stem	Good	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	720		
T 09-00367	367	Rowan, Sorbus aucuparia	7	250	2	4	3	3	E-2	2	M	3 stems from 2.0m, One sided crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	10+	B1	3000		
T 09-00368	368	Swedish whitebeam, Sorbus intermedia	5	150	2	2	2	2	E-2	2	EM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1800		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00369	369	Rowan, Sorbus aucuparia	6	230	3	3	2	2	E-2	2	M	2 stems from 3.0m	Poor	Excessive deadwood	Road	Crown clean, Crown lift to 5.1m Over road Or field, Monitor for death	10+	C1	2760	Fell for cycleway	
T 09-00370	370	Swedish whitebeam, Sorbus intermedia	4	130	2	2	1	2	W-2	2	YM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	C1	1560		
T 09-00371	371	Rowan, Sorbus aucuparia	7	290	2	3	3	3	S-2	3	OM	Multi stem from 2.0m	Poor	Excessive deadwood, Bark death	Road	Fell	<10	U	3480	Fell for cycleway	
T 09-00372	372	Rowan, Sorbus aucuparia	6	270	3	4	2	3	E-2	2	M	Multi stem from 2.0m	Fair	Excessive deadwood	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Monitor for death	10+	B1	3240	Fell for cycleway	
T 09-00373	373	Whitebeam, Sorbus aria	6	240	3	4	2	2	N-2	2	EM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2880	Fell for cycleway	
T 09-00374	374	Swedish whitebeam, Sorbus intermedia	7	250	3	4	3	2	N-2	2	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	3000	Fell for cycleway	
T 09-00375	375	Swedish whitebeam, Sorbus intermedia	6	250	2	4	4	2	E-2	2	EM	Multi stem from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3000	Fell for cycleway	
T 09-00376	376	Swedish whitebeam, Sorbus intermedia	5	150	2	3	2	2	N-2	2	YM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1800	Fell for cycleway	
T 09-00377	377	Swedish whitebeam, Sorbus intermedia	6	270	3	3	4	4	W-2	2	EM	Multi stem from 2.0m	Fair	None	Lamp, Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear lamp	40+	B1	3240	Fell for cycleway	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00378	378	Swedish whitebeam, Sorbus intermedia	7	280	4	4	3	3	E-2	2	M	Multi stem from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3360	Fell for cycleway	
T 09-00379	379	Rowan, Sorbus aucuparia	4	170	2	3	1	2	E-2	2	OM	3 stems from 2.0m	Poor	Excessive deadwood, Part failed fork, Recent crown failure	Path	Fell	<10	U	2040	Fell for cycleway	
T 09-00380	380	Birch, Betula sp.	8	310	4	3	3	4	E-0	1	EM	3 stems from the ground	Fair	None	Buildings	No recommendations are given	40+	B1	3720		
T 09-00381	381	Flowering cherry, Prunus Sp	6	270	6	4	1	4	N-2	3	M	Multi stem from 2.0m	Poor	Excessive deadwood	None	Crown clean, Monitor for death	10+	C1	3240		
T 09-00382	382	Flowering cherry, Prunus Sp	3	120	2	2	1	1	N-1	1	Y	Multi stem from 2.0m, Weeping form	Fair	None	None	No action is required	20+	C1	1440		
T 09-00383	383	Flowering cherry, Prunus Sp	3	130	2	2	1	2	N-2	1	YM	Multi stem from 2.0m, Weeping form	Poor	Basal damage	None	Crown clean, Monitor for death	10+	C1	1560		
T 09-00384	384	Flowering cherry, Prunus Sp	4	100	1	2	1	0	W-2	2	YM	Multi stem from 2.0m	Fair	Thinning crown	None	Crown clean	20+	C1	1200		
T 09-00385	385	Flowering cherry, Prunus Sp	5	300	5	4	1	4	W-2	0	M	Multi stem from 2.0m	Poor	Excessive deadwood, basal suckers	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Remove epicormics, Monitor for death	10+	C1	3600		
T 09-00386	386	Hornbeam, Carpinus betulus	5	70	1	1	1	1	N-2	2	Y	Multi stem from 2.0m, Upright crown	Poor	Basal damage	None	No action is required	20+	C1	840		
T 09-00387	387	Flowering cherry, Prunus Sp	3	80	2	1	0	1	N-2	2	YM	Multi stem from 2.0m, One sided crown	Poor	Basal damage	None	No action is required	10+	C1	960		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00388	388	Flowering cherry, Prunus Sp	4	150	3	3	2	2	N-2	1	YM	Multi stem from 2.0m, One sided crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	C1	1800		
T 09-00389	389	Flowering cherry, Prunus Sp	5	150	2	3	2	1	N-1	2	YM	Single main stem with heavy side branches, Leaning	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	C1	1800		
G 09-00390	-	Lime, Tilia sp.	17	1000	7	7	7	7	-	0	M	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	12000		
T 09-00391	391	Sycamore, Acer pseudoplatanus	16	550	6	7	6	6	N-2	3	M	3 stems from 3.0m	Fair	Basal damage	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	6600		
T 09-00392	392	Sycamore, Acer pseudoplatanus	13	320	3	4	5	3	E-2	4	EM	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3840		
T 09-00393	393	Sycamore, Acer pseudoplatanus	13	320	5	5	5	4	N-2	2	EM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3840		
T 09-00394	394	Norway maple, Acer platanoides	12	200	3	3	2	2	W-2	2	YM	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2400		
T 09-00395	395	Sycamore, Acer pseudoplatanus	15	370	5	5	5	2	S-3	4	M	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4440		
T 09-00396	396	Sycamore, Acer pseudoplatanus	8	170	4	3	4	4	N-2	3	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2040		
T 09-00397	397	Sycamore, Acer pseudoplatanus	12	330	5	5	5	5	S-2	3	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3960		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00398	398	Sycamore, Acer pseudoplatanus	13	300	5	5	4	3	E-2	3	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3600		
T 09-00399	399	Sycamore, Acer pseudoplatanus	8	170	2	3	3	2	N-3	3	YM	Multi stem from 3.0m	Fair	None	None	No action is required	40+	B1	2040		
T 09-00400	400	Sycamore, Acer pseudoplatanus	17	570	7	6	5	5	S-3	4	M	3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	6840		
T 09-00401	401	Sycamore, Acer pseudoplatanus	14	430	6	6	5	4	N-2	2	M	Multi stem from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	5160		
G 09-00402	402	Norway maple, Sycamore, Acer platanoides cv.	13	350	5	5	5	5	-	2	EM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4200		
T 09-00403	403	Norway maple, Acer platanoides	11	250	5	3	4	4	E-2	2	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	3000		
T 09-00404	404	Swedish whitebeam, Sorbus intermedia	12	370	4	4	4	4	E-2	2	M	Multi stem from 3.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4440		
T 09-00405	405	Norway maple, Acer platanoides	14	270	4	3	5	4	S-3	3	EM	3 stems from 4.0 m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-00406	406	Sycamore, Acer pseudoplatanus	12	270	4	4	3	4	E-2	2	EM	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-00407	407	Swedish whitebeam, Sorbus intermedia	12	360	5	5	1	3	E-2	2	M	Multi stem from 2.0m, Leaning	Fair	Root plate failure	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	4320		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00408	408	Norway maple, Acer platanoides	12	330	6	7	6	4	N-3	2	EM	3 stems from 3.0m, Spreading crown	Fair	Excessive end weight	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	40+	B1	3960		
T 09-00409	409	Sycamore, Acer pseudoplatanus	15	420	4	6	5	4	S-2	2	M	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5040		
G 09-00410	410	Norway maple, Sycamore, Acer platanoides cv.	14	350	5	5	5	5	-	2	EM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4200		
T 09-00411	411	Swedish whitebeam, Sorbus intermedia	10	360	4	4	3	4	S-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4320		
T 09-00412	412	Sycamore, Acer pseudoplatanus	16	460	6	6	5	5	N-2	3	M	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5520		
G 09-00413	413	Norway maple, Sycamore, Acer platanoides cv.	13	370	5	5	5	5	-	2	EM	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4440		
T 09-00414	414	Norway maple, Acer platanoides	13	350	5	5	4	4	W-3	2	EM	Single main stem with heavy side branches	Poor	Thinning crown, Bark damage, Bark death, Basal damage	Road	Crown clean, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	C1	4200		
T 09-00415	415	Sycamore, Acer pseudoplatanus	10	270	4	5	4	2	E-2	2	YM	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240		
T 09-00416	416	Norway maple, Acer platanoides	14	300	5	4	4	3	S-2	3	EM	Multi stem from 5.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3600		
T 09-00417	417	Norway maple, Acer platanoides	14	310	4	3	3	3	W-2	3	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3720		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00418	418	Swedish whitebeam, Sorbus intermedia	12	400	4	4	3	4	E-2	3	M	Multi stem from 2.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4800		
T 09-00419	419	Ash, Fraxinus excelsior	13	270	4	5	5	4	N-4	1	EM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3240		
T 09-00420	420	Sycamore, Acer pseudoplatanus	16	440	5	5	5	5	N-2	2	M	Multi stem from 3.0m	Fair	None	Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	5280		
T 09-00421	421	Sycamore, Acer pseudoplatanus	15	410	6	6	6	6	S-2	2	M	3 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4920		
T 09-00422	422	Norway maple, Acer platanoides	12	500	4	5	5	3	N-2	3	M	Multi stem from 3.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	6000		
T 09-00424	424	Sycamore, Acer pseudoplatanus	12	310	5	4	5	4	W-2	3	YM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3720		
T 09-00424	424	Sycamore, Acer pseudoplatanus	19	620	5	5	5	5	S-3	5	M	3 stems from 3.0m	Fair	None	None	No action is required	40+	B1	7440		
T 09-00425	425	Sycamore, Acer pseudoplatanus	10	320	3	5	5	3	W-2	2	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3840		
T 09-00426	426	Norway maple, Acer platanoides	4	120	1	2	2	1	E-2	2	Y	Multi stem from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1440		
T 09-00427	427	Sycamore, Acer pseudoplatanus	13	400	6	5	5	3	N-3	4	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4800		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00428	428	Norway maple, Acer platanoides	20	620	7	7	6	5	N-3	5	M	Multi stem from 3.0m	Fair	Excessive end weight	Road	Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	7440		
T 09-00429	429	Sycamore, Acer pseudoplatanus	17	440	5	6	5	5	E-3	5	M	3 stems from 4.0 m	Fair	None	None	No action is required	40+	B1	5280		
T 09-00430	430	Norway maple, Acer platanoides	5	90	1	2	1	2	W-2	2	Y	2 stems from 2.0m	Fair	None	None	No action is required	40+	C1	1080		
T 09-00431	431	Sycamore, Acer pseudoplatanus	16	480	5	6	5	4	N-3	2	M	2 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	5760		
T 09-00432	432	Sycamore, Acer pseudoplatanus	8	200	3	3	3	3	S-2	2	YM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2400		
T 09-00433	433	Ash, Fraxinus excelsior	11	330	5	5	5	5	S-3	2	YM	Single main stem with heavy side branches	Fair	Excessive end weight	Path, Road, Overhead telephone cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m, Clear overhead cables	20+	B1	3960		
T 09-00434	434	Sycamore, Acer pseudoplatanus	7	210	3	3	4	2	S-2	2	YM	2 stems from 2.0m, 3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2520		
T 09-00435	435	Sycamore, Acer pseudoplatanus	15	480	6	7	7	6	S-2	2	-	3 stems from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	5760		
T 09-00436	436	Norway maple, Acer platanoides	10	260	5	4	3	3	N-2	2	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3120		
T 09-00437	437	Sycamore, Acer pseudoplatanus	11	290	4	5	4	4	E-2	2	YM	3 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m	40+	B1	3480		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
																Over road Or field					
T 09-00438	438	Sycamore, Acer pseudoplatanus	14	380	5	5	5	5	E-2	1	EM	Multi stem from 3.0m	Fair	None	Lamp, Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear lamp	40+	B1	4560		
T 09-00439	439	Norway maple, Acer platanoides	16	440	5	5	4	2	S-2	5	M	Multi stem from 3.0m, Upright crown	Fair	Thinning crown	None	Crown clean, Reduce end weight by 2.0m	10+	B1	5280		
T 09-00440	440	Norway maple, Acer platanoides	16	570	5	5	4	4	E-2	4	M	3 stems from 2.0m	Fair	Narrow fork	Road	Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	6840		
T 09-00441	441	Norway maple, Acer platanoides	17	540	6	4	5	5	S-2	4	M	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	6480		
T 09-00442	442	Norway maple, Acer platanoides	16	470	4	4	5	6	N-2	4	M	2 stems from 3.0m	Fair	Thinning crown, None	Road	Crown clean, Reduce end weight by 1.0m, Crown lift to 5.1m Over road Or field	20+	B1	5640		
T 09-00443	443	Ash, Fraxinus excelsior	13	270	4	5	4	3	E-4	3	YM	Single main stem with heavy side branches	Fair	Thinning crown	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Monitor for death	10+	B1	3240		
T 09-00444	444	Sycamore, Acer pseudoplatanus	12	290	3	4	4	4	S-2	2	EM	Multi stem from 2.0m	Fair	None	Path	Crown clean, Crown lift to 2.4m Over path Or lawn	40+	B1	3480		
T 09-00445	445	Norway maple, Acer platanoides	9	230	2	3	3	2	W-2	2	YM	3 stems from 2.0m	Poor	Recent crown failure	Path	Crown lift to 2.4m Over path Or lawn, Monitor for death	10+	C1	2760		
T 09-00446	446	Ash, Fraxinus excelsior	8	140	3	2	2	2	N-2	3	YM	Single main stem with heavy side branches	Poor	Excessive deadwood	None	Crown clean	10+	C1	1680		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00447	447	Sycamore, Acer pseudoplatanus	9	310	4	4	4	4	E-2	3	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3720		
T 09-00448	448	Sycamore, Acer pseudoplatanus	19	510	5	7	5	6	S-2	6	M	3 stems from 3.0m	Fair	None	None	No action is required	40+	B1	6120		
T 09-00449	449	Norway maple, Acer platanoides	12	340	4	4	5	4	N-2	3	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4080		
T 09-00450	450	Norway maple, Acer platanoides	14	370	5	5	5	4	S-3	4	EM	3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4440		
T 09-00451	451	Norway maple, Acer platanoides	16	510	7	5	6	7	W-2	4	M	3 stems from 3.0m, Spreading crown	Fair	Thinning crown, Excessive end weight	Road	Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	6120		
T 09-00452	452	Sycamore, Acer pseudoplatanus	18	630	6	7	6	5	E-4	3	M	3 stems from 4.0 m	Fair	Forming cavity	None	No action is required	40+	B1	7560		
T 09-00453	453	Norway maple, Acer platanoides	18	610	7	7	6	7	E-4	7	M	2 stems from 4.0m	Fair	Excessive end weight	None	Reduce end weight by 2.0m	20+	B1	7320		
T 09-00454	454	Ruby Ash	20	550	5	6	8	6	S-5	6	M	3 stems from 5.0m	Fair	None, Recent crown failure	None	Crown clean, Reduce end weight by 2.0m	20+	B1	6600		
T 09-00455	455	Sycamore, Acer pseudoplatanus	17	530	7	6	6	4	S-3	5	M	Multi stem from 3.0m	Fair	None	None	No action is required	40+	B1	6360		
T 09-00456	456	Norway maple, Acer platanoides	14	330	5	4	4	4	N-2	2	EM	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3960		
T 09-00457	457	Ash, Fraxinus excelsior	13	340	4	5	5	4	N-2	2	EM	Single main stem with heavy side branches	Fair	Excessive ivy	Path, Road	Crown clean, Remove ivy, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m	20+	B1	4080		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
																Over road Or field					
T 09-00458	458	Norway maple, Acer platanoides	17	550	5	6	7	6	S-2	4	M	Multi stem from 3.0m	Fair	Excessive end weight	Road	Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	6600		
T 09-00459	459	Norway maple, Acer platanoides	14	420	5	4	5	5	S-3	3	EM	3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5040		
T 09-00460	460	Sycamore, Acer pseudoplatanus	12	320	5	3	4	3	N-2	5	EM	3 stems from 2.0m	Fair	None	None	No action is required	40+	B1	3840		
T 09-00461	461	Sycamore, Acer pseudoplatanus	14	480	5	6	5	4	N-2	3	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5760		
T 09-00462	462	Ash, Fraxinus excelsior	12	270	4	4	4	4	N-3	2	EM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	3240		
T 09-00463	463	Ash, Fraxinus excelsior	10	180	3	3	3	3	E-3	2	YM	Multi stem from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2160		
T 09-00464	464	Ash, Fraxinus excelsior	14	340	3	5	4	3	E-3	2	EM	2 stems from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	4080		
T 09-00465	465	Sycamore, Acer pseudoplatanus	11	290	4	4	4	4	W-2	2	EM	Multi stem from 2.0m	Poor	Thinning crown	Road	Crown clean, Crown lift to 5.1m Over road Or field	20+	C1	3480		
T 09-00466	466	Sycamore, Acer pseudoplatanus	18	510	7	6	5	5	N-2	4	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	6120		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00467	467	Norway maple, Acer platanoides	14	440	5	5	4	3	E-2	2	M	Multi stem from 2.0m	Fair	None	Road, Overhead telephone cables	Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	5280		
T 09-00468	468	Flowering cherry, Prunus Sp	7	480	4	3	5	3	N-2	2	M	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	10+	B1	5760		
T 09-00469	469	Norway maple, Acer platanoides	14	390	5	5	5	5	S-2	2	EM	Multi stem from 2.0m	Poor	Thinning crown	None	Crown clean, Reduce end weight by 2.0m, Monitor for death	10+	C1	4680		
T 09-00470	470	Norway maple, Acer platanoides	11	360	5	5	4	4	N-2	3	EM	Multi stem from 2.0m, Spreading crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	4320		
T 09-00471	471	Ruby Ash	10	270	4	5	4	5	W-2	2	YM	Multi stem from 3.0m, Spreading crown	Fair	Recent crown failure, Excessive end weight	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	3240		
T 09-00472	472	Sycamore, Acer pseudoplatanus	11	350	5	4	5	4	N-2	2	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4200		
G 09-00473	473	Birch, Rowan, Betula sp.	10	250	3	3	3	3	-	1	EM	Single stem	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	20+	B1	3000		
T 09-00474	474	Hornbeam, Carpinus betulus	13	540	5	5	4	4	W-3	3	M	Multi stem from 3.0m, Upright crown	Fair	None	Road, Buildings	Crown lift to 5.1m Over road Or field, Clear back from building	40+	B1	6480	Fell	
T 09-00475	475	Hornbeam, Carpinus betulus	13	450	5	6	5	4	N-3	2	M	Multi stem from 3.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5400		
T 09-00476	476	Hornbeam, Carpinus betulus	13	420	5	4	5	3	W-2	2	M	Multi stem from 2.0m, Upright crown	Fair	Thinning crown	Road	Crown clean, Crown lift to 5.1m Over road Or field	20+	B1	5040		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00477	477	Hornbeam, Carpinus betulus	13	430	4	5	3	4	W-2	2	M	Multi stem from 2.0m, Upright crown	Fair	Thinning crown	Road	Crown clean, Crown lift to 5.1m Over road Or field	20+	B1	5160	Fell	
T 09-00478	478	Hornbeam, Carpinus betulus	13	450	3	5	4	3	W-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5400		
G 09-00479	479	Himalayan birch, Betula utilis	9	300	4	4	4	4	-	1	EM	Multi stem from 1.0m	Fair	None	None	No action is required	20+	B1	3600		
T 09-00480	480	Dawn redwood, Metasequoia glyptostroboides	9	320	4	3	3	1	S-1	1	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	3840		
T 09-00481	-	Birch, Betula sp.	12	470	5	4	5	5	S-1	1	M	3 stems from 1.0m	Fair	None	None	No recommendations are given	20+	B1	5640		
H 0900-482	-	Holly, Cherry laurel, Privet , Ilex aquifolium cv.	2	100	1	1	1	1	-	0	EM	0	Fair	None	None	Maintain as hedge	20+	C1	1200		
G 09-00483	-	Lawson cypress, Chamaecyparis lawsoniana	12	450	3	3	3	3	-	2	M	Single stem, Multi stem from 2.0m	Fair	Thinning crown	None	No recommendations are given	10+	B1	5400		
T 09-00484	-	Rowan, Sorbus aucuparia	6	270	3	3	3	3	N-2	2	M	Multi stem from 2.0m	Poor	Thinning crown	None	No recommendations are given	10+	C1	3240		
S0-00485	485	Hawthorn, Crataegus sp.	5	250	3	3	3	3	-	1	M	Multi stem	Fair	Excessive ivy	None	No recommendations are given	20+	B1	3000	Fell for new road layout	
T 09-00486	486	Ash, Fraxinus excelsior	12	250	4	3	4	5	N-2	2	YM	Multi stem	Fair	Excessive ivy	None	No recommendations are given	20+	B1	3000	Fell for new road layout	
T 09-00487	487	Ash, Fraxinus excelsior	11	250	5	4	5	3	N-0	3	YM	Multi stem	Poor	Excessive deadwood, Thinning crown	None	Monitor for death	10+	C1	3000	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00488	-	Beech, Fagus sylvatica sp.	6	130	2	2	1	2	N-1	1	Y	Single stem	Fair	None	None	No action is required	40+	C1	1560	Fell for new road layout	
G 09-00489	-	#N/A	10	200	5	5	5	5	-	0	YM	Multi stem	Fair	None	None	Crown clean, Thin stems as appropriate	40+	B1	2400	Fell for new road layout	
T 09-00490	-	Birch, Betula sp.	12	250	4	2	3	3	N-1	1	EM	Single main stem with heavy side branches	Fair	None	None	No recommendations are given	20+	B1	3000	Fell for new road layout	
G 09-00491	-	Birch, Eucalyptus, Scots pine, Serbian spruce, Goat willow, Betula sp.	8	150	2	2	2	2	-	0	YM	Single stem, Multi stem	Fair	None	None	No recommendations are given	20+	C1	1800	Fell for new road layout	3
G 09-00492	-	Ash, Fraxinus excelsior	13	500	7	7	7	7	-	1	EM	Multi stem, Spreading crown	Fair	Thinning crown, Recent crown failure, Excessive ivy	Path, Road	Crown clean, Remove ivy, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Monitor for death	10+	B1	6000	Fell in part	
G 09-00493	-	Hawthorn, Crataegus sp.	7	250	4	4	4	4	-	0	M	Multi stem	Poor	Excessive deadwood, Excessive ivy	None	Crown clean, Remove ivy	20+	C1	3000	No dig surfacing. Fell in part as per TPP for new hard surfacing.	
G 09-00494	494	English elm, Ulmus procera	9	160	5	5	5	5	-	0	YM	Multi stem	Poor	Excessive deadwood	Road	Crown lift to 5.1m Over road Or field, Monitor for death, Fell dead or dying stems	10+	C1	1920		
H 0900-495	495	Elder, Sambucus nigra	5	150	2	2	2	2	-	0	M	Multi stem	Fair	None	None	Maintain as hedge	20+	C1	1800		
G 09-00496	496	Buddelia, Crataegus x prunifolia	5	70	4	4	4	4	-	0	M	Multi stem	Fair	None	None	No action is required	10+	C1	840	Fell in part to facilitate new hard surfacing	
H 0900-497	497	Ash, Elder, Hawthorn, Fraxinus sp. cv.	7	150	2	2	2	2	-	0	M	Multi stem	Poor	Excessive deadwood	None	Maintain as hedge, Fell dead or dying stems	20+	C1	1800		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-498	498	Elder, Sambucus nigra	5	170	3	3	3	3	-	0	M	Multi stem	Poor	Excessive deadwood	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge, Fell dead or dying stems	10+	C1	2040	Fell for new road layout	
G 09-00499	499	English elm, Ulmus procera	0	350	0	0	0	0	-	0	-	0	Poor	Dead	0	Fell	<10	U	4200		
T 09-00500	500	Rowan, Sorbus aucuparia	4	130	2	2	2	2	W-2	2	EM	3 stems from 2.0m, 3 stems from 5.0m	Fair	None	None	No action is required	20+	C1	1560	Fell for new road layout	
T 09-00501	501	Rowan, Sorbus aucuparia	6	200	2	2	2	1	W-2	2	M	2 stems from 2.0m, Upright crown	Fair	None	None	No action is required	20+	B1	2400	Fell for new road layout	
T 09-00502	502	Rowan, Sorbus aucuparia	4	80	1	1	1	1	S-2	1	YM	Multi stem from 2.0m	Fair	None	None	No action is required	20+	C1	960	Fell for new road layout	
T 09-00503	503	Rowan, Sorbus aucuparia	4	80	1	1	1	1	N-2	2	YM	Single stem	Fair	None	None	No action is required	20+	C1	960	Fell for new road layout	
T 09-00504	504	Rowan, Sorbus aucuparia	4	80	1	1	1	1	W-2	2	Y	Single stem, 3 stems from 2.0m, 3 stems from 3.0m	Fair	None	None	No action is required	20+	C1	960	Fell for new road layout	
T 09-00505	505	Rowan, Sorbus aucuparia	5	130	2	2	2	2	W-2	2	EM	Multi stem from 2.0m	0	None	None	No action is required	20+	C1	1560	Fell for new road layout	
T 09-00506	506	Rowan, Sorbus aucuparia	6	220	3	3	3	3	S-2	2	EM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2640	Fell for new road layout	
T 09-00507	507	Rowan, Sorbus aucuparia	5	150	2	2	2	2	S-2	2	EM	Multi stem from 1.0m	Fair	None	0	No action is required	20+	C1	1800	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00508	508	Rowan, Sorbus aucuparia	4	150	2	2	2	2	W-2	2	YM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800	Fell for new road layout	
T 09-00509	509	Rowan, Sorbus aucuparia	5	160	2	2	2	1	S-2	2	EM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	1920	Fell for new road layout	
T 09-00510	510	Rowan, Sorbus aucuparia	5	70	1	1	1	1	E-2	2	Y	Single stem	Fair	None	None	No action is required	20+	C1	840	Fell for new road layout	
S 09-00511	-	Cherry laurel, Prunus laurocerasus	8	150	4	4	4	4	-	1	M	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800		
T 09-00512	512	Rowan, Sorbus aucuparia	4	60	1	1	1	1	S-2	2	Y	Single stem	Fair	None	None	No action is required	20+	C1	720	Fell for new road layout	
T 09-00513	513	Rowan, Sorbus aucuparia	5	220	3	3	2	2	W-1	2	M	Multi stem from 1.0m	Fair	Thinning crown	Path	Crown clean, Crown lift to 2.4m Over path Or lawn, Monitor for death	10+	B1	2640	Fell for new road layout	
T 09-00514	514	Rowan, Sorbus aucuparia	5	70	1	1	1	1	S-2	2	Y	Single stem	Fair	None	None	No action is required	20+	C1	840	Fell for new road layout	
T 09-00515	515	Rowan, Sorbus aucuparia	6	190	3	3	1	1	E-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	None	No action is required	20+	B1	2280	Fell for new road layout	
T 09-00516	516	Rowan, Sorbus aucuparia	6	180	3	3	1	2	N-2	2	-	2 stems from 2.0m, Upright crown	Fair	None	None	No action is required	20+	B1	2160	Fell for new road layout	
T 09-00517	517	Rowan, Sorbus aucuparia	5	150	3	2	1	2	E-1	2	M	3 stems from 1.0m	Fair	None	None	No action is required	20+	C1	1800	Fell for new road layout	
T 09-00518	518	Rowan, Sorbus aucuparia	5	170	2	3	2	1	E-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	None	No action is required	20+	B1	2040	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00519	519	Rowan, Sorbus aucuparia	6	200	2	3	1	2	W-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	None	No action is required	20+	B1	2400	Fell for new road layout	
T 09-00520	520	Rowan, Sorbus aucuparia	3	80	2	2	2	1	S-2	2	EM	Multi stem from 2.0m	Poor	Excessive deadwood	None	Fell	<10	U	960	Fell for new road layout	
T 09-00521	521	Rowan, Sorbus aucuparia	4	80	2	2	1	2	E-2	2	EM	3 stems from 2.0m	Fair	Thinning crown	None	Crown clean	10+	C1	960	Fell for new road layout	
T 09-00522	522	Rowan, Sorbus aucuparia	4	80	2	3	2	1	W-1	2	EM	Multi stem from 2.0m	Fair	None	None	No action is required	20+	C1	960	Fell for new road layout	
T 09-00523	523	Rowan, Sorbus aucuparia	3	80	1	2	1	1	S-2	2	EM	Multi stem from 2.0m	Fair	None	None	No action is required	20+	C1	960	Fell for new road layout	
T 09-00524	524	Rowan, Sorbus aucuparia	4	120	3	3	2	1	E-2	2	EM	Multi stem from 2.0m, Leaning	Fair	Root plate failure	None	No action is required	10+	C1	1440	Fell for new road layout	
T 09-00525	525	Rowan, Sorbus aucuparia	5	140	2	3	2	1	N-2	2	YM	2 stems from 3.0m, Leaning	Fair	Bark damage	None	No action is required	20+	C1	1680	Fell for new road layout	
T 09-00526	526	Rowan, Sorbus aucuparia	5	130	2	2	1	1	W-2	2	EM	Multi stem from 2.0m, Upright crown	Fair	None	None	No action is required	20+	C1	1560	Fell for new hard surfacing	
T 09-00527	527	Rowan, Sorbus aucuparia	4	100	2	2	2	1	S-2	2	EM	Multi stem from 2.0m	Poor	Thinning crown	None	No action is required	10+	C1	1200	Fell for new road layout	
T 09-00528	528	Rowan, Sorbus aucuparia	3	100	2	2	1	1	S-2	2	EM	2 stems from 2.0m	Poor	Excessive deadwood, Bark death	None	Fell	<10	U	1200	Fell for new road layout	
T 09-00529	529	Rowan, Sorbus aucuparia	6	180	3	3	2	2	E-2	2	M	Multi stem from 2.0m, Upright crown	Fair	Bark damage	None	Monitor for death	10+	B1	2160	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00530	530	Rowan, Sorbus aucuparia	6	200	3	3	2	2	E-2	2	M	Multi stem from 2.0m, Upright crown	Poor	Excessive deadwood	None	Fell	<10	U	2400	Fell for new road layout	
T 09-00531	531	Birch, Betula sp.	12	260	2	3	3	3	E-2	0	M	2 stems from 5.0m	Fair	Recent crown failure	None	Crown clean	20+	B1	3120	Fell for new hard surfacing	
T 09-00532	532	Birch, Betula sp.	7	260	3	3	3	3	S-2	0	M	Multi stem from 4.0m	Fair	None	Lamp	Clear lamp	20+	B1	3120	Fell for new hard surfacing	
T 09-00533	533	Birch, Betula sp.	8	240	2	2	2	2	W-2	0	M	Multi stem from 4.0m	Fair	None	None	No action is required	20+	B1	2880	Fell for new hard surfacing	
T 09-00534	534	Birch, Betula sp.	8	230	2	3	3	3	S-2	0	M	Multi stem from 3.0m	Fair	None	None	No action is required	20+	B1	2760	Fell for new hard surfacing	
T 09-00535	535	Lime, Tilia sp.	9	250	4	3	3	3	S-2	0	YM	Single main stem with heavy side branches	Fair	Vandalism, Recent crown failure	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3000		
G 09-00536	536	Birch, Betula sp.	11	230	3	3	3	3	-	1	EM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	2760		
T 09-00537	537	Birch, Betula sp.	7	150	2	3	3	2	S-2	2	EM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	C1	1800	Fell for new hard surfacing	
T 09-00538	538	Birch, Betula sp.	6	140	2	2	2	1	S-2	1	YM	2 stems from 3.0m	Fair	None	None	Crown clean	20+	C1	1680	Fell for new hard surfacing	
T 09-00539	539	Birch, Betula sp.	6	130	3	2	3	3	S-2	1	YM	3 stems from 2.0m	Poor	Excessive deadwood	None	Crown clean, Monitor for death	10+	C1	1560	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-00540	-	Sycamore, Acer pseudoplatanus	8	350	5	5	5	5	-	2	YM	Multi stem from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4200	Fell for new hard surfacing	4
T 09-00541	541	Birch, Betula sp.	7	160	3	2	1	2	S-2	2	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	1920	Fell for new hard surfacing	
T 09-00542	542	Birch, Betula sp.	8	230	3	3	3	3	S-2	1	EM	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2760	Fell for new hard surfacing	
T 09-00543	543	Lime, Tilia sp.	10	240	3	3	2	3	W-2	2	YM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	2880	Fell for new hard surfacing	
T 09-00544	544	Lime, Tilia sp.	9	310	4	4	3	3	E-1	2	YM	Multi stem from 1.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3720	Fell for new hard surfacing	
G 09-00545	545	Lime, Tilia sp.	10	300	4	4	4	4	-	1	YM	Single main stem with heavy side branches	Fair	None	Lamp, Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear lamp	40+	B1	3600	Fell for new hard surfacing	9
T 09-00546	546	Lime, Tilia sp.	8	350	4	4	4	3	N-1	1	YM	Multi stem from 1.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4200	Fell for new hard surfacing	
T 09-00547	547	Lime, Tilia sp.	8	200	3	4	3	2	W-1	1	YM	2 stems from The ground	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	2400	Fell for new hard surfacing	
G 09-00548	548	Lime, Tilia sp.	10	280	4	4	4	4	-	2	YM	Single main stem with heavy side branches	Fair	Recent crown failure	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3360	Fell for new hard surfacing	2

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00549	549	Lime, Tilia sp.	9	330	4	4	4	4	N-1	2	YM	2 stems from 1.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3960	Fell for new hard surfacing	
G 09-00550	550	Lime, Tilia sp.	10	320	4	4	4	4	-	1	YM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3840	Fell for new hard surfacing	4
G 09-00551	-	Birch, Betula sp.	11	250	5	5	5	5	-	1	EM	Single main stem with heavy side branches	Fair	None	None	No recommendations are given	20+	B1	3000		
W 09-00552	552	Ash, Hawthorn, Fraxinus sp. cv.	12	450	5	5	5	5	-	0	EM	Multi stem	Fair	None	Road	Crown clean, Remove ivy, Crown lift to 5.1m Over road Or field	20+	B1	5400		
G 09-00553	553	English elm, Ulmus procera	14	400	5	5	5	5	-	1	YM	Multi stem	Poor	Excessive deadwood, Thinning crown	None	Fell dead or dying stems	<10	U	4800	Fell for new road layout	12
H 0900-554	554	Beech, Fagus sylvatica sp.	2	80	1	1	1	1	-	0	Y	Multi stem	Fair	None	None	Maintain as hedge	40+	C1	960	Fell in part for new road layout	
G 09-00555	555	Ash, Fraxinus excelsior	5	120	3	2	3	2	N-2	2	Y	2 stems from The ground	Good	None	None	No action is required	20+	C1	1440		
H 0900-556	-	Leyland cypress, Cupressocyparis leylandii	14	300	4	4	4	4	-	1	EM	Single stem	Fair	None	Road, Overhead electric cables	Crown lift to 5.1m Over road Or field, No recommendations are given, Clear overhead cables	20+	B1	3600		
T 09-00557	-	Norway maple, Acer platanoides	9	160	2	3	3	2	S-1	2	YM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	1920		
S 09-00558	-	Laburnum, Laburnum sp.	4	100	3	2	3	3	-	1	M	Multi stem	Fair	None	None	No action is required	20+	C1	1200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00559	-	Monterey cypress, Cupressus macrocarpa	13	580	6	5	5	4	W-1	1	EM	Single main stem with heavy side branches	Fair	None	Path, Road, Overhead electric cables	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	20+	B1	6960	Fell for road widening	
T 09-00560	-	Monterey cypress, Cupressus macrocarpa	14	780	7	5	7	6	W-1	1	EM	Multi stem from 5.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	9360	Fell for road widening	
T 09-00561	-	Apple, Malus sp.	5	270	4	4	2	3	S-19	1	EM	Multi stem from 1.0m, Multi stem from 5.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3240	Fell for road widening	
T 09-00562	-	Monterey cypress, Cupressus macrocarpa	15	660	5	6	6	6	W-1	1	M	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	7920	Fell for new hard surfacing	
S 09-00563	563	Elder, Viburnums, Sambucus nigra	6	150	4	4	4	4	-	1	M	Multi stem	Fair	None	None	No action is required	20+	C1	1800		
T 09-00564	564	Birch, Betula sp.	7	280	4	3	4	2	S-1	1	YM	2 stems from The ground	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	3360	Fell for new hard surfacing	
T 09-00565	565	Oak, Quercus sp.	17	1130	6	6	7	6	W-2	1	M	Single stem to 8.0m	Fair	Excessive deadwood, Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 2.0m	40+	B1	13560	New no dig surfacing	
W 09-00566	566	Ash, Birch, Fraxinus sp. cv.	12	250	4	4	4	4	-	1	EM	Single main stem with heavy side branches	Fair	None	None	Thin stems as appropriate	40+	B1	3000	Fell in part for new road layout	
W 09-00567	567	Ash, Birch, Fraxinus sp. cv.	14	350	4	4	4	4	-	3	EM	Single main stem with heavy side branches	Fair	Thinning crown	None	Crown clean, Monitor for death, Thin stems as appropriate	20+	B1	4200	Fell in part for new road layout	15
G 09-00568	568	Ash, Alder, Birch, Hazel, Fraxinus sp. cv.	8	150	3	3	3	3	-	1	Y	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Thin stems as appropriate	20+	C1	1800	Fell in part for new road layout	42

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-00569	569	Ash, Alder, Birch, Fraxinus sp. cv.	10	170	3	3	3	3	-	1	YM	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	2040	Fell in part	
T 09-00570	-	Horse chestnut, Aesculus hippocastanum	19	730	7	7	5	7	S-2	2	OM	Multi stem from 5.0m	Poor	Thinning crown, Bark damage	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Monitor for death	10+	C1	8760	No dig surfacing	
T 09-00571	571	Rowan, Sorbus aucuparia	7	230	4	3	2	2	W-2	2	M	2 stems from 1.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2760		
T 09-00572	572	Norway maple, Acer platanoides	12	330	4	5	4	5	W-2	3	EM	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3960		
T 09-00573	-	Flowering cherry, Prunus Sp	11	310	3	5	5	3	E-2	2	M	Multi stem from 2.0m	Fair	None	None	No recommendations are given	20+	B1	3720		
T 09-00574	-	Flowering cherry, Prunus Sp	7	270	1	2	2	1	E-1	2	M	Multi stem from 1.0m, Upright crown	Fair	None	None	No recommendations are given	20+	B1	3240		
G 09-00575	-	Cabbage palm, Canary date palm, Cordyline australis	2	300	2	2	2	2	-	1	Y	Single stem	Fair	None	None	No action is required	40+	B1	3600	Fell	
T 09-00576	-	Laburnum, Laburnum sp.	5	250	3	2	2	2	N-1	2	M	Multi stem from 1.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	3000		
T 09-00577	-	Cabbage palm, Cordyline australis	4	150	2	2	2	2	-	2	YM	Multi stem, Multi stem from 5.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	C1	1800		
T 09-00578	578	Rowan, Sorbus aucuparia	7	200	3	3	2	2	N-2	2	M	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	20+	B1	2400	Fell for new hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00579	579	Norway maple, Acer platanoides	12	360	5	5	4	3	E-2	2	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4320		
T 09-00580	580	Rowan, Sorbus aucuparia	6	200	3	3	2	1	N-2	2	M	2 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2400		
T 09-00581	-	Rowan, Sorbus aucuparia	6	240	3	3	3	2	E-2	2	M	Single main stem with heavy side branches	Fair	Thinning crown	Path	Crown lift to 2.4m Over path Or lawn	10+	B1	2880		
T 09-00582	582	Ash, Fraxinus excelsior	5	120	2	1	2	1	W-2	1	Y	Single stem	Fair	None	None	No action is required	20+	C1	1440	Fell for new road layout	
T 09-00583	583	Ash, Fraxinus excelsior	15	530	7	6	3	7	W-3	1	M	2 stems from 3.0m	Fair	Excessive end weight	None	Crown clean, Remove ivy, Reduce end weight by 2.0m, Monitor for death	20+	B1	6360	Fell for new road layout	
T 09-00584	584	Ash, Fraxinus excelsior	19	720	5	7	7	7	N-5	2	M	Multi stem from 5.0m	Fair	Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 2.0m, Monitor for death	20+	B1	8640	Fell for new road layout	
T 09-00585	585	Ash, Fraxinus excelsior	15	550	4	5	6	6	S-3	2	OM	Single stem to 6.0m	Poor	Hollow, Thinning crown, Excessive ivy	None	Fell	<10	U	6600	Fell for new road layout	
T 09-00586	586	Ash, Fraxinus excelsior	17	380	4	5	4	6	E-4	3	M	2 stems from 3.0m	Fair	Exposed, Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 2.0m	20+	B1	4560	Fell for new road layout	
T 09-00587	587	Ash, Fraxinus excelsior	15	470	3	4	5	5	N-6	3	M	Multi stem	Poor	Excessive deadwood, Thinning crown, Excessive ivy	Lamp	Crown clean, Remove ivy, Reduce end weight by 2.0m, Monitor for death, Clear lamp	10+	C1	5640	Fell for new road layout	
T 09-00588	588	Ash, Fraxinus excelsior	18	670	6	7	7	7	W-3	2	M	2 stems from 4.0m, Spreading crown	Fair	Excessive end weight, Excessive ivy	Road	Crown clean, Remove ivy, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	20+	B1	8040	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-589	589	Ash, Elder, Hawthorn, Fraxinus sp. cv.	11	300	4	4	4	4	-	0	M	Multi stem	Poor	Excessive deadwood, Excessive ivy	Path	Crown clean, Remove ivy, Crown lift to 2.4m Over path Or lawn, Maintain as hedge	20+	C1	3600	Fell for new road layout	
G 09-00590	590	Horse chestnut, Aesculus hippocastanum	7	250	3	3	3	3	-	2	YM	Single main stem with heavy side branches	Fair	Basal damage	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3000		
T 09-00591	591	Ash, Fraxinus excelsior	6	150	2	2	2	2	E-2	2	Y	Multi stem from 2.0m	Fair	None	None	No action is required	20+	C1	1800		
T 09-00592	592	Ash, Fraxinus excelsior	7	180	4	4	3	2	N-0	2	YM	Multi stem	Fair	Thinning crown	None	Monitor for death	10+	B1	2160		
G 09-00593	593	Ash, Fraxinus excelsior	10	220	4	4	4	4	-	2	YM	Single stem, 3 stems from the ground	Fair	None	None	Crown clean	20+	B1	2640		
T 09-00594	594	Ash, Fraxinus excelsior	17	620	6	6	9	5	W-1	3	M	2 stems from 1.0m, Spreading crown	Poor	Excessive deadwood, Excessive end weight, Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 3.0m, Monitor for death	10+	C1	7440		
G 09-00595	595	Ash, Fraxinus excelsior	15	350	5	5	5	5	-	1	EM	Multi stem	Poor	Excessive deadwood, Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 2.0m, Monitor for death	10+	C1	4200		
T 09-00596	596	Ash, Fraxinus excelsior	18	680	5	6	5	5	N-5	2	M	2 stems from 5.0m	Poor	Excessive deadwood, Thinning crown, Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 2.0m, Monitor for death	10+	C1	8160		
T 09-00597	597	Ash, Fraxinus excelsior	17	530	3	4	7	6	S-4	4	M	2 stems from 3.0m, Spreading crown	Fair	Thinning crown	Road	Crown clean, Remove ivy, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m	10+	B1	6360		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-00598	598	Ash, Fraxinus excelsior	9	400	4	4	4	4	-	2	YM	Multi stem	Fair	Excessive ivy	Road	Crown clean, Remove ivy, Crown lift to 5.1m Over road Or field	20+	B1	4800		
H 0900-599	599	Ash, Elder, Hawthorn, Fraxinus sp. cv.	7	300	3	3	3	3	-	0	M	Multi stem	Fair	Excessive ivy	Road	Crown clean, Remove ivy, Crown lift to 5.1m Over road Or field, Maintain as hedge	20+	B1	3600		
G 09-00600	600	Birch, Betula sp.	8	130	1	2	2	1	-	2	YM	Single stem	Good	None	None	No action is required	40+	C1	1560		
H 0900-601	601	Leyland cypress, Cupressocyparis leylandii	14	750	5	5	5	5	-	2	M	Single main stem with heavy side branches	Fair	None	None	Maintain as hedge	20+	B1	9000		
T 09-00602	602	Alder, Alnus sp.	13	480	4	6	5	1	N-1	2	EM	3 stems from 1.0m, Spreading crown, One sided crown	Fair	None	None	Tidy branch stumps	20+	B1	5760		
G 09-00603	603	Alder, Birch, Hazel, Alnus spp.	14	250	5	5	5	5	-	1	EM	Multi stem	Fair	None	Wall or fence	Crown clean, Remove ivy, Thin stems as appropriate, Clear back from wall or fence	20+	B1	3000		
T 09-00604	604	Birch, Betula sp.	16	300	5	5	4	2	S-0	2	M	2 stems from The ground	Fair	None	None	No action is required	20+	B1	3600	Fell for hard surfacing	
G 09-00605	605	Alder, Alnus sp.	11	230	4	3	2	3	-	0	YM	Single main stem with heavy side branches	Fair	None	None	Thin stems as appropriate	20+	B1	2760	Fell for hard surfacing	1
T 09-00606	606	Hazel, Corylus sp.	7	150	5	6	5	2	E-0	1	M	Multi stem, One sided crown	Fair	None	Wall or fence	Clear back from wall or fence	40+	C1	1800	Fell for hard surfacing	
T 09-00607	-	Ash, Fraxinus excelsior	11	350	5	3	4	4	N-2	1	YM	2 stems from 2.0m	Fair	Narrow fork, Thinning crown	None	Monitor for death	20+	B1	4200	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
S 09-00608	-	Berberis	2	50	1	1	2	1	-	0	EM	Multi stem	Fair	None	None	No action is required	20+	C1	600	Fell for new road layout	
T 09-00609	-	Ash, Fraxinus excelsior	12	480	6	6	3	6	N-2	2	EM	Multi stem from 3.0m, Spreading crown	Fair	Excessive deadwood, Excessive ivy	Path, Road	Crown clean, Remove ivy, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by 2.0m, Monitor for death	10+	B1	5760	Fell for new road layout	
T 09-00610	-	Ash, Fraxinus excelsior	12	450	4	4	4	5	W-1	1	EM	2 stems from 1.0m	Fair	Thinning crown	None	Crown clean, Monitor for death	10+	B1	5400	Fell for new road layout	
G 09-00611	-	Plum, Purple plum, Prunus domestica	5	200	3	3	3	3	-	1	EM	Multi stem	Fair	None	None	No recommendations are given	20+	B1	2400	Fell for hard surfacing	5
T 09-00612	612	Lime, Tilia sp.	8	320	3	3	2	2	E-1	1	YM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3840		
T 09-00613	613	Lime, Tilia sp.	8	250	3	4	3	4	E-2	1	YM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3000		
T 09-00614	614	Hornbeam, Carpinus betulus	9	310	2	2	3	2	N-1	2	M	3 stems from 1.0m, Upright crown	Fair	Basal damage	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	10+	B1	3720	Fell for hard surfacing	
T 09-00615	615	Hornbeam, Carpinus betulus	9	250	2	3	2	2	N-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3000	Fell for hard surfacing	
T 09-00616	616	Hornbeam, Carpinus betulus	9	280	2	3	2	2	W-1	2	M	Multi stem from 2.0m, Upright crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3360	Fell for hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00617	617	Hornbeam, Carpinus betulus	9	280	2	3	2	2	W-2	2	M	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3360	Fell for hard surfacing	
T 09-00618	618	Hornbeam, Carpinus betulus	9	280	3	3	3	2	N-2	2	M	Multi stem from 2.0m, Upright crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3360	Fell for hard surfacing	
H 0900-619	619	Hawthorn, Crataegus sp.	2	100	1	1	1	1	-	0	EM	Multi stem	Fair	None	None	Maintain as hedge	40+	C1	1200	Fell for hard surfacing	
G 09-00620	620	Lime, Tilia sp.	5	140	2	2	2	2	-	2	Y	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	C1	1680	Fell in part for cycleway (remove 2 of the 3 trees)	
T 09-00621	621	Sycamore, Acer pseudoplatanus	11	310	5	5	5	5	E-1	3	EM	2 stems from 2.0m, Spreading crown	Fair	None	Road	Crown clean, Crown lift to 5.1m Over road Or field	40+	B1	3720	Fell for hard surfacing	
T 09-00622	622	Norway maple, Acer platanoides	12	440	4	5	3	4	E-2	2	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	5280	Fell for hard surfacing	
H 0900-623	623	Ash, Hawthorn, Fraxinus sp. cv.	5	130	2	2	2	2	-	0	EM	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	40+	C1	1560	Fell for hard surfacing	
T 09-00624	624	Lime, Tilia sp.	13	350	5	5	5	3	N-2	0	EM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	4200	Fell for hard surfacing	
T 09-00625	625	Horse chestnut, Aesculus hippocastanum	12	320	5	5	5	2	S-3	2	EM	Multi stem from 3.0m, Spreading crown	Fair	Bark damage	None	No action is required	20+	B1	3840		
T 09-00626	626	Horse chestnut, Aesculus hippocastanum	14	430	5	5	4	4	W-2	0	EM	2 stems from 2.0m	Fair	None	None	No action is required	40+	B1	5160	Fell for hard surfacing	
T 09-00627	627	Lime, Tilia sp.	14	400	5	3	5	4	N-1	0	EM	2 stems from 1.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4800	Fell for hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
H 0900-628	628	Ash, Hawthorn, Hazel, Fraxinus sp. cv.	10	160	3	3	3	3	-	0	YM	Multi stem	Fair	None	None	Maintain as hedge	40+	B1	1920	Fell for new hard surfacing	
T 09-00629	629	Horse chestnut, Aesculus hippocastanum	3	100	1	1	1	1	W-1	1	Y	Multi stem from 1.0m	Fair	None	None	No recommendations are given	40+	C1	1200	Fell for hard surfacing	
G 09-00630	-	Hybrid poplar, Populus x euroamericana	12	140	3	2	3	2	N-1	1	Y	Single main stem with heavy side branches	Fair	None	None	No recommendations are given	20+	C1	1680		
T 09-00631	-	Lime, Tilia sp.	5	120	3	3	2	2	W-1	2	Y	3 stems from the ground, One sided crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1440		
T 09-00632	-	Ash, Fraxinus excelsior	18	560	6	4	6	2	N-2	7	M	2 stems from 2.0m, Spreading crown	Poor	Excessive deadwood	None	Crown clean, Remove ivy, Reduce end weight by 2.0m, Monitor for death	10+	C1	6720		
T 09-00633	-	Oak, Quercus sp.	16	730	4	6	6	5	N-2	2	M	3 stems from 3.0m, Spreading crown	Fair	Excessive ivy	None	Crown clean, Remove ivy	40+	B1	8760		
T 09-00634	-	Scots pine, Pinus sylvestris	18	520	7	5	4	4	E-6	3	M	Single stem, Leaning	Fair	Root plate failure	None	Crown clean, Remove ivy, inspect base rot	10+	B1	6240		
T 09-00635	-	Oak, Quercus sp.	19	780	7	7	5	7	E-4	2	M	2 stems from 5.0m	Fair	Excessive deadwood, Excessive ivy	None	Crown clean, Remove ivy, Reduce end weight by 2.0m	40+	B1	9360		
T 09-00636	-	Oak, Quercus sp.	20	620	6	4	4	7	N-6	4	M	Single main stem with heavy side branches	Fair	Thinning crown	None	No recommendations are given	40+	B1	7440		
T 09-00637	-	Horse chestnut, Aesculus hippocastanum	17	600	4	6	6	4	S-2	2	M	Single main stem with heavy side branches	Fair	None	None	No recommendations are given	20+	B1	7200		
G 09-00638	-	Lime, Tilia sp.	16	600	6	6	6	6	-	0	M	Multi stem	Fair	None	Path	Crown lift to 5.1m Over road Or field	40+	B1	7200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
W 09-00639	-	Ash, Elder, Wych elm, Hawthorn, Hazel, Lime, Fraxinus sp. cv.	13	400	5	5	5	5	-	0	-	Multi stem	Fair	Excessive deadwood	None	Crown clean, Remove ivy, Thin stems as appropriate	40+	B1	4800		
G 09-00640	-	Ash, Fraxinus excelsior	6	150	2	2	2	2	-	2	Y	Multi stem from 3.0m	Fair	None	None	No recommendations are given	20+	C1	1800	Fell in part for hard surfacing	6
G 09-00641	-	Ash, Fraxinus excelsior	6	130	1	1	1	1	-	2	Y	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	C1	1560		
T 09-00642	-	Ash, Fraxinus excelsior	4	130	3	2	2	2	N-1	2	Y	Multi stem from 1.0m	Fair	None	None	No recommendations are given	20+	C1	1560		
G 09-00643	-	Ash, Fraxinus excelsior	7	350	3	3	3	3	-	2	Y	Multi stem	Fair	Thinning crown	None	No recommendations are given	10+	B1	4200		
T 09-00644	-	Wych elm, Salix sp.	0	550	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	<10	U	6600		
T 09-00645	-	Horse chestnut, Aesculus hippocastanum	17	610	6	3	3	7	N-6	2	M	Single main stem with heavy side branches	Poor	Thinning crown	None	No recommendations are given	10+	C1	7320		
H 0900-646	-	Leyland cypress, Cupressocyparis leylandii	15	650	6	6	6	6	-	2	M	Multi stem from 1.0m, Spreading crown	Fair	None	Path, Wall or fence	Crown lift to 2.4m Over path Or lawn, Maintain as hedge	10+	B1	7800		
G 09-00647	647	Turkish hazel, Corylus colurna	5	80	1	1	1	1	-	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	960	Fell in part for new road layout	3
G 09-00648	648	Himalayan birch, Betula utilis	7	30	1	1	1	1	-	2	Y	Single main stem with heavy side branches	Fair, Dead	Excessive deadwood	None	Fell dead or dying stems	20+	C1	360	Fell for new road layout	5
T 09-00649	649	Wych elm	0	150	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	<10	U	1800		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00650	650	Wych elm.	15	550	5	6	5	5	N-3	3	M	2 stems from 3.0m	Poor	Excessive deadwood	Road	Fell	<10	U	6600		
T 09-00651	-	Purple plum, Prunus cerasifera 'Pissardii'	6	330	2	3	3	2	N-2	2	M	Multi stem from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	3960		
W 09-00652	-	Ash, Wych elm, Fraxinus sp. cv.	14	350	6	6	6	6	-	2	YM	Multi stem	Fair	Excessive deadwood	Path	Crown lift to 2.4m Over path Or lawn, Monitor for death	10+	B1	4200		
T 09-00653	-	Monterey cypress, Cupressus macrocarpa	17	700	4	7	7	4	S-4	2	M	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	8400		
G 09-00654	-	Wych elm, Sycamore, Salix sp.	15	450	4	5	6	4	-	3	EM	Multi stem	Fair	None	Road	Crown lift to 5.1m Over road Or field, Monitor for death	40+	B1	5400		
T 09-00655	655	Norway maple, Acer platanoides	7	150	1	2	2	2	W-2	2	YM	Single stem	Fair	Thinning crown	None	Crown clean	20+	C1	1800		
T 09-00656	656	Norway maple, Acer platanoides	7	140	2	4	2	1	E-2	3	Y	Single main stem with heavy side branches	Fair	Thinning crown	None	Crown clean	20+	C1	1680		
T 09-00657	657	Rowan, Sorbus aucuparia	5	90	2	1	1	1	W-3	3	EM	Multi stem from 3.0m	Fair	None	None	No action is required	20+	C1	1080		
T 09-00658	-	Sycamore, Acer pseudoplatanus	20	770	5	5	6	4	W-4	4	M	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	9240		
T 09-00659	-	Ash, Fraxinus excelsior	21	840	5	6	6	6	S-4	5	M	Single main stem with heavy side branches	Poor	Thinning crown	None	Crown clean, Monitor for death	10+	C1	10080		
T 09-00660	-	Sycamore, Acer pseudoplatanus	14	350	5	3	5	6	S-2	3	EM	2 stems from The ground	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	4200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00661	661	Norway maple, Acer platanoides	7	180	1	1	3	3	S-2	3	YM	2 stems from 3.0m	Fair	Thinning crown	None	Crown clean	20+	B1	2160		
T 09-00662	662	Pear, Pyrus sp.	7	110	3	3	3	2	S-2	2	YM	Single main stem with heavy side branches	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	40+	C1	1320		
T 09-00663	663	Pear, Pyrus sp.	7	110	3	2	3	2	E-2	2	YM	Single main stem with heavy side branches	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	40+	C1	1320		
T 09-00664	664	Pear, Pyrus sp.	9	150	3	3	3	2	E-3	2	YM	Single main stem with heavy side branches	Fair	None	Buildings	Tidy branch stumps, Clear back from building	40+	C1	1800		
T 09-00665	665	Pear, Pyrus sp.	5	110	2	3	2	2	N-2	2	YM	Multi stem from 2.0m	Fair	None	None	No action is required	40+	C1	1320		
T 09-00666	-	Sycamore, Acer pseudoplatanus	17	630	5	5	7	5	S-1	2	M	3 stems from 3.0m	Fair	None	Path, Road, Overhead electric cables	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear overhead cables	40+	B1	7560		
T 09-00667	-	Monterey pine, Pinus radiata	21	1330	6	7	7	6	E-2	4	M	2 stems from 2.0m	Fair	None	Overhead electric cables	Crown clean, Clear overhead cables	40+	B1	15960		
T 09-00668	668	Monterey pine, Pinus radiata	14	530	5	6	6	3	E-2	2	M	2 stems from 3.0m	Fair	Excessive deadwood, Forming cavity	Path	Crown clean, Crown lift to 2.4m Over path Or lawn, Reduce end weight by 2.0m	20+	B1	6360		
T 09-00669	669	Sycamore, Acer pseudoplatanus	18	1160	4	6	7	6	S-1	2	M	Spreading crown, Single stem to 8.0m	Fair	Excessive ivy	Path	Crown clean, Remove ivy, Crown lift to 2.4m Over path Or lawn	40+	B1	13920		
T 09-00670	-	Crack willow, Salix fragilis	15	650	4	6	5	4	W-1	2	M	Multi stem from 1.0m, Spreading crown	Fair	Excessive end weight, Excessive ivy	Path, Road, Overhead electric cables	Crown clean, Remove ivy, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Reduce end weight by	20+	B1	7800		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
																2.0m, Clear overhead cables					
T 09-00671	-	Monterey pine, Pinus radiata	20	880	5	6	6	6	W-2	2	M	2 stems from 2.0m	Fair	None	None	No recommendations are given	20+	B1	10560		
G 09-00672	672	Lime, Tilia sp.	9	220	3	3	3	3	-	2	YM	Multi stem from 3.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	2640		
T 09-00673	673	Norway maple, Acer platanoides	8	230	4	3	2	2	E-3	3	YM	Multi stem from 3.0m, Leaning	Fair	None	None	No action is required	40+	B1	2760		
T 09-00674	674	Lime, Tilia sp.	10	250	4	5	4	3	W-3	2	EM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3000		
G 09-00675	675	Lime, Tilia sp.	6	200	3	3	3	3	-	2	YM	Multi stem from 2.0m, Spreading crown	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	2400		
G 09-00676	676	Norway maple, Sycamore, Acer platanoides cv.	9	210	3	3	2	3	-	2	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	2520		
G 09-00677	677	Sycamore, Acer pseudoplatanus	9	200	2	2	2	2	-	2	YM	Single main stem with heavy side branches	Fair	Thinning crown	None	Crown clean	40+	B1	2400		
T 09-00678	678	Ash, Fraxinus excelsior	7	130	2	3	2	1	S-2	2	Y	Multi stem from 2.0m	Fair	None	None	No action is required	20+	C1	1560		
T 09-00679	679	Ash, Fraxinus excelsior	6	100	2	2	2	0	S-2	2	Y	Single stem	Fair	None	None	No action is required	20+	C1	1200		
G 09-00680	680	Turkish hazel, Corylus colurna	11	300	4	4	4	4	-	2	YM	Single main stem with heavy side branches	Good	None	Path	Crown lift to 2.4m Over path Or lawn	40+	A1	3600		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-00681	681	Turkish hazel, Corylus colurna	11	300	3	3	3	3	-	2	YM	Single main stem with heavy side branches	Fair	Thinning crown	None	Crown lift to 2.4m Over path Or lawn, Monitor for death	20+	B1	3600		
G 09-00682	682	Sycamore, Acer pseudoplatanus	8	250	3	4	3	2	W-3	3	YM	Multi stem from 3.0m	Fair	None	Path, None	No action is required	40+	B1	3000		
T 09-00683	683	Sycamore, Acer pseudoplatanus	7	230	4	4	4	4	S-2	2	YM	3 stems from 2.0m, Spreading crown	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2760	Fell for hard surfacing	
T 09-00684	684	Sycamore, Acer pseudoplatanus	9	260	4	5	4	4	S-2	2	YM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3120		
G 09-00685	-	Lime, Tilia sp.	9	300	4	4	3	3	-	1	YM	Single main stem with heavy side branches	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	3600		
T 09-00686	686	Sycamore, Acer pseudoplatanus	9	310	4	4	4	3	N-2	2	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3720		
G 09-00687	687	Gingko, Gingko biloba	6	140	2	2	2	2	-	2	YM	Single stem	Fair	None	None	No action is required	40+	C1	1680	Fell for new road layout	3
G 09-00688	688	Ash, Fraxinus excelsior	6	120	3	3	3	2	-	2	Y	Multi stem from 2.0m	Fair	Thinning crown	Path	Crown clean, Crown lift to 2.4m Over path Or lawn, Monitor for death	10+	C1	1440	Fell in part for road widening	
T 09-00689	689	Ash, Fraxinus excelsior	6	140	2	3	3	2	S-2	2	Y	3 stems from 2.0m	Fair	None	None	No action is required	20+	C1	1680	Fell for road widening	
G 09-00690	-	Norway maple, Acer platanoides	11	320	4	4	4	4	-	2	YM	Single main stem with heavy side branches	Fair	Thinning crown	Path	Crown clean, Crown lift to 2.4m Over path Or lawn	20+	B1	3840		
G 09-00691	-	Birch, Lime, Crack willow, Betula sp.	9	350	5	5	5	5	-	0	YM	Multi stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	4200		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
G 09-00692	692	Sycamore, Acer pseudoplatanus	9	230	3	4	3	4	-	2	YM	Single main stem with heavy side branches, Multi stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2760	Fell for hard surfacing	6
G 09-00693	693	Ash, Fraxinus excelsior	8	160	3	3	2	3	-	2	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	B1	1920	Fell for hard surfacing	6
G 09-00694	694	Sycamore, Acer pseudoplatanus	9	220	3	3	2	3	-	2	YM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2640	Fell for hard surfacing	3
G 09-00695	695	Ash, Birch, Norway maple, Fraxinus sp. cv.	11	250	3	3	3	3	-	2	YM	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn, Thin stems as appropriate	40+	B1	3000		
G 09-00696	696	Birch, Betula sp.	9	130	2	2	2	2	-	2	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	20+	C1	1560		
T 09-00697	697	Lime, Tilia sp.	7	130	2	3	3	2	S-2	2	Y	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1560	Fell for hard surfacing	
G 09-00698	698	Lime, Tilia sp.	6	140	2	3	3	3	-	2	Y	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1680	Fell for hard surfacing	3
G 09-00699	699	Lime, Tilia sp.	6	150	2	2	2	2	-	3	Y	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	1800	Fell for hard surfacing	3
T 09-00700	700	Lime, Tilia sp.	6	140	3	3	2	2	N-3	2	YM	Multi stem from 3.0m	Poor	Thinning crown	Road	Crown lift to 5.1m Over road Or field, Monitor for death	20+	C1	1680	Fell for hard surfacing	
T 09-00701	701	Lime, Tilia sp.	8	160	3	4	3	2	E-2	2	Y	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	B1	1920	Fell for hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00702	702	Lime, Tilia sp.	7	210	3	3	2	2	N-2	2	Y	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	2520	Fell for hard surfacing	
T 09-00703	703	Lime, Tilia sp.	7	200	3	3	3	2	N-2	2	Y	Multi stem from 3.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	2400	Fell	
T 09-00704	704	Lime, Tilia sp.	8	180	4	3	4	2	S-2	2	Y	Single main stem with heavy side branches	Fair	None	Path, Road, Buildings	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field, Clear back from building	40+	B1	2160	Fell	
T 09-00705	705	Lime, Tilia sp.	6	140	3	3	2	2	W-2	2	Y	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1680		
T 09-00706	706	Lime, Tilia sp.	6	130	3	2	3	2	E-2	2	Y	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1560	Fell	
T 09-00707	707	Lime, Tilia sp.	5	120	2	2	2	2	N-2	2	Y	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1440	Fell for hard surfacing	
G 09-00708	708	Lime, Tilia sp.	5	140	2	3	2	2	-	3	Y	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1680	Fell for hard surfacing	3
T 09-00709	709	Lime, Tilia sp.	6	90	2	3	2	2	S-2	2	Y	Single stem	Fair	Thinning crown	Road	Crown lift to 5.1m Over road Or field	20+	C1	1080		
T 09-00710	710	Shag bark maple	7	150	2	3	3	3	S-2	3	YM	2 stems from The ground	Fair	None	None	No action is required	40+	C1	1800	Fell for new road layout	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00711	711	Lime, Tilia sp.	5	120	2	2	3	3	W-2	2	Y	Single main stem with heavy side branches	Fair	Recent crown failure	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1440		
T 09-00712	712	Lime, Tilia sp.	6	100	2	2	2	3	W-2	2	Y	Single main stem with heavy side branches	Fair	Thinning crown	None	Crown clean	20+	C1	1200		
T 09-00713	713	Lime, Tilia sp.	6	110	2	2	2	1	S-2	2	Y	Single stem	Fair	Basal damage	None	No action is required	20+	C1	1320		
T 09-00714	714	Mongolian Lime	5	140	2	2	2	2	S-2	1	Y	Single stem	Good	0	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1680		
T 09-00715	715	Mongolian Lime	5	140	2	2	2	2	E-2	2	Y	Single stem	Good	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1680		
T 09-00716	716	Lime, Tilia sp.	7	120	2	2	1	3	W-2	2	Y	Single main stem with heavy side branches	Fair	Thinning crown	None	No action is required	20+	C1	1440		
T 09-00717	717	Lime, Tilia sp.	0	100	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	<10	U	1200		
T 09-00718	718	Lime, Tilia sp.	0	80	0	0	0	0	-	0	-	0	Dead	Dead	0	Fell	<10	U	960		
T 09-00719	719	Lime, Tilia sp.	8	150	4	3	2	4	E-2	2	Y	Single stem	Fair	None	Buildings	Clear back from building	40+	C1	1800		
T 09-00720	720	Lime, Tilia sp.	6	130	3	2	2	2	S-2	2	Y	Multi stem from 2.0m	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1560		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00721	721	Mongolian Lime	4	140	2	1	1	2	E-2	1	Y	Single stem	Fair	Recent crown failure	Path, Road	Crown lift to 2.4m Over path Or lawn, Tidy branch stumps, Crown lift to 5.1m Over road Or field, Prune to establish single dominant leader	20+	C1	1680		
T 09-00722	722	Mongolian Lime	6	140	2	2	2	2	S-2	2	Y	Single stem	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1680		
T 09-00723	723	Lime, Tilia sp.	8	130	3	2	1	2	E-2	3	Y	Single stem	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	C1	1560		
T 09-00724	724	Lime, Tilia sp.	7	120	3	2	2	2	E-2	2	Y	Single main stem with heavy side branches	Fair	Thinning crown	None	No action is required	20+	C1	1440		
T 09-00725	725	Lime, Tilia sp.	7	150	3	3	3	3	N-2	2	Y	Single main stem with heavy side branches	Fair	None	Path, Buildings	Crown lift to 2.4m Over path Or lawn, Clear back from building	40+	C1	1800		
T 09-00726	726	Mongolian Lime,	5	150	3	2	2	2	E-2	2	Y	Single stem	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1800		
T 09-00727	727	Mongolian Lime,	5	120	2	2	1	2	N-2	1	Y	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	40+	C1	1440		
T 09-00728	728	Norway maple, Acer platanoides	12	220	4	3	2	3	N-3	3	YM	3 stems from 3.0m	Fair	None	None	No action is required	40+	B1	2640	Fell for hard surfacing	
T 09-00729	729	Norway maple, Acer platanoides	13	270	3	4	4	3	W-2	2	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	3240	Fell for hard surfacing	

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00730	730	Alder, Alnus sp.	5	140	2	2	2	2	E-2	1	YM	Single stem	Poor	Excessive deadwood	None	Crown clean, Remove ivy	20+	C1	1680	Fell for hard surfacing	
G 09-00731	731	Ash, Fraxinus excelsior	5	150	3	3	3	3	-	2	Y	Single main stem with heavy side branches	Poor	Excessive deadwood	Road	Crown clean, Remove ivy, Crown lift to 5.1m Over road Or field, Fell dead or dying stems	10+	C1	1800	Fell for hard surfacing	3
T 09-00732	732	Norway maple, Acer platanoides	13	360	5	5	4	3	E-2	2	EM	Multi stem from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	4320	Fell for hard surfacing	
T 09-00733	733	Norway maple, Acer platanoides	13	270	3	4	4	3	E-2	2	YM	2 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3240	Fell for hard surfacing	
T 09-00734	734	Norway maple, Acer platanoides	13	280	4	4	4	3	N-2	2	EM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3360	Fell for hard surfacing	
T 09-00735	735	Norway maple, Acer platanoides	12	310	4	3	4	3	N-2	2	EM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3720	Fell for hard surfacing	
G 09-00736	736	Beech, Italian alder, Fagus sylvatica cv.	13	350	5	5	5	5	-	2	EM	Single stem	Fair	None	Path	Crown lift to 2.4m Over path Or lawn	20+	B1	4200	Fell for hard surfacing	9
T 09-00737	737	Lime, Tilia sp.	5	160	3	2	2	3	W-2	2	Y	Multi stem from 2.0m	Fair	None	Road	No action is required	40+	B1	1920	Fell for hard surfacing	
G 09-00738	738	Norway maple, Acer platanoides	7	250	3	3	3	3	-	2	YM	Single main stem with heavy side branches	Fair	None	Path, Road	Crown clean, Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	3000		
T 09-00739	739	Norway maple, Acer platanoides	7	210	4	3	2	2	E-3	3	YM	2 stems from 3.0m, 3 stems from 2.0m	Fair	Thinning crown	Road	Crown clean, Crown lift to 5.1m Over road Or field	40+	B1	2520		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
T 09-00740	740	Norway maple, Acer platanoides	7	250	3	3	3	3	S-2	3	YM	3 stems from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3000		
T 09-00741	741	Norway maple, Acer platanoides	7	290	4	4	4	4	N-2	3	YM	Single main stem with heavy side branches	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3480		
T 09-00742	742	Norway maple, Acer platanoides	7	220	3	4	3	3	N-3	3	YM	Single main stem with heavy side branches, 3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2640		
G 09-00743	743	Lime, Italian alder, Tilia spp.	6	220	3	3	3	3	-	3	Y	Multi stem from 2.0m, Spreading crown	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	B1	2640		
G 09-00744	744	Norway maple, Acer platanoides	8	280	4	4	4	4	-	2	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	3360		
T 09-00745	745	Norway maple, Acer platanoides	8	230	3	4	3	3	E-2	2	YM	Multi stem from 2.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2760	Fell for new hard surfacing	
T 09-00746	746	Norway maple, Acer platanoides	6	110	2	2	2	2	W-2	2	Y	Single stem	Fair	None	None	No action is required	40+	C1	1320		
T 09-00747	747	Norway maple, Acer platanoides	6	200	3	4	3	3	N-3	2	YM	Multi stem from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	40+	B1	2400		
T 09-00748	748	Norway maple, Acer platanoides	6	220	3	3	3	2	E-3	2	YM	3 stems from 3.0m	Fair	None	Road	Crown lift to 5.1m Over road Or field	20+	B1	2640		
T 09-00749	749	Lime, Tilia sp.	8	260	4	4	4	2	N-3	1	YM	Single main stem with heavy side branches	Fair	None	None	No action is required	40+	B1	3120	Fell for new road layout	
T 09-00750	750	Lime, Tilia sp.	5	140	3	2	1	2	S-2	2	Y	2 stems from 2.0m	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m	40+	C1	1680		

Tree No.	Tag No.	Species	Height (m)	DBH (mm)	Canopy Spread				Lower branch direction and height (m)	Crown Clearance (m)	Age	General Observations					ULE	Category	RPA base radius (mm)	Work Recommendations to facilitate the Proposed Development	No. of trees where known
					N	E	S	W				Crown Form	Condition	Defect	Obstacle	Action					
																Over road Or field					
T 09-00751	751	Lime, Tilia sp.	5	120	3	2	2	3	S-2	2	Y	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn, Crown lift to 5.1m Over road Or field	40+	C1	1440		
T 09-00752	752	Lime, Tilia sp.	7	160	3	2	2	4	W-2	2	Y	Single main stem with heavy side branches	Fair	None	Path, Road	Crown lift to 2.4m Over path Or lawn	40+	B1	1920		

Key to Abbreviations Used in the Survey

Ref No	Specific identification number given to each tree or group. T=Tree/H=Hedge/G=Group/W=Woodland/S=Shrub.	
Tag No	Tree marked with individual tree tag of this reference number on site.	
Species	Common name followed by botanical name shown in *italics*	
RPA	Root Protection Area (As defined by BS5837)	
Stem diameter	Diameter of main stem, measured in millimetres at 1.5 m above ground level. (MS = Multi-stem tree measured in accordance with BS5837 Annexe C)	Av / Average: indicates an average representative measured dimension for the group or feature
Spread	The width and breadth of the crown. Estimated on the four compass points in metres.	
Crown clearance	The estimated height (in metres) above ground level of the lowest significant branch attachments.	
#	Estimated dimensions	
*	Indicates estimated position of tree (not indicated on topographical survey).	
P	Privately owned tree (e.g. tree not located within the road boundary or adjacent public land).	
Category	Categorisation of the quality and benefits of trees on Site as per Table 1 and 2 of BS5837:2012. 1=Arboricultural quality/value 2=Landscape quality/value 3=Cultural quality/value (including conservation)	
	A=High quality/value 40yrs+ (light green). B=Moderate quality/value 20yrs+ (mid blue) C=Low quality/value min 10yrs/stem diameter less than 150mm (grey). U=Unsuitable for retention (dark red).	
Life stage	**Young (Y):** Newly planted tree 0-10 years. **Semi-Mature (SM):** Tree in the first third of its normal life expectancy for the species (significant potential for future growth in size). **Early Mature (EM):** Tree in the second third of its normal life expectancy for the species (some potential for future growth in size) **Mature (M):** Tree in the final third of its normal life expectancy for the species (having typically reached its approximate ultimate size). **Over Mature (OM):** Tree beyond the normal life expectancy for the species. **Veteran (V):** Tree which is of interest biologically, aesthetically or culturally because of its condition, size or age.	
Structural condition	**Good:** No significant structural defects **Fair:** Structural defects which can be resolved via remedial works. **Poor:** Structural defects which cannot be resolved via remedial works. **Dead:** Dead.	
Physiological condition	**Good:** Normal vitality including leaf size, bud growth, density of crown and wound wood development. **Fair:** Lower than normal vitality, reduced bud development, reduced crown density, reduced response to wounds. **Poor:** Low vitality, low development and distribution of buds, discoloured leaves, low crown density, little extension growth for the species. **Dead:** Dead **Fair/Good** = Indicates an intermediate condition **Fair – Good** = Indicates a range of conditions (e.g. within a group)	

Preliminary management recommendations	Works identified during the tree survey as part of sound arboricultural management, based on the current context of the Site (where relevant reference has been made to tree management based on the potential future context of the site).
Works to facilitate the development	Tree works identified as necessary to facilitate the Proposed Development following a desk top analysis of the proposals in relation to tree constraints.

Appendix B Tree Clearance Plans

Greenhills:

- BCID-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SHEET 2

SHEET 1

T 09-00733 T 09-00734 T 09-00735 G 09-00736 G 09-00738 T 09-00739 G 09-00743 T 09-00740 T 09-00741 G 09-00743 T 09-00742 G 09-00744 T 09-00745 T 09-00746 T 09-00747 T 09-00748 T 09-00749 T 09-00750 T 09-00751 T 09-00752

Dublin Baile Átha Cliath

Loftus Hall; Aengus Hall Apts.

Loftus Hall; Hall Apts.

Westend Gate Apts

Car Park

The Square Shopping Centre

BLESSINGTON ROAD

ALDERPARK COURT

Tallagh

INSET

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001	01 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-00712 T 09-00713 T 09-00714 T 09-00715 T 09-00716 T 09-00717 T 09-00718 T 09-00719 T 09-00720 T 09-00721 T 09-00722 T 09-00723 T 09-00724 T 09-00725 T 09-00726 T 09-00727 T 09-00728 T 09-00729 T 09-00730 T 09-00737 T 09-00732 G 09-00731 T 09-00733 T 09-00734 T 09-00735

SHEET 3 SHEET 2 SHEET 2 SHEET 1

Civic Theatre Broadfield Hall Hotel Car Park Car Park Car Park Car Park Car Park

BLESSINGTON ROAD

Barley Glen Block D Barley Glen Block C Barley Glen Block B

Horan Hall; Alen Hall; Virginia Hall; Swan Hall

Loftus Hall; Aengus Hall Apts

Dublin Baile Átha Cliath

VIRGINIA HEIGHTS

409 410 411 412 ES 408 407 406 405 404 403 209 210 211 212 213 214 215 216 208 207 206

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0002	02 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'F' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

SHEET 4
SHEET 3
SHEET 3
SHEET 2

Tallaght General Hospital
Tallaght General Hospital
Cookstown Industrial Estate
COOKSTOWN WAY
Car Park
Library
ES
Civic Theatre
Civic Theatre
LAMB BUS
BUS
DN225
DN300
DN600
LP
G 09-00690
G 09-00692
G 09-00692
G 09-00694
G 09-00694
G 09-00694
G 09-00695
G 09-00696
G 09-00696
G 09-00696
G 09-00698
G 09-00698
G 09-00698
G 09-00699
G 09-00699
G 09-00699
T 09-00697
T 09-00700
T 09-00701
T 09-00702
T 09-00703
T 09-00704*
T 09-00705
T 09-00706
T 09-00707
T 09-00708
T 09-00708
T 09-00708
T 09-00709
T 09-00710*
T 09-00711
T 09-00712
T 09-00713
T 09-00714
T 09-00715

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0003	03 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

SHEET 3

SHEET 4

SHEET 5

Existing tree identified on topographical survey not present on site.

Civic Theatre

Car Park

Car Park

Institute of Technology Tallaght

BELGARD SQUARE NORTH

BELGARD SQUARE EAST

BLESSINGTON ROAD

BLESSINGTON ROAD

ABBERLEY SQUARE NO

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0004	04 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

G 09-00672
G 09-00672
G 09-00672
G 09-00672
T 09-00671
T 09-00670
T 09-00669
T 09-00668
T 09-00667
T 09-00666
T 09-00665
T 09-00664
T 09-00663*
T 09-00662
T 09-00660*
T 09-00659
T 09-00658
T 09-00657
T 09-00661

Existing tree identified on topographical survey not present on site.

SHEET 4
SHEET 5
SHEET 6

BLESSINGTON ROAD
BUS LANE
BUS LANE
BUS LANE
BUS LANE

Graveyard
Saint Maelruain's Church
Burial Ground
Uppercross Court Apts.
Burial Ground
Saint Ma Catholic And Prio
Castle (Site of)
Government Complex
Courthouse
Courthouse Sq. Apts.
Unit 1, Block 7
Unit 2, Block 7
Square Apts.
Credit Union
Car Park
ABBERLEY SQUARE NORTH
ABBERLEY SQUARE EAST
ABBERLEY SQUARE SOUTH
HIGH STREET

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date: 21/03/23 | Scale: 1:500 @ A1, 1:1000 @ A3 | Drawn: C. COUPLAND | Checked: A.DUGGAN | Approved: C.ACTON

Project Code: BCIDA | Originator Code: ACM | QMS Code:

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name: BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0005 | Sheet Number: 05 of 44 | Status: S4 | Rev: L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SHEET 7
SHEET 6
SHEET 5

T 09-00649
T 09-00650
T 09-00651
W 09-00652
T 09-00653
G 09-00654P
T 09-00655
T 09-00656
T 09-00657
T 09-00658
T 09-00659
T 09-00660*
T 09-00661

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

Saint Mary's Catholic Church And Priory
Castle (Site of)
Car Park
Area Under Construction
Greenhills Court Apts.
Church
GREENHILLS ROAD
MAIN ROAD
BANCROFT PARK
BANCROFT AVENUE

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0006	06 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'F' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

T 09-00636 T 09-00637 T 09-00635 T 09-00634 T 09-00633 T 09-00632 T 09-00631 W 09-00639 G 09-00638 G 09-00630 T 09-00644 T 09-00645 T 09-00642 G 09-00643 G 09-00647 G 09-00648 T 09-00650 T 09-00649 H 0900-646 G 09-00641 G 09-00640

LP DN225 DN300 DN200 BUS GREENHILLS ROAD SHEET 6 SHEET 7 SHEET 8 Car Park Saint Mary's National School Playground BANCROFT PARK BANCROFT AVENUE Clubhouse Hills Court Apartments

Approximate construction compound area and location. All existing trees to be retained, RPA extents shown. Site hoarding to be erected around compound. Access points to be positioned away from existing trees.

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM MOTT MACDONALD

Date 21/03/23 | Scale 1:500 @ A1, 1:1000 @ A3 | Drawn C. COUPLAND | Checked A.DUGGAN | Approved C.ACTON

Project Code BCIDA | Originator Code ACM | QMS Code

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name: BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0007 | Sheet Number 07 of 44 | Status S4 | Rev L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-00631 G 09-00630 T 09-00629 H 09-00628 H 09-00623 G 09-00620 T 09-00621 T 09-00622 T 09-00627 T 09-00626 T 09-00624 T 09-00625

DN300 DN225 DN450 LP

GREENHILLS ROAD

CROSSHAVEN

Car Park

NO ENTRY

SHEET 7 SHEET 8 SHEET 9

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0008	08 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

RPA's measured out on site prior to works commencing to inform earthworks and retaining wall structure design

T 09-00613 T 09-00612 G 09-00611 T 09-00607 S 09-00608 T 09-00609 T 09-00610 G 09-00600 G 09-00600 G 09-00600 H 09-00601* T 09-00602 G 09-00603 T 09-00604 G 09-00605 T 09-00606 H 09-00619 T 09-00618 T 09-00617 T 09-00614 T 09-00615 T 09-00616

SHEET 8 SHEET 9 SHEET 10

BROOMHILL ROAD GREENHILLS ROAD MAYBERRY ROAD BIRCHVIEW RISE BIRCHVIEW DRIVE TYMONVILLE COURT

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0009	09 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

SHEET 9

SHEET 10

SHEET 11

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0010	10 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0011	11 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

G 09-00569
W 09-00566
H 09-00556P
S 09-00563
T 09-00557P
S 09-00558P
G 09-00555
G 09-00568
W 09-00567
T 09-00565
T 09-00564
T 09-00562
T 09-00561
T 09-00559
T 09-00560
H 09

M50 NORTHBOUND PARKWAY MOTORWAY
M50 SOUTHBOUND PARKWAY MOTORWAY
GREENHILLS ROAD
BALLYMOUNT ROAD UPPER
Fashion City
Car Park
STOP
LANE BUS
LP
DN300
DN375
DN450
DN600
DN225

SHEET 12
SHEET 13

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0012	12 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

SHEET 12 SHEET 13 SHEET 14 SHEET 15

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0013	13 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

CALMOUNT ROAD

The Exchange

SHEET 14
SHEET 13
SHEET 14
SHEET 16

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0014	14 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'I' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0015	15 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'F' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0016	16 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'F' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titleblox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0017	17 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0018	18 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-00476 T 09-00477 T 09-00475 T 09-00478 T 09-00474 T 09-00480 G 09-00479 T 09-00484 G 09-00483 H 09-00482P* T 09-00481P T 09-00259P H 0900-260P* S 09-00261P G 09-00473 T 09-00472 T 09-00468 T 09-00466 T 09-00465 T 09-00471 T 09-00464

SHEET 18 SHEET 19 SHEET 19 SHEET 20

GREENHILLS ROAD WALKINSTOWN ROAD WALKINSTOWN AVENUE BESSBOROUGH ROAD ST PETERS ROAD CROMWELL'S FORT ROAD

Mulcahy Keane Estate Mulcahy Keane Industrial Estate

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0019	19 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

WALKINSTOWN ROAD

WALKINSTOWN DRIVE

THOMAS MOORE ROAD

HARDEBECK AVENUE

Area Under Const

Walkinstown Car Park

Baile Átha Cliath Dublin

DN225 DN300 DN450 DN375

H 0900-260P*
T 09-00259P
H 09-00256P
T 09-00255P
T 09-00253P
H 09-00251P
T 09-00250P
T 09-00249P
T 09-00246
T 09-00245
T 09-00244
T 09-00243
T 09-00242
T 09-00241
T 09-00239
T 09-00257P
H 09-00258P*
S 09-00254P
H 09-00252P*
T 09-00248P
S 09-00247P
S 09-00261P
G 09-00473
T 09-00472
T 09-00471
T 09-00470
T 09-00469
T 09-00468
T 09-00467
T 09-00466
T 09-00465
T 09-00464
T 09-00463
T 09-00462
T 09-00461
T 09-00460
T 09-00459
T 09-00458

SHEET 19
SHEET 20
SHEET 21

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0020	20 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0021	21 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SLIEVEBLOOM PARK · SLIEVEBLOOM ROAD · BRANDON ROAD · DRIMNAGH ROAD · BALFE ROAD · Clubhouse · Bank · Car Park · NO ENTRY

G 09-00215 · G 09-00214 · G 09-00217 · T 09-00216 · H 09-00212P* · H 09-00210P* · T 09-00213 · T 09-00211P · T 09-00209 · T 09-00208 · T 09-00207 · T 09-00206 · T 09-00205 · T 09-00204 · G 09-00203P* · G 09-0019GP · T 09-00202 · T 09-00201P · T 09-00200P · T 09-00199P · T 09-00198P · T 09-00197 · T 09-0021BP · H 09-0021BP

SHEET 22 SHEET 21 · SHEET 23 SHEET 22

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSI_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 — Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0022	22 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

ERRIGAL ROAD

Car Park

Our Lady's Childrens Hospital

DRIMNAGH ROAD

CRUMLIN ROAD

SAINT MARY'S DRIVE

SAINT MARY'S CRESCENT

SAINT MARY'S PARK

SHEET 22

SHEET 23

SHEET 24

T 09-00196P, T 09-00195, T 09-00192, T 09-00191, T 09-00190P, T 09-00189P, T 09-00194, T 09-00193, T 09-00187P, S 09-00188P, T 09-00186, T 09-00185, T 09-00184, T 09-00183, T 09-00182P, T 09-00181, T 09-00178, T 09-00177, T 09-00175, G 09-00176, T 09-00174, T 09-00173, T 09-00172, T 09-00171, T 09-00180, T 09-00179

DN225

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date: 21/03/23 | Scale: 1:500 @ A1, 1:1000 @ A3 | Drawn: C. COUPLAND | Checked: A.DUGGAN | Approved: C.ACTON

Project Code: BCIDA | Originator Code: ACM | QMS Code:

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name: BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0023 | Sheet Number: 23 of 44 | Status: S4 | Rev: L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

T 09-00151P
T 09-00152
T 09-00153
T 09-00154
T 09-00155
T 09-00156P
T 09-00157P
T 09-00158
T 09-00159
T 09-00160
T 09-00161P
H 09-00162
G 09-00163
G 09-00164
H 09-00165
G 09-00166
G 09-00167
T 09-00168
T 09-00169
T 09-00170
T 09-00171
T 09-00172
T 09-00369
T 09-00371
T 09-00372
T 09-00373
T 09-00374
T 09-00379
T 09-00380

SHEET 23
SHEET 24
SHEET 25
SHEET 38
SHEET 39

RAFTER'S ROAD
SLIEVEMORE ROAD
COOLEY ROAD
CRUMLIN ROAD
CRUMLIN PARK
KILDARE PARK
ST MARY'S ROAD
Our Lady's Childrens Hospital
Car Park

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0024	24 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-00130P
T 09-00131
T 09-00132
T 09-00133
T 09-00134
T 09-00135P
T 09-00136P
H 09-00137P*
T 09-00138P
T 09-00139P
T 09-00140P
T 09-00141P
T 09-00142P
T 09-00143P
T 09-00144P
T 09-00145P
T 09-00146P
T 09-00147P
T 09-00148P
T 09-00149P
T 09-00150P
T 09-00151P
S 09-00156P

SHEET 24
SHEET 25
SHEET 26

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0025	25 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

N

The Iveragh Grounds
Sunshine Industrial Estate
Further Education College
Car Park
Crumlin College
Crumlin College of Further Education
Clubhouse
Bank
CRUMLIN ROAD
OLD COUNTY ROAD
CLONARD ROAD
BANGOR DRIVE
ARDAGH ROAD
BUS LANE
BUS STOP
DN300
DN225
LP
TP
G 09-00122
G 09-00123
H 09-00124P
H 09-00125P*
H 09-00126
H 09-00128P*
H 09-00129P
T 09-00127
SHEET 25
SHEET 26
SHEET 27

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSI_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0026	26 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SHEET 26

SHEET 27

SHEET 28

SHEET 27

T 09-00116
T 09-00117
T 09-00118
T 09-00119
T 09-00120
T 09-00121
T 09-00110
T 09-00112
T 09-00108
T 09-00106
T 09-00102
T 09-00099
T 09-00100
T 09-00101
T 09-00103
T 09-00104
G 09-00115
T 09-00114
T 09-00113
T 09-00111
T 09-00109
T 09-00107
T 09-00105
G 09-00098
H 09-0097P

CRUMLIN ROAD
OLD COUNTY ROAD
KEEPER ROAD
HERBERTON ROAD
Crumlin Shopping Centre
Health Centre
Loreto College

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0027	27 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-0080
T 09-0079
G 09-0077
G 09-0078
T 09-0081
T 09-0082
G 09-0083
S 09-0084P*
T 09-0085P*
H 09-0086P
T 09-0087P
T 09-0088P
T 09-0089P
S 09-0090P*
G 09-0091P*
H 09-0092P
T 09-0096P*
H 09-0097P
G 09-0093P
H 09-0094P*
G 09-0095P
09-0098

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

SHEET 29
SHEET 28
SHEET 28
SHEET 27

HERBERTON DRIVE
DOLPHIN ROAD
CRUMLIN ROAD
RUTLAND AVENUE
PARNELL ROAD
GLENEALY ROAD
SAINT JAMES'S
Dolphin Park
Dolphin Bridge
Avenue Flats
Rutland Avenue Flats
Fire Station
Library
Loreto Junior National School
Loreto Primary School

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0028	28 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SHEET 30
SHEET 29

SHEET 29
SHEET 28

G 09-0067 G 09-0067 G 09-0067 G 09-0067 G 09-0067 G 09-0067 G 09-0067

G 09-0069 G 09-0069 G 09-0069

G 09-0077 G 09-0077 G 09-0077 G 09-0077 G 09-0077 G 09-0077 G 09-0077

T 09-0065 T 09-0066 H 09-0063 T 09-0068 T 09-0070 T 09-0071 T 09-0073 T 09-0074 T 09-0076 T 09-0075 T 09-0072

REUBEN STREET SOUTH CIRCULAR ROAD DOLPHIN HOUSE (FLATS) REILLY'S AVENUE REHOBOTH PLACE REHOBOTH AVENUE SAINT JAMES TERRACE

Ospidéal Ollscoille Bhaile Átha Cliath
Dublin City University
Church of Our Lady of Dolours
Rehoboth Works

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040
Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0029	29 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-0057
T 09-0058
T 09-0059
T 09-0060
T 09-0061
T 09-0062
T 09-0064
H 09-0063
H 09-0063
G 09-0067
G 09-0067
G 09-0067

SHEET 31
SHEET 30
SHEET 30
SHEET 29

AVE MARIA ROAD
ROSARY ROAD
LOURDES ROAD
ST MARGARET'S TCE
MARROWBONE LANE
CORK STREET
DONORE AVENUE
DARLEY'S TERRACE
CAMERON STREET
MAXWELL STREET
EUGENE STREET
FINGAL STREET
EMERALD TERRACE
EMERALD SQUARE
VAUXHALL AVENUE
BOARDMANS LANE
HUXLEY CLOSE
The Barley House Apts.
McGovern's Corner
Eleveden House
Comeron Court Apts.
Saint Teresa's Gardens
Car Park
LAN/BUS
BUS
STOP
DN225
LP

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0030	30 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-0051 T 09-0050 T 09-0052 G 09-0049 T 09-0053 T 09-0048 T 09-0047 T 09-0046 T 09-0045 T 09-0044 G 09-0041 G 09-0054 T 09-0055 T 09-0056 T 09-0058 G 09-0043

SHEET 30 SHEET 31 SHEET 32

CORK STREET BRICKFIELD LANE ORMOND STREET WEAVERS' SQUARE CHAMBER STREET JOHN STREET SOUTH ALLINGHAM STREET MARION VILLAS ROBINSON TERRACE

Brabazon House Apts. Convent Brú Chaoimhín Mount Brown House Abbey House Mount Brown House

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0031	31 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-0039 G 09-0036 G 09-0038 G 09-0041 G 09-0041 G 09-0041 G 09-0038 G 09-0038 S 09-0040 G 09-0042 T 09-0035 T 09-0034 T 09-0033 G 09-0032 G 09-0033

SHEET 31 SHEET 32 SHEET 32 SHEET 33

THE COOMBE JOHN STREET SOUTH IMLICO WATKIN'S BUILDINGS BRABAZON STREET WEAVERS CL COOMBE COURT NEWMARKET STREET HANOVER STREET WEST MARK'S ALLEY TK ROBINSON'S LOCK CORK STREET ARDEE STREET SAINT LUKE'S AVENUE WEAVERS STREET BRABAZON PLACE NEWMARKET CHAMBER STREET NEW ROW SQUARE

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0032	32 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. ¶* INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SHEET 32

SHEET 33

SHEET 34

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0033	33 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

T 09-002
T 09-003
S 09-004
T 09-005
T 09-001
G 09-006
G 09-006
G 09-006
G 09-006
T 09-007
T 09-008
T 09-009
T 09-0010
T 09-0011
T 09-0012
T 09-0013
T 09-0014

SHEET 34
SHEET 33

Disclaimer
a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0034	34 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY PAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0035	35 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

HARTY AVENUE
Harty Court
Court Ufi Artaigh
STANFORD GREEN
HUGHES ROAD SOUTH
BALFE ROAD
BUSKING ROAD
WALLACE ROAD
JOHN MCCORMACK AVENUE
JOHN MCCORMACK
HARTY AVENUE

T 09-00439 T 09-00440 T 09-00435 T 09-00436 T 09-00438 T 09-00437 T 09-00434 T 09-00433 T 09-00432 T 09-00428 T 09-00429 T 09-00431 T 09-00427 T 09-00430 T 09-00426 T 09-00425 T 09-00424 T 09-00423 T 09-00422 T 09-00421 T 09-00419 T 09-00420 T 09-00418 T 09-00415 T 09-00417 T 09-00416 T 09-00414 T 09-00412 T 09-00409 G 09-00413 T 09-00411* G 09-00410

SHEET 35
SHEET 20
SHEET 36
SHEET 37

Approximate construction compound location. All existing tree canopies and RPA extents to be established, retained and fenced as construction exclusion zones. Access points to be positioned away from existing trees.

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0036	36 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

SAINT MARY'S PARK

SAINT MARY'S CRESCENT

SAINT MARY'S DRIVE

T 09-00409 T 09-00408 T 09-00401 T 09-00400 T 09-00399 T 09-00398 T 09-00397 T 09-00396 T 09-00395 T 09-00394 T 09-00393 T 09-00392 T 09-00391 T 09-00389 T 09-00388

T 09-00411* G 09-00410 G 09-00410 T 09-00407 T 09-00406 T 09-00405 T 09-00404 T 09-00403 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00402 G 09-00390

LP

SHEET 36 SHEET 37 SHEET 37 SHEET 38

THE BELFRY

Saint Mary's Church of Ireland

Graveyard

Melville House

SAINT AGNES ROAD

CHERVILLE AVENUE

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0037	37 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0038	38 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSI_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair / National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0039	39 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0040	40 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'F' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA — Údarás Náisiúnta Iompair, National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS**

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1, 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0041	41 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'I' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code	Drawing File Name	Sheet Number	Status	Rev
BCIDA	ACM		BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0042	42 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00~DR-ES-0001 to 0044.dwg



GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.
b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.
c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSI_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.
d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.
e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority

Engineering Designer: AECOM / MOTT MACDONALD

Date	Scale	Drawn	Checked	Approved
21/03/23	1:500 @ A1 1:1000 @ A3	C. COUPLAND	A.DUGGAN	C.ACTON

Project Code	Originator Code	QMS Code
BCIDA	ACM	

Programme Title: **BUSCONNECTS DUBLIN**
CORE BUS CORRIDORS INFRASTRUCTURE WORKS

Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME
GREENHILLS TO CITY CENTRE SECTION
TREE CLEARANCE PLAN

Drawing File Name	Sheet Number	Status	Rev
BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0043	43 of 44	S4	L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\Greenhills\BCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

GENERAL NOTES

1. TREE SURVEY CARRIED OUT BY SUB CONSULTANTS AS DETAILED IN ARBORICULTURAL REPORT.
2. TREE LOCATIONS ARE BASED ON AVAILABLE TOPOGRAPHICAL SURVEY LOCATIONS WITH REFERENCE TO AERIAL IMAGERY AND ON SITE OBSERVATIONS.
3. * INDICATES A TREE / GROUP WHOSE POSITION IS INDICATIVE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
4. 'P' INDICATES A TREE / GROUP IDENTIFIED DURING SURVEY AS BEING WITHIN PRIVATE OWNERSHIP.
5. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT & TREE PROTECTION PLANS.
6. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.

KEY

- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE RETAINED**
- **SURVEYED EXISTING TREE, GROUP OR HEDGE TO BE REMOVED**
- **UNSURVEYED EXISTING TREE FEATURE TO BE RETAINED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **UNSURVEYED EXISTING TREE FEATURE TO BE REMOVED** *(AS BASED UPON TOPOGRAPHICAL SURVEY AND AERIAL IMAGERY)*
- **ROOT PROTECTION AREAS (RPA) OF RETAINED TREES** *(AS DEFINED BY BS 5837:2012)*
- **ROOT PROTECTION AREAS (RPA) OF REMOVED TREES** *(AS DEFINED BY BS 5837:2012)*
- **NO DIG ZONE** *(NEW HARD SURFACING MUST BE ACHIEVED USING A PROPRIETARY RAFT OR TILE SYSTEM INSTALLED USING NO DIG TECHNIQUES AS SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)*

0 5.0 10.0 20.0 30.0 40.0 50.0m

BAR SCALE

Disclaimer

a. © National Transport Authority (NTA) 2022. This drawing is confidential and the copyright in it is owned by NTA. This drawing must not be either loaned, copied or otherwise reproduced in whole or in part or used for any purpose without the prior permission of NTA.

b. This drawing is to be used for the design element identified in the titlebox. Other information shown is to be considered indicative only. The drawing is to be read in conjunction with all other relevant design drawings.

c. O.S. data used for plans are printed under © Ordnance Survey Ireland Government of Ireland. All rights reserved. Licence Number 2022/OSi_NMA_180 National Transport Authority. All elevations are in metres and relate to OSi Geoid Model (OSGM15) Malin Head. All Co-ordinates are in Irish Transverse Mercator Grid (ITM) as defined by OSi active local GPS station.

d. Information concerning the position of apparatus shown on this drawing is based on drawings supplied by the utility owners and/or the utility works contractor, whilst every care has been taken in the preparation of this drawing, positions should be taken as approximate and are intended for general guidance only and no representation is made by the NTA as to the accuracy, completeness, sufficiency or otherwise of this drawing and the position of the apparatus.The information contained herein does not purport to be comprehensive or final as the apparatus is subject to being altered and/or superceded. Recipients should not rely on this information. Any liabilities are hereby expressly disclaimed.

e. The information contained herein has been provided by the NTA but does not purport to be comprehensive or final. Recipients should not rely on the information. Neither the NTA nor any of its directors, officers, employees, agents, stakeholders or advisers make any representation or warranty as to, or accept any liability or responsibility in relation to, the adequacy, accuracy, reasonableness or completeness of the information provided as part of this document or any matter on which the information is based (including but not limited to loss or damage arising as a result of reliance by recipients on the information or any part of it). Any liabilities are hereby expressly disclaimed.

Project Ireland 2040 Building Ireland's Future

Rev	Date	Drn	Chk'd	App'd	Description
L02	21/03/23	CC	AD	CA	UPDATED WITH PROJECT TEAM COMMENTS

Client: NTA Údarás Náisiúnta Iompair National Transport Authority	Engineering Designer: AECOM / MOTT MACDONALD	Programme Title: BUSCONNECTS DUBLIN CORE BUS CORRIDORS INFRASTRUCTURE WORKS	
Date: 21/03/23	Scale: 1:500 @ A1, 1:1000 @ A3	Drawn: C. COUPLAND	Checked: A.DUGGAN / Approved: C.ACTON
Project Code: BCIDA	Originator Code: ACM	QMS Code:	Drawing Title: TALLAGHT/CLONDALKIN TO CITY CENTRE CORE BUS CORRIDOR SCHEME GREENHILLS TO CITY CENTRE SECTION TREE CLEARANCE PLAN
Drawing File Name: BCIDA-ACM-ENV_ZZ-0009_XX_00-DR-LL-0044	Sheet Number: 44 of 44	Status: S4	Rev: L02

DO NOT SCALE USE FIGURED DIMENSIONS ONLY

D:\ARB PROJECTS\Bus Connects - Tree Clearance Plans Offline for PDF\GreenhillsBCIDA-ACM-ENV_LA-0009_XX_00-DR-ES-0001 to 0044.dwg

Appendix C Arboricultural Method Statement

C.1 Arboricultural Method Statement Overview

This Arboricultural Method Statement details the specification for tree protection measures and how sensitive operations are to be achieved in proximity to trees to be retained. It also addresses the general management of Site activities to ensure that retained trees are not inadvertently damaged.

This document may need to be amended to reflect more detailed or updated information as it becomes available. The final agreed version must be read in conjunction with the Tree Protection Plan and copies of both documents must be permanently available on Site for reference throughout the development. All Site personnel must be made fully aware of its contents and the implications for work they may be involved in. All elements of the agreed Method Statement must be adhered to in full. No changes may take place to the content or application of the Method Statement without the prior written approval of the Project Arboriculturist.

When planning permission is in place, some details (including changes in layout, services, materials, tree protection measures and the order of works) may be subject to change. No changes should be enacted without the prior written approval of the Project Arboriculturist. The Method Statement must be reviewed in advance of the commencement.

C.2 Pre commencement site meeting

Prior to the commencement of works on Site a meeting must take place including the Site Manager and Project Arboriculturist. This meeting will allow a further discussion of the programme of works, tree protection measures, the locations of the areas for storage/site organisation and the agreement of
any changes to the Method Statement which will then be formally updated and approved as required.

C.3 Order of operations

1 Pre commencement Site meeting;

2 Preliminary tree works;

3 Site briefing for Site personnel;

4 Installation of protective fencing and ground protection as required;

5 Demolition and enabling works including utility diversions;

6 Re adjustment of protective fencing and ground protection as required;

7 Construction operations ;

8 Re adjustment of protective fencing and ground protection as required;

9 Installation of new hard surfaces and hard landscaping;

10 Site signed off on agreed completion of significant development works;

11 Dismantling of tree protection measures;

12 Soft landscaping works within the Root Protection Area (RPA) of retained trees;

C.4 Preliminary tree works

All approved tree works are to be completed by suitably qualified and insured contractors and must take place before protective fencing is installed and any Site works begin.

All tree works must be carried out in line with the principles of BS3998: 2010 Tree work – recommendations and be conducted in such a way that no damage is caused to any tree to be retained. The tree works contractor must avoid the production of ruts on unmade ground.

A tree works specification which identifies trees to be felled or pruned is included in the schedule in Appendix A.

Due to the extensive nature of the Site and the potential for tree growth in the period between planning and construction, prior to the commencement of works on a given area of the Site a walkover must be undertaken by the Site team including the Project Arboriculturist to determine if any additional tree works are likely to be required to facilitate the development.

If further additional tree works are deemed to be required during the development the advice of the Project Arboriculturist is to be obtained.

Prior to the commencement of any tree works a thorough check for protected species (including nesting birds, bats and badgers) is to be undertaken. If evidence of any protected species is discovered the advice of a suitably qualified ecologist must be obtained. Tree works are to be undertaken outside of the typical nesting bird season (March to September). Outside of this period any individual trees will be inspected for evidence of nesting birds by a suitably qualified person prior to works being carried out.

C.5 Site briefing

The Site Manager is responsible for ensuring that all personnel are made fully aware of the constraints posed by retained trees on Site and the measures in place to ensure they are protected, including having full on-site access to the Arboricultural Method Statement and Tree Protection Plan (TPP). It is good practice for the Project Arboriculturist to be involved in the Site briefing to ensure all constraints and tree protection measures are clearly understood.

C.6 Site monitoring

An auditable system of Site monitoring shall be established to guide contractors on Site, ensure that tree protection measures are implemented and adhered to.

This includes Site visits by the Project Arboriculturist (as appointed by the developer) to confirm the correct installation of protective fencing, to oversee sensitive elements of works within the RPA of retained trees and to sign off the Site when works are complete before fencing can be dismantled.

The frequency of Site monitoring will be agreed in writing before works begin on Site (but is recommended to be at least every four weeks in addition to ad hoc monitoring of particularly sensitive operations near retained trees as required). An example Site monitoring form is included as Appendix D.

C.7 Toolbox Talk

A Toolbox Talk should be provided to Site workers to highlight the need for safe driving of plant and working within the defined corridor to ensure that accidents and resulting potential damage to trees not covered by tree protection measures are eliminated. A copy of the TPP should be used in the process of explaining to all personal the requirements required to ensure retained trees are not damaged and copies of both the TPP and this Method Statement must be available in the Site office at all times.

C.8 Protective fencing

In many areas of the Site the works are contained within the existing road boundary bordered by existing walls or fencing and surrounded by hard surfacing. In such cases no additional tree protection fencing is likely to be required.

Where retained trees are at risk of damage, the default position as set out by BS 5837:2012 is that retained trees must be protected from construction operations with the erection of robust protective fencing positioned on the outer edge of the RPA or crown spread (whichever is greatest).

All Site operations will be restricted to the area outside of tree protection fencing and this area will form a Construction Exclusion Zone (CEZ) unless agreed otherwise. Protection measures will be installed as set out in the Tree Protection Plan.

The area inside the fence and any additional tree protection measures will be sacrosanct and must not be removed or altered without the prior approval of the Project Arboriculturist. Any damage to tree protection measures must be reported immediately.

Default Specification:

Fencing shall be constructed with robust vertical and horizontal scaffold framework with weldmesh panels firmly attached in accordance with BS 5837:2012 Figure 2. Vertical support poles and bracing poles must be located with care to avoid underground utility services and will be sited to avoid the structural roots of retained trees. Where driven supports are not feasible due to the presence of roots or underground utilities block trays, counterweights or equivalent can be utilised.



Figure 3 Default specification for tree protection barrier in accordance with BS5837:2012 figure 2.

Alternative equivalent robust and immovable fencing specification including site hoarding will also be appropriate.

Suitable all-weather signage will be fixed to fencing to notify site staff and visitors of the construction exclusion zone and its purpose.

Failure to fully respect the positioning of barriers and tree protection measures may result in the LPA imposing a temporary stop notice or other enforcement action and is likely to require the use of a more onerous barrier specification and potentially expensive remedial works.

When entering and exiting the Site the fencing contractor must avoid the production of ruts on the unprotected surface of the ground.

Protective fencing and ground protection shall stay in place until all construction operations are completed and removal is agreed with the Project Arboriculturist.

Chestnut Paling stem/limb wrapping:

Where tree stem or the limbs of trees are at risk of damage (e.g. where plant is unavoidably operating within 5m) they will be protected with a double layer of hessian, carpet felt or equivalent cushioning material and a double

layer of chestnut paling fencing or equivalent hardwood batons secured with wire which is to be wrapped around the stem or branch and must not be pinned or attached to the tree itself. Measures must be removed following completion of works.

C.9 Ground protection

Existing hard surfacing will act as fit for purpose ground protection where it is to be retained within the RPA of retained trees. For existing areas of unsurfaced ground within RPAs where construction access is unavoidable ground protection will be required to protect the structure of the soil from compaction. This should also apply to areas for new tree planting.

As set out in section 6.2.3.3 of BS5837:2012 the following ground protection measures will be appropriate:

- Suitable ground protection for pedestrian only access will comprise a single thickness of scaffold boards set on a compressible layer of 100mm of woodchip on a geotextile separation layer.
- Pedestrian operated plant up to two tonnes in weight would require the use of a proprietary ground protection system (such as Ground Guards, Eki mats, Eve Trakway or equivalent) set on a minimum depth of 150mm woodchip or sharp sand.
- Heavier loads will require ground protection to an engineering specification in conjunction with arboricultural advice.

As a guide the threshold beyond which root development is significantly affected is a bulk density ranging from 1.4g per cm^3 for clay soils, to 1.75g per cm^3 for sandy soils.

C.10 Carriageway widening into footways or verges

Where the carriageway is to be widened into the existing footway or verge within the RPA of a retained tree this must be supervised by the Project Arboriculturist. The outer extent of the required excavation (nearest to the tree) should be carefully excavated by hand to allow roots to be assessed and pruned as necessary. Exposed roots must be covered with hessian sacking or equivalent. The existing kerb edging and haunching can then be very carefully removed with an excavator working from the existing carriageway, reaching towards the tree and working backwards, reverting to working using hand tools in areas close to retained tree roots as required.

New edging must have the thinnest profile and extent of haunching possible and pinned alternatives will be applied where feasible. Backfill is to utilise the excavated parent material to replicate the original soil profile.

The subbase for replacement hard surfacing (where required) must be hand tamped only to prevent significant compaction of the underlying soil.

C.11 Footway or verge widening into existing carriageway

Where the footway is to be widened into the existing carriageway, the existing kerb will need to be carefully removed under arboricultural supervision. Kerb stones must be removed using hand tools including pneumatic breakers. Plant positioned on the carriageway can lift out kerb sections using slings. Haunching must be carefully broken out by hand. Any exposed roots must then be covered with soil or hessian to prevent drying out. There will be no constraint on new edging or haunching as it will sit within or above the existing build-up of the carriageway where no roots are present. Backfill must utilise good quality topsoil where the verge is being widened. Where the footway is being widened, the new section of the footway can be constructed using a standard methodology providing the subbase of the existing footway is retained intact and undisturbed.

C.12 Removal and/or replacement of an existing hard surface within an RPA

At the time of writing the full extent of resurfacing has not been fully determined, however there is a potential for extensive areas of resurfacing across the scheme. Where resurfacing is required within the RPA of a retained tree, the following principles will apply:

Replacement hard surfacing on top of existing surface:

Where possible the new hard surface is to be installed on top of the existing surface and the existing edging is to be retained intact.

Removal of existing surface (wearing course):

Before work commences, the Project Arboriculturist will assess the potential for significant roots immediately below the wearing course and in such areas, all works must be achieved by hand. The wearing course must be removed with hand tools (including a handheld pneumatic breaker where required). The existing surface must be 'rolled back' with contractors working from the existing hard surface and with pedestrian only access on the exposed subbase.

With the prior agreement of the Project Arboriculturist, it will be acceptable to use light tracked machinery such as a mini excavator with an untoothed bucket to assist with the removal of the existing surfacing where this can be achieved without damage to any significant roots beneath.

Machinery must work from existing hard surfacing only at all times. Where surface roots are obviously present, and at the junction between hard and soft ground, surfacing is to be removed by hand only.

Restoring hard surfacing to soft ground:

Following the removal of the wearing course, the subbase is to be broken up using hand tools only via pedestrian only access. Materials must be removed using wheelbarrows, or, via hand loading of long reach machinery positioned on adjacent hard surfacing or ground protection. The subbase is to be rolled back. Following removal any low points or hollows are to be filled with sharp sand or gravel, and topsoil be applied to the required level which can then be seeded or turfed as required. This area must then be completely fenced off for the remainder of the development works or be otherwise protected with ground protection.

Installing replacement pedestrian or light vehicular hard surfacing on an existing subbase.

The subbase must be retained intact, ameliorated as required and utilised for the new surface. Levels are to be increased using inert granular fill by a maximum of 100mm. The subbase must be hand tamped only to prevent significant compaction of the underlying soil.

Exposed roots must be treated in accordance with the guidelines in Section C19 of this Method Statement.

Following the removal of existing hard surfacing the unprotected ground within RPAs must be immediately protected with protective fencing and or ground protection (where access is required) as set out in Section C9 to ensure that the structure of the soil and tree roots are protected.

Pedestrian only access onto the exposed and retained subbase will be acceptable to allow the installation of replacement hard surfacing. The new surface should be laid as quickly as possible.

Any exposed roots greater than 25mm in diameter must be assessed by the Project Arboriculturist. If roots which are to be retained are exposed at ground level these should be covered with a thin layer of sharp sand and adjacent levels built up around them. This layer must not be significantly compacted and hand-tamped only.

Installing replacement heavy vehicular hard surfacing on an existing subbase:

The subbase must be retained intact, ameliorated as required and utilised for the new surface. Exposed roots are unlikely to be encountered due to the heavily engineered subbase of the existing surface. Where encountered any roots must be treated in accordance with the guidelines in Section C19 of this Method Statement. The new surface must be rolled out working from the existing subbase only.

Surfacing operations are to be conducted solely from the existing footprint of the road. Access beyond the footprint will be restricted with tree protection barriers as necessary.

Edging:

Existing edging within the RPA of a retained tree will be retained intact and used as the edging for the new surface.

Where the removal of existing edging is unavoidable within an RPA this will be removed carefully by hand under the supervision of the Project Arboriculturist.

Plant positioned outside of the RPA or on existing hard surfacing within the RPA may reach in to assist in lifting edging out of its position using slings but must not be used to excavate around the edging unless otherwise agreed in advance with the Project Arboriculturist.

Where possible new edging must be installed without excavation using pinned alternatives. Where an excavated edge is unavoidable both the edging and any footing must have the narrowest profile possible. Where significant roots are present which cannot be pruned, reinforced sections of kerb acting as lintels to bridge important roots will be applied where possible.

C.13 Installation of new hard surfacing within RPAs

Very small areas of new hard surfacing in the outer RPA of a retained tree can be constructed using hand excavation supervised by the Project Arboriculturist. Due to the very small incursion within an RPA no specialist construction measures will be required. No roots greater than 25mm in diameter will be severed without the consent of the Project Arboriculturist. Where significant roots are encountered the methodology set out below will be applied to avoid root severance. The approach below will apply where any significant area of new surfacing is required within the RPA of a retained tree (as shown on the Tree Protection Plan).

Three-Dimensional Load Bearing Raft:

Construction of the significant areas of new footway or cycleway hard surfacing within the RPA of retained trees shall follow 'no dig' principles. The surface shall be engineer designed to meet the highest expected loads, including those used for the construction of the route.

A proprietary 3D cellular confinement system will be used to allow the hard surface to be installed without excavation within RPAs.

Work will preferably be carried out in dry conditions within the period of May to October when the ground is less liable to compaction.

Existing ground vegetation shall be treated with an approved herbicide such as glyphosate 2-3 weeks before construction takes place. Killed vegetation can then be subject to a maximum 50 mm vegetative scrape which must take place by hand. Any arisings shall be removed (if left in situ they could cause anaerobic conditions as they break down which could be detrimental to tree roots).

Any hollows must be filled with inert granular material such as sharp sand or washed no fines gravel. Builder's sand must not be used as this contains salts which are toxic to tree roots.

Any rocks, stumps (if present) or other protruding objects within the footprint of the load bearing surface must be removed. Stumps must be ground out below ground level. All other objects must be removed by hand.

A robust geotextile membrane must be laid out across the proposed area for the load bearing surface within the RPA. Joints must overlap by approx. 300 mm and be stapled together. This must be capable of resisting puncture by the angular stone fill, and also able to filter pollutants to prevent or reduce contamination of the soil. The load bearing surface is only required within the RPAs.

It is essential to consider the final levels of the load bearing surface which will typically be 75mm-100 mm in thickness for footway or cycleway applications plus the final wearing course (dependent on its application).

The final surface must be resistant to future growth of tree roots and also must be positioned to give a minimum clearance of 500mm from the base of a retained tree. The resulting gap can be filled with inert granular fill if required. A three-dimensional load bearing surface which allows the lateral and horizontal movement of air and water (e.g. Cellweb or equivalent), must be fully expanded and stapled together. This is to be laid on top of the geotextile layer. This surface must be able to support the greatest expected load the surface is likely to experience (including any construction traffic).

The load bearing surface shall be 'rolled out', with construction operations beginning from outside the RPA or from existing hard standing and progressing forwards using the new load bearing surface. The load bearing surface must be filled with 4/20, 20/20 or 20/40 washed angular stone.

Edging is not typically required to stabilise the load bearing surface and the edge of the surface. If edging is required, this must be installed without excavation within RPAs. Appropriate methods would include the use of treated wooden peg and boards.

Concrete kerb stones can be cast directly onto the web if required, however all uncured concrete must be fully contained with impermeable plastic sheeting and sandbags to prevent run off into the RPA of retained trees. The use, storage and mixing of concrete must comply with the provisions set out in section C19.

Where a road edge kerb must be installed by excavation, this must be of the thinnest possible profile, with the minimum extent of haunching feasible and all excavation work must be undertaken by hand with any roots managed under the guidance of the Project Arboriculturist. Alternative kerb construction may be required where significant roots are identified (such as using lintels or equivalent to bridge important roots).

The load bearing surface must have an even transition with adjacent hard surfacing or structures. This must be achieved outside of the RPA of all retained trees. Where this is not possible, structural soil or a mixture of topsoil and sharp sand can be employed to raise levels by up to 100mm. Where levels are to be raised in excess of this height the advice of the Project Arboriculturist must be obtained.

C.14 Demolition

Existing boundary walls, noise barriers, footbridges, lamp columns and other structures are to be demolished within or close to the RPA of retained trees. All demolition must be inward into the existing footprint of the structure or away from tree positions and be achieved by working backwards away from retained trees. No arisings are to fall or be stored in unsurfaced or protected areas of tree RPAs.

All plant and machinery associated with the demolition process will be positioned outside of the RPA of retained trees or on existing hard surfacing or ground protection and must operate under the guidance of a banksman where they must operate within 5m of any part of a retained tree.

Existing footings are to be retained in situ where possible to minimise disturbance. Where removal is unavoidable footings within RPAs must be broken out carefully by hand, or where feasible via the careful use of plant positioned outside of RPAs or on ground protection/existing hard surfacing under the supervision of the Project Arboriculturist.

C.15 Construction of New Boundary Walls

New boundary walls are to be constructed within the RPA of retained trees (such as at the far west of the scheme adjacent to T0013-T0020). Where a new wall cannot avoid an RPA, specialist construction methods must be employed to prevent extensive root severance. Footings must utilise carefully located pads or narrow diameter piles with floating beams (at or above ground level) unless the presence of significant roots has been otherwise discounted following trail excavations under the supervision of the Project Arboriculturist.

Footings must be carefully positioned with hand dug (potentially using compressed air/soil vacuum) trial holes or trenches to identify optimal positioning to avoid significant roots.

Ground protection must be in place where repeated access is required over unsurfaced ground within an RPA.

C.16 Installation of Piles

Where new piles are to be installed within or close to the RPA or retained trees the canopy of the tree is to be pruned back before any construction work commences on Site to provide a clearance of the pile head to facilitate this work. For smaller piles, smaller plant or pedestrian installation only should be applied.

Piling rigs are to be sited outside of the RPA or on ground protection within an RPA and protective fencing is to be installed to maintain an exclusion zone within as much of the RPA as possible.

The piling rig is to be positioned as far from the canopy and RPA of the tree as possible and reach inwards.

Piles will be the lowest diameter feasible. Where piles are to be installed within the RPA of a retained tree an initial trial hole will be excavated by hand to allow for the assessment and management of any exposed roots under the supervision of the Project Arboriculturist. Pile locations will be adjusted to avoid significant tree roots where feasible.

Pile caps within the RPA must be located above the existing ground level to minimise the level of disturbance. Beams must not bear on the existing ground level unless the presence of significant tree roots can be discounted following careful trial excavation.

C.17 Movement of Vehicles and People and the Movement and Operation of Machinery

Due to the spatial constraints on Site, construction works and, in particular, the use of machinery must be carefully co-ordinated to avoid damage to retained trees. A banksman must be in place for any operations which occur within 5m of any part of a retained tree. Long reach machinery with jibs, booms or counterweights will require particular care.

Where trees are at risk of impact damage from plant that cannot be controlled with exclusion fencing or a careful working methodology, consideration must be given to any requirement for access facilitation pruning which must be agreed in advance with the Project Arboriculturist and tree owner (where appropriate).

C.18 Site organisation, storage and mixing of materials

The final locations for temporary Site organisation and compounds will be agreed at the pre commencement Site meeting with the Project Arboriculturist and will be confirmed in writing. Site compounds are proposed at the eight locations shown on the Tree Protection Plan. The area of constraint associated with retained trees within or surrounding compounds will be fenced off as an exclusion zone at the outset.

The storage and mixing of materials and any re-fuelling shall take place at least 5m from the RPA of any retained trees and also take into account any potential for run off. Where this is an issue measures such as bunding with robust impermeable polythene sheeting and sandbags must be put in place to prevent accidental run off reaching the rooting zone of retained trees.

No changes in ground level are permitted within the RPA of a retained tree.

No fires shall take place within an RPA or within 5m of any part of a retained tree. No signs, cables or other items are to be attached to any part of a retained tree.

C.19 General principles for the management of tree roots

Where agreed excavation by hand tools or compressed air takes place within an RPA, the following principles will apply:

- Individual or small groups of roots less than 25 mm in diameter will be retained where possible but can be severed with a sharp tool such as secateurs or pruning saws to leave a clean cut end (ideally 100mm back from the face of the excavation to account for future regrowth) where they pose an obstruction.
- Where roots are encountered which are larger than 25 mm in diameter or where significant groups of smaller roots are found, the advice of the Project Arboriculturist must be sought to decide an appropriate course of action (following consultation with the PA where appropriate).
- Roots must only be exposed for the minimum period possible. In the interim period any exposed roots (including the face of any excavation within an RPA) must be completely covered with dampened hessian sacking (which may require ongoing re wetting) to avoid drying out and exposure to light. Backfill for excavations should ideally utilise the parent material and must not be significantly compacted.

C.20 Installation of new lamp columns, road signs and bus shelters

Where new features such as lamp columns, road signs or bus shelters are to be installed within the RPA of a retained tree, the final position of the feature must be adjusted to give the greatest clearance of adjacent tree stems possible and to reduce any conflict with tree branches or any requirement for pruning.

Footings must be excavated by hand or compressed air (e.g. air spade/soil vacuum) for at least the upper 0.5-1m and be adjusted to avoid significant tree roots. Footings must be the smallest dimensions feasible and utilise screw piles or equivalent where necessary. Any uncured concrete required must use the driest mix feasible and excavations must be lined with an impermeable liner to prevent uncured concrete leaching into the surrounding soil. Any cabling must be installed in accordance with the principles set out in C22.

C.21 Installation of new drainage within RPAs

Drainage has been designed to avoid the RPA of retained trees as fully as possible. Solutions such as surface channels, off set chambers positioned to avoid RPAs as fully as possible and hand excavated sections of piped filter drain positioned to avoid trees roots will be utilised to further reduce impacts on adjacent trees as appropriate. Where excavation for new drainage must take place within an RPA, the method of installation will be agreed in advance with the Project Arboriculturist and will typically involve the nearest area of excavation to the tree being completed by hand or equivalent to allow significant roots to be carefully exposed and pruned. Roots will be managed in accordance with the principles set out in Section C19.

C.22 Installation or diversion of utilities within RPAs

Utility diversion and new utilities have not been fully defined at this stage. The default position is that all services be located outside of the RPA of retained trees. In the context of this Site, it is not feasible to fully avoid the RPA of retained trees and therefore either trenchless installation below tree root systems or hand dug/compressed air excavation through RPAs where significant roots can be retained and worked around will be required.

Use of trenchless techniques:

Where services cannot avoid the RPA of retained trees, the primary consideration must be to install them using trenchless insertion techniques such as impact moling, direct drilling or equivalent.

Insertion and retrieval pits must be located outside of the RPA of retained trees. The depth of the run must be at least 2m below ground level and should be located as far from the tree as possible.

The mole must be lubricated with water only.

Installation must follow the principles set out in the National Joint Utilities Group (NJUG) Vol 4: Guidelines for the planning, installation, and maintenance of utility apparatus in proximity to trees (issue 2) and BS5837 Section 7.7 and Table 3.

Replacement pipes must be installed via pipe bursting, re lining or equivalent trenchless techniques where they are located within the RPA of a retained tree. Pipe bursting or relining equipment must be positioned outside of the RPA at all times.

Hand digging

Where trenchless installation is not feasible, shallow utility runs can be installed under the supervision of the Project Arboriculturist. The excavation will be located as far from the stem of the tree as possible and must be carried out by hand, ideally using compressed air such as an Air Spade and soil vacuum.

Pedestrian only access will be permitted and ground protection measures as set out in Section C9 will be employed where no hard surfacing is in place with fencing positioned immediately adjacent to restrict any further access into RPAs.

Excavation will be supervised by the Project Arboriculturist, who will be on hand to advise on the management of any roots encountered and to ensure the approved tree protection methodology is fully adhered to. Roots smaller than 25mm in diameter can be cut with a clean sharp tool where they pose an obstruction.

Should significant roots (larger than 25mm diameter or large clumps of smaller roots) be encountered, these will be retained and wrapped in dampened hessian to prevent drying out and pipes will be routed around them wherever possible. If significant roots are encountered which cannot be feasibly worked around and retained, the Project Arboriculturist will liaise with the PA to agree appropriate action.

Pipes must be constructed to resist future incursion by tree roots.

All spoil/arisings from excavation will be placed onto ground protection boards to prevent compaction, ground level changes and to assist in removal or reinstatement. Backfill is to utilise the excavated parent material where feasible, applied to restore the soil profile to its original structure (i.e. topsoil will be installed last) and must be lightly hand-tamped only

Services shall be installed following the principles set out in the National Joint Utilities Group (NJUG) Vol 4: Guidelines for the planning, installation, and maintenance of utility apparatus in proximity to trees (issue 2).

C.23 Redundant utilities

Where existing services are to be removed these must be winched out from an access/inspection chamber located outside of an RPA or left in situ.

Redundant pipe work will be sealed off and will not be removed via excavation within the RPA of a retained tree. Redundant pipe work can be filled with an inert material or if confirmed to be fully watertight may be filled with foamed concrete applied from an access point located outside of the RPA of all retained trees. Concrete must be managed in accordance with section C18 of this Method Statement.

C.24 Dismantling of tree protection measures

All protective fencing and ground protection must remain in place until all significant Site works for a given location have been completed and approval has been obtained from the Project Arboriculturist.

Appendix D Site Monitoring Form (Example)

Appointed Project Arboricultural Consultant: Company: Consultant's name: Tel: Mob:	
Development site address:	Planning Authority (PA):
Developer's details: Company: Developer's name: Tel:	

Stage of Development (x)

Pre-construction works		**Construction works**		**Post-construction works**			
Tree works	☐	Demolition	☐	Rectifying tree damage/pruning	☐		
Protective fencing/tape	☐	Grading/muck away	☐	Hard landscaping/walls/drives	☐		
Fencing signage	☐	Placing portacabin	☐	Removal of protective fencing etc	☐		
Ground protection	☐	Excavation/services	☐	Soft landscaping	☐		
Temporary haul road	☐	Construction work	☐	Special surfacing	☐	Tree planting	☐

Comments: